



**LIMITED REMEDIAL INVESTIGATION**

**PIG'S EYE DUMP  
RAMSEY COUNTY, MINNESOTA**

**VOLUME I  
FINAL REPORT**

Prepared for

Minnesota Pollution Control Agency  
520 Lafayette Road North  
St. Paul, Minnesota 55155

|                              |   |                                    |
|------------------------------|---|------------------------------------|
| MPCA Contract Work Order No. | : | M6823                              |
| PRC Project No.              | : | 080-0004                           |
| Date Prepared                | : | November 30, 1994                  |
| Prepared by                  | : | PRC Environmental Management, Inc. |
| PRC Project Manager          | : | Thomas Wiberg                      |
| PRC Telephone No.            | : | (612) 224-1149                     |
| MPCA Project Manager         | : | Doug Beckwith                      |
| MPCA Telephone No.           | : | (612) 296-6300                     |

## CONTENTS

| <u>Section</u>  | <u>Page</u> |
|---|-------------|
| LIST OF SYMBOLS, ACRONYMS, AND ABBREVIATIONS . . . . .  | vii         |
| EXECUTIVE SUMMARY . . . . .   | ES-1        |
| 1.0 INTRODUCTION . . . . .  | 1-1         |
| 1.1 LRI OBJECTIVES . . . . .  | 1-1         |
| 1.2 LRI REPORT ORGANIZATION . . . . .   | 1-2         |
| 2.0 SITE BACKGROUND AND HISTORY . . . . .   | 2-1         |
| 2.1 SITE LOCATION . . . . .   | 2-1         |
| 2.2 SITE LAYOUT . . . . .   | 2-1         |
| 2.3 SITE HISTORY AND RESPONSE ACTIONS . . . . .   | 2-2         |
| 2.4 PREVIOUS INVESTIGATIONS . . . . .   | 2-3         |
| 3.0 LRI ACTIVITIES . . . . .  | 3-1         |
| 3.1 LAND SURVEY . . . . .   | 3-1         |
| 3.2 GEOPHYSICAL SURVEY . . . . .  | 3-1         |
| 3.3 SOIL GAS SURVEY . . . . .   | 3-1         |
| 3.4 GROUNDWATER SAMPLING USING PRC'S GEOPROBE™ . . . . .  | 3-2         |
| 3.5 MONITORING WELL INSTALLATION, GROUNDWATER SAMPLING,<br>AND MONITORING WELL SURVEY AND GROUNDWATER LEVEL<br>MEASUREMENT ACTIVITIES . . . . . | 3-3         |
| 3.5.1 Monitoring Well Installation . . . . .  | 3-3         |
| 3.5.2 Groundwater Sampling . . . . .  | 3-5         |
| 3.5.3 Monitoring Well Survey and Groundwater Level Measurement . . . . .  | 3-5         |
| 3.6 SURFACE WATER SAMPLING AND ELEVATION MEASUREMENTS . . . . .   | 3-6         |
| 3.7 SEDIMENT SAMPLING . . . . .   | 3-6         |
| 3.8 TRENCHING . . . . .   | 3-7         |
| 4.0 PHYSICAL SETTING . . . . .  | 4-1         |
| 4.1 POPULATION AND LAND USE . . . . .   | 4-2         |
| 4.2 PHYSIOGRAPHY . . . . .  | 4-3         |
| 4.3 CLIMATE . . . . .   | 4-3         |
| 4.4 SOIL TYPES . . . . .  | 4-4         |
| 4.5 GEOLOGY . . . . .   | 4-4         |
| 4.5.1 Regional Geology . . . . .  | 4-4         |
| 4.5.2 Site-Specific Geology . . . . .   | 4-6         |

## CONTENTS (Continued)

| <u>Section</u>   | <u>Page</u> |
|--|-------------|
| 4.6 HYDROGEOLOGY . . . . .                                 | 4-8         |
| 4.6.1 Regional Hydrogeology . . . . .                      | 4-9         |
| 4.6.2 Site-Specific Hydrogeology . . . . .                 | 4-10        |
| 5.0 NATURE AND EXTENT OF CONTAMINATION . . . . .           | 5-1         |
| 5.1 SOIL GAS SURVEY RESULTS . . . . .                      | 5-2         |
| 5.2 GEOPROBE™ GROUNDWATER SAMPLING RESULTS . . . . .       | 5-2         |
| 5.2.1 VOC Analytical Results . . . . .                     | 5-3         |
| 5.2.2 SVOC Analytical Results . . . . .                    | 5-4         |
| 5.2.3 Metal Analytical Results . . . . .                   | 5-4         |
| 5.2.4 Pesticide Analytical Results . . . . .               | 5-5         |
| 5.2.5 PCB Analytical Results . . . . .                     | 5-5         |
| 5.3 MONITORING WELL GROUNDWATER SAMPLING RESULTS . . . . . | 5-5         |
| 5.3.1 VOC Analytical Results . . . . .                     | 5-6         |
| 5.3.2 SVOC Analytical Results . . . . .                    | 5-6         |
| 5.3.3 Metal Analytical Results . . . . .                   | 5-7         |
| 5.3.4 Pesticide Analytical Results . . . . .               | 5-7         |
| 5.3.5 PCB Analytical Results . . . . .                     | 5-7         |
| 5.4 SURFACE WATER SAMPLING RESULTS . . . . .               | 5-7         |
| 5.4.1 VOC Analytical Results . . . . .                     | 5-8         |
| 5.4.2 SVOC Analytical Results . . . . .                    | 5-8         |
| 5.4.3 Metal Analytical Results . . . . .                   | 5-8         |
| 5.4.4 Pesticide Analytical Results . . . . .               | 5-9         |
| 5.4.5 PCB Analytical Results . . . . .                     | 5-9         |
| 5.5 SEDIMENT SAMPLING RESULTS . . . . .                    | 5-9         |
| 5.5.1 VOC Analytical Results . . . . .                     | 5-9         |
| 5.5.2 SVOC Analytical Results . . . . .                    | 5-10        |
| 5.5.3 Metal Analytical Results . . . . .                   | 5-10        |
| 5.5.4 Pesticide Analytical Results . . . . .               | 5-10        |
| 5.5.5 PCB Analytical Results . . . . .                     | 5-11        |
| 5.6 TRENCH SOIL SAMPLING RESULTS . . . . .                 | 5-11        |
| 5.6.1 VOC Analytical Results . . . . .                     | 5-11        |
| 5.6.2 SVOC Analytical Results . . . . .                    | 5-12        |

## CONTENTS (Continued)

| <u>Section</u>   | <u>Page</u> |
|--|-------------|
| 5.6.3 Metal Analytical Results . . . . .   | 5-12        |
| 5.6.4 Pesticide Analytical Results . . . . .                                       | 5-12        |
| 5.6.5 PCB Analytical Results . . . . .   | 5-12        |
| 5.7 TRENCHING OBSERVATIONS . . . . .   | 5-13        |
| 5.7.1 Trench T-1 . . . . .   | 5-13        |
| 5.7.2 Trench T-2 . . . . .   | 5-13        |
| 5.7.3 Trench T-3 . . . . .   | 5-13        |
| 5.7.4 Trench T-4 . . . . .   | 5-14        |
| 6.0 CONCLUSIONS AND RECOMMENDATIONS . . . . .                                      | 6-1         |
| 7.0 REFERENCES . . . . .   | 7-1         |
| <u>Appendix</u> [Appendixes are located in Volume II]                              |             |
| A LAND SURVEY REPORT   |             |
| B GEOPHYSICAL SURVEY REPORT  |             |
| C PRC STANDARD OPERATING PROCEDURES  |             |
| D BORING LOGS  |             |
| E MONITORING WELL COMPLETION DIAGRAMS  |             |
| F CONTRACT LABORATORY PROGRAM (CLP) DATA SUMMARY AND DATA                          |             |
| G PRC'S CLOSE SUPPORT LABORATORY (CSL) DATA SUMMARY AND<br>METHOD DETECTION LIMITS |             |

### Attachment

#### OVERSIZE FIGURES

#### FIGURES

| <u>Figure</u>   | <u>Page</u> |
|---|-------------|
| 2-1 SITE LOCATION . . . . .                             | 2-5         |
| 3-1 SOIL GAS SURVEY SAMPLING LOCATIONS . . . . .        | 3-8         |
| 3-2 GEOPROBE™ GROUNDWATER SAMPLING LOCATIONS . . . . .  | 3-9         |
| 3-3 MONITORING WELL AND STREAM GAGE LOCATIONS . . . . . | 3-10        |



## FIGURES (Continued)

| <u>Figure</u>   | <u>Page</u> |
|---|-------------|
| 3-4 SURFACE WATER SAMPLING LOCATIONS . . . . .  | 3-11        |
| 3-5 SEDIMENT SAMPLING LOCATIONS . . . . .   | 3-12        |
| 3-6 TRENCH LOCATIONS . . . . .  | 3-13        |
| 4-1 SITE LOCATION . . . . .   | 4-12        |
| 4-2 GEOMORPHIC REGIONS OF RAMSEY COUNTY . . . . .   | 4-13        |
| 4-3 SOIL MAP OF RAMSEY COUNTY . . . . .   | 4-14        |
| 4-4 STRATIGRAPHIC COLUMN OF SOUTHEASTERN MINNESOTA . . . . .  | 4-15        |
| 4-5 BEDROCK GEOLOGY OF RAMSEY COUNTY . . . . .  | 4-16        |
| 4-6 CROSS SECTION INDEX . . . . .   | 4-17        |
| 4-7 CROSS SECTION A-A' . . . . .  | 4-18        |
| 4-8 CROSS SECTION B-B' . . . . .  | 4-19        |
| 4-9 GROUNDWATER CONTOUR MAP OF UPPER WATER-BEARING UNIT -<br>SEPTEMBER 14, 1994 . . . . .                                     | 4-20        |
| 4-10 GROUNDWATER CONTOUR MAP OF UPPER WATER-BEARING UNIT -<br>OCTOBER 4, 1994 . . . . .                                       | 4-21        |
| 4-11 GROUNDWATER CONTOUR MAP OF UPPER WATER BEARING UNIT -<br>OCTOBER 15, 1994 . . . . .                                      | 4-22        |
| 5-1A CHLORINATED VOC CONCENTRATIONS DETECTED IN SOIL GAS . . .  | Attachment  |
| 5-1B CHLORINATED VOC CONCENTRATIONS DETECTED IN SOIL GAS . . .  | Attachment  |
| 5-2 AROMATIC AND OTHER VOC CONCENTRATIONS DETECTED IN SOIL GAS  | Attachment  |
| 5-3 BENZENE; 1,1-DCE; TOTAL VOC; AND TOTAL VOC TIC CONCENTRATIONS<br>DETECTED IN GEOPROBE™ GROUNDWATER SAMPLES - CLP DATA . . | Attachment  |
| 5-4 BENZENE AND 1,4-DCB CONCENTRATIONS DETECTED IN GEOPROBE™<br>GROUNDWATER SAMPLES - CSL . . . . .                           | Attachment  |
| 5-5 SVOC CONCENTRATIONS DETECTED IN GEOPROBE™ GROUNDWATER<br>SAMPLES . . . . .  | Attachment  |
| 5-6 METAL CONCENTRATIONS DETECTED IN GEOPROBE™ GROUNDWATER<br>SAMPLES . . . . .   | Attachment  |
| 5-7 PESTICIDE CONCENTRATIONS DETECTED IN GEOPROBE™<br>GROUNDWATER SAMPLES . . . . .   | Attachment  |
| 5-8 PCB CONCENTRATIONS DETECTED IN GEOPROBE™ GROUNDWATER<br>SAMPLES . . . . .   | Attachment  |

|      |  |            |
|------|--|------------|
| 5-9  | BENZENE, TOTAL VOC, AND TOTAL VOC TIC CONCENTRATIONS<br>DETECTED IN GROUNDWATER . . . . .                      | Attachment |
| 5-10 | TOTAL SVOC AND TOTAL SVOC TIC CONCENTRATIONS DETECTED IN<br>GROUNDWATER . . . . .                              | Attachment |
| 5-11 | METAL CONCENTRATIONS DETECTED IN GROUNDWATER . . . . .   | Attachment |
| 5-12 | TOTAL VOC, TOTAL SVOC, TOTAL VOC TIC, AND TOTAL SVOC TIC<br>CONCENTRATIONS DETECTED IN SURFACE WATER . . . . . | Attachment |
| 5-13 | METAL CONCENTRATIONS DETECTED IN SURFACE WATER . . . . .   | Attachment |
| 5-14 | TOTAL VOC, TOTAL SVOC, AND TOTAL SVOC TIC CONCENTRATIONS<br>DETECTED IN SEDIMENT . . . . .                     | Attachment |
| 5-15 | TOTAL CHROMIUM AND LEAD CONCENTRATIONS DETECTED IN<br>SEDIMENT . . . . .                                       | Attachment |
| 5-16 | PESTICIDE CONCENTRATIONS DETECTED IN SEDIMENT . . . . .  | Attachment |

## TABLES

| <u>Table</u> | <u>Page</u>  |
|--------------|--|
| 3-1          | SOIL GAS SURVEY SAMPLING DEPTHS . . . . . 3-14                                   |
| 3-2          | GEOPROBE™ GROUNDWATER SAMPLING DEPTHS . . . . . 3-16                             |
| 4-1          | GROUNDWATER ELEVATIONS ON SEPTEMBER 14, 1994 . . . . . 4-23                      |
| 4-2          | GROUNDWATER ELEVATIONS ON OCTOBER 4, 1994 . . . . . 4-24                         |
| 4-3          | GROUNDWATER ELEVATIONS ON OCTOBER 15, 1994 . . . . . 4-25                        |
| 4-4          | SURFACE WATER ELEVATIONS ON OCTOBER 15, 1994 . . . . . 4-26                      |
| 5-1          | CHLORINATED VOC CONCENTRATIONS IN SOIL GAS . . . . . 5-11                        |
| 5-2          | AROMATIC AND OTHER VOC CONCENTRATIONS IN SOIL GAS . . . . . 5-12                 |
| 5-3          | VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CLP<br>DATA . . . . . 5-24 |
| 5-4          | VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CSL<br>DATA . . . . . 5-29 |
| 5-5          | SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES . . . . . 5-31              |
| 5-6          | METAL CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES . . . . . 5-37             |
| 5-7          | PESTICIDE CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES . . . . . 5-41         |
| 5-8          | PCB CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES . . . . . 5-43               |
| 5-9          | VOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL<br>SAMPLES . . . . . 5-44      |

## TABLES (Continued)

| <u>Table</u>  | <u>Page</u> |
|---|-------------|
| 5-10 SVOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL<br>SAMPLES . . . . .        | 5-47        |
| 5-11 METAL CONCENTRATIONS IN GROUNDWATER MONITORING WELL<br>SAMPLES . . . . .       | 5-50        |
| 5-12 VOC CONCENTRATIONS IN SURFACE WATER SAMPLES . . . . .                          | 5-52        |
| 5-13 SVOC CONCENTRATIONS IN SURFACE WATER SAMPLES . . . . .                         | 5-53        |
| 5-14 METAL CONCENTRATIONS IN SURFACE WATER SAMPLES . . . . .                        | 5-54        |
| 5-15 VOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94 . . . . .              | 5-55        |
| 5-16 VOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 9/14/94 . . . . .             | 5-56        |
| 5-17 SVOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94 . . . . .             | 5-57        |
| 5-18 SVOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 09/14/94 . . . . .           | 5-58        |
| 5-19 TOTAL METAL CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED<br>5/5/94 . . . . .   | 5-59        |
| 5-20 TOTAL METAL CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED<br>09/14/94 . . . . . | 5-60        |
| 5-21 PESTICIDE CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94 . . . . .        | 5-61        |
| 5-22 PCB CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 09/14/94 . . . . .            | 5-62        |
| 5-23 VOC CONCENTRATIONS IN TRENCH SOIL SAMPLES . . . . .                            | 5-63        |
| 5-24 SVOC CONCENTRATIONS IN TRENCH SOIL SAMPLES . . . . .                           | 5-64        |
| 5-25 METAL CONCENTRATIONS IN TRENCH SOIL SAMPLES . . . . .                          | 5-65        |
| 5-26 PCB CONCENTRATIONS IN TRENCH SOIL SAMPLES . . . . .                            | 5-66        |

## LIST OF SYMBOLS, ACRONYMS, AND ABBREVIATIONS

|               |   |  |
|---------------|---|--|
| %RSD          | - | Percent relative standard deviation  |
| μg/L          | - | Microgram per liter  |
| AWQC          | - | Ambient Water Quality Criteria   |
| bgs           | - | Below ground surface   |
| BTEX          | - | Benzene, toluene, ethylbenzene, and xylene   |
| CCAL          | - | Continuing calibration   |
| CERCLIS       | - | Comprehensive Environmental Response, Compensation, and Liability Information System |
| CLP           | - | Contract Laboratory Program  |
| CRQL          | - | Contract required quantitation limit   |
| CSL           | - | Close support laboratory   |
| DCA           | - | Dichloroethane   |
| DCB           | - | Dichlorobenzene  |
| DCE           | - | Dichloroethene   |
| ECD           | - | Electron capture detector  |
| Enviroscience | - | Enviroscience, Inc.  |
| EPA           | - | U.S. Environmental Protection Agency   |
| ESI           | - | Expanded site inspection   |
| FID           | - | Flame ionization detector  |
| Fromm         | - | Fromm Applied Technology   |
| GC            | - | Gas chromatograph  |
| GC/MS         | - | Gas chromatography/mass spectroscopy   |
| gpm           | - | Gallon per minute  |
| HRS           | - | Hazard Ranking System  |
| HSA           | - | Headspace Autosampler  |
| Huntingdon    | - | Huntingdon Engineering and Environmental, Inc.                                       |
| ICAL          | - | Initial calibration  |
| ID            | - | Inside diameter  |
| LRI           | - | Limited remedial investigation   |
| MDH           | - | Minnesota Department of Health   |

## LIST OF SYMBOLS, ACRONYMS, AND ABBREVIATIONS (Continued)

|           |   |   |
|-----------|---|---|
| MDL       | - | Method Detection Limit                                      |
| MDNR      | - | Minnesota Department of Natural Resources                   |
| MIBK      | - | Methyl isobutyl ketone                                      |
| mL        | - | Milliliter  |
| MPCA      | - | Minnesota Pollution Control Agency                          |
| MSL       | - | Mean sea level  |
| MS/MSD    | - | Matrix spike/matrix spike duplicate                         |
| MWCC      | - | Metropolitan Waste Control Commission                       |
| NPL       | - | National Priorities List                                    |
| PA        | - | Preliminary assessment                                      |
| PAH       | - | Polynuclear aromatic hydrocarbon                            |
| PCA       | - | Perchloroethane   |
| PCB       | - | Polychlorinated biphenyl                                    |
| PCE       | - | Perchloroethene   |
| PID       | - | Photoionization detector                                    |
| Pig's Eye | - | Pig's Eye Landfill  |
| PLP       | - | Permanent List of Priorities                                |
| ppb       | - | Part per billion  |
| ppm       | - | Part per million  |
| PRC       | - | PRC Environmental Management, Inc.                          |
| PRT       | - | Post-run tubing   |
| QA/QC     | - | Quality assurance and quality control                       |
| QC        | - | Quality control   |
| RAL       | - | Recommended Allowable Limit for Drinking Water Contaminants |
| RCRA      | - | Resource Conservation and Recovery Act                      |
| RPD       | - | Relative percent difference                                 |
| SOG       | - | Standard operating guideline                                |
| SOP       | - | Standard operating procedure                                |
| SSI       | - | Screening site inspection                                   |
| SVOC      | - | Semivolatile organic compound                               |
| TAL       | - | Target analyte list   |

# **LIST OF SYMBOLS, ACRONYMS, AND ABBREVIATIONS (Continued)**

|      |   |  |
|------|---|--|
| TCA  | - | Trichloroethane                            |
| TCE  | - | Trichloroethene                            |
| TCLP | - | Toxicity characteristic leaching procedure |
| TIC  | - | Tentatively identified compound            |
| USCS | - | Unified Soil Classification System         |
| VOC  | - | Volatile organic compound                  |

## EXECUTIVE SUMMARY

PRC Environmental Management, Inc. (PRC), has prepared this draft limited remedial investigation (LRI) report for the Minnesota Pollution Control Agency (MPCA) in partial fulfillment of Work Order No. M-6823 under Multi-Site III Contract No. M-6823. This report documents the LRI conducted at the Pig's Eye dump (Pig's Eye) site in St. Paul, Minnesota. The report was prepared after the completion of the LRI work plan by MPCA, the health and safety plan by PRC, and field work conducted by both MPCA and PRC. The limited nature of the LRI was directed by the MPCA project manager. The LRI does not include evaluations or discussions of contaminant fate and transport or risk assessment.

The Pig's Eye site is an inactive dump located approximately 3 miles southeast of downtown St. Paul in Ramsey County, Minnesota. The site covers about 320 acres and is situated in Sections 3, 4, and 10 of Township 22 North, Range 16 West. The site is bordered to the north and east by the Soo Line railyard and an unnamed access road, to the south by Pig's Eye Lake, and to the west by Pig's Eye Lake Road. The Pig's Eye site is undeveloped except for a small area in the western portion of the site. This area is occupied by the City of St. Paul's wood recycling facility which occupies about 10 to 15 acres and consists of a small one-room building containing an office, equipment for chipping and shredding, and piles of wood.

The remainder of the site consists of wooded and grassy areas. During wet times of the year, standing water is present in the low-lying areas, especially in the middle and southern portions of the site. The northern portion of the site is more heavily wooded. A study of historical aerial photographs shows that areas of the site were composed of wetlands and small lakes before dumping operations took place. Battle Creek enters the site at its eastern boundary, flows west across the site, and then bends to the south and enters Pig's Eye Lake. Small ponds are now present in the southwest and southeast portions of the site.

The Pig's Eye site was operated by the City of St. Paul as a dump from about 1956 until 1972. The dump was closed in 1972 by order of MPCA, mainly as a result of its location in the Mississippi River flood plain. The Pig's Eye dump accepted both municipal and industrial wastes from the City

of St. Paul and surrounding communities. The dump is estimated to have accepted 8.23 million cubic yards of waste material during its 16 years of operation.

From 1977 through 1985, the Metropolitan Waste Control Commission (MWCC) disposed of sewage sludge ash in the southern part of the site under a permit from MPCA. About 236,642 cubic yards of ash was placed on 31 acres of the site. After the ash was placed on site, it was covered with 6 inches of soil cover.

In July 1988, part of the site near the wood recycling facility caught fire. An emergency response contractor for MPCA detected hydrogen cyanide in the smoke plume from this fire. Information from the City of St. Paul indicates that portions of the site also caught fire at other times in the past.

In 1981, the U.S. Environmental Protection Agency (EPA) received a Notification of Hazardous Waste Site form from a local hauler indicating that barrels of solvents and paint sludges were transported to the Pig's Eye site. The Pig's Eye site was then placed on EPA's Comprehensive Environmental Response, Compensation, and Liability Information System (CERCLIS) inventory of potential hazardous waste sites.

In 1983, EPA performed a preliminary assessment (PA) at the site. In December 1988 and January 1989, MPCA staff conducted a screening site inspection (SSI) at the site. After the completion of the SSI, the Pig's Eye site was placed on the State of Minnesota's Permanent List of Priorities (PLP) in December 1989.

Because the data obtained during the SSI documents a release of hazardous substances, MPCA determined that additional data was needed to further assess potential environmental impacts from the site. An expanded site inspection (ESI) was therefore conducted to collect data to develop a more refined Hazard Ranking System (HRS) score and to assess the likelihood of the site to qualify for the National Priorities List (NPL).

On January 31, 1994, MPCA authorized PRC to conduct the LRI, and PRC conducted on-site field and sampling activities from April to October 1994. The field activities were divided into two major



activities: a contaminant source and geophysical investigation; and a geologic and hydrogeologic investigation.

Soil gas and groundwater samples were collected during the contaminant source investigation. Soil gas and groundwater surveys and sampling were conducted to identify sources of contamination. The purpose of the contaminant source investigation was to delineate zones of gross contamination and provide real-time information to help determine the locations of the monitoring wells and trenches installed for the geologic and hydrogeologic investigation. The purpose of the geophysical survey was to identify the extent of fill material at the site.

The geologic and hydrogeologic investigation included installing 12 monitoring wells and 4 stream gages; digging 4 trenches; sampling and analyzing groundwater, sediment, and surface water; surveying monitoring well and stream gages; and measuring groundwater and surface water elevations.

The site-specific geology characterized during the LRI indicates that the Pig's Eye site is underlain by Late Wisconsinan- and Holocene-aged unconsolidated sediments of the modern Mississippi River and the ancient Phalen Channel. Based on observations made during monitoring well installation activities, two shallow water-bearing units may be present. An upper, unconfined unit is present at the interface of the fill material and the organic silt and peat unit. A deeper confined or semiconfined unit may be present in the sand unit below the organic silt and peat unit. Although well nests were not installed during the LRI, it appears that the organic silt and peat unit may act as a local semiconfining or confining unit. Both of these water-bearing units, however, are considered part of the larger unconsolidated valley fill aquifer that fills the buried Phalen Channel. Because the sand unit lies directly over bedrock, the shallow water-bearing units below the site are also in direct hydrogeologic contact with the underlying Prairie du Chien-Jordan Aquifer.

An analysis of groundwater and stream gage elevation measurements for the upper water-bearing unit and surface water bodies indicates that groundwater mounding occurs both northeast and southwest of Battle Creek. Groundwater flows and discharges to the Mississippi River, Battle Creek, and Pig's Eye Lake.

Contaminants detected in groundwater, surface water, and sediment at the Pig's Eye site include volatile organic compounds (VOC), semivolatile organic compounds (SVOC), metals, pesticides, and polychlorinated biphenyls (PCB). The aerial extent of contamination in groundwater, surface water, and sediment occurs in a random fashion with no patterns discernible from the analytical results. This observation is expected because of the types of wastes and management practices at the site.

Results of analytical data for groundwater, surface water, and sediment samples collected at the Pig's Eye site indicate that an impact to the environment has occurred from the Pig's Eye site.

Contaminants have migrated through the upper-water bearing unit to the lower-water bearing unit.

Leachate from the site also discharges to on-site surface water bodies that are hydrologically connected to the Mississippi River. One major source area, an area of abandoned battery casings, has been identified in the southern portion of the site.

Based on the results of the LRI and to further characterize site conditions, PRC recommends the following:

- Additional monitoring wells should be installed in the deeper unconsolidated valley fill deposits underlying the site. If groundwater from these wells also shows contamination, installation of bedrock monitoring wells at the site should be considered.
- Groundwater samples from the monitoring wells should also be analyzed for oxygen, nitrates, and sulfates to determine whether or not natural bioremediation is occurring at the site.
- Monitoring well nests should be installed in the shallow and deeper water-bearing units to determine if the organic silt and peat unit acts as a semiconfining or confining unit at the site.
- Seismic or other nonintrusive geophysical survey methods, such as a gravity survey, should be performed to locate the axis of the buried valley.
- Toxicity Characteristic Leaching Procedure (TCLP) analysis of the ash from the ash disposal area and soil and sediment near the battery casings disposal area should be performed to determine if the materials are Resource Conservation and Recovery Act (RCRA) hazardous wastes. If TCLP analysis indicates that this material is above TCLP limits for RCRA hazardous waste, the soil, battery casings, and ash should either be removed or remediated.

- Invertebrate sampling and additional sediment sampling in Battle Creek and Pig's Eye Lake should be conducted in order to assess potential impact of the site on the food chain in the area.

## **1.0 INTRODUCTION**

PRC Environmental Management, Inc. (PRC), has prepared this limited remedial investigation (LRI) report for the Minnesota Pollution Control Agency (MPCA) in partial fulfillment of Work Order No. M-6823 under Multi-Site III Contract No. M-6823. This report documents the LRI conducted at the Pig's Eye dump (Pig's Eye) site in St. Paul, Minnesota. This report was prepared after the completion of the LRI work plan by MPCA, the health and safety plan by PRC, and field work conducted by both MPCA and PRC. The limited nature of the LRI was directed by the MPCA project manager. The LRI does not include evaluations or discussions of contaminant fate and transport or a risk assessment. This LRI report has been prepared in accordance with the most current U.S. Environmental Protection Agency (EPA) guidance (EPA 1988) as modified from discussions with the MPCA project manager. This section discusses the LRI objectives and the organization of the LRI report.

### **1.1 LRI OBJECTIVES**

The objectives for the LRI as stated in MPCA's work plan and discussed with the MPCA project manager are as follows:

- Evaluate the magnitude and extent of contamination in on-site soil, sediment, groundwater, and surface water
- Evaluate the lateral extent of fill material using geophysical techniques
- Evaluate the presence of volatile organic compounds (VOC) in the soil gas within the fill material
- Characterize the groundwater quality of the uppermost aquifer
- Characterize the water quality of potentially impacted surface water bodies adjacent to the site
- Characterize the sediment in surface water bodies adjacent to the site
- Characterize the composition of the fill material by trenching

## 1.2

### LRI REPORT ORGANIZATION

This LRI report is bound in two volumes. Volume I consists of an executive summary and seven sections including references. Figures and tables for each section are presented at the end of the appropriate section. A short description of each section is provided below.

- The Executive Summary provides a general overview of the information in the LRI report.
- Section 1.0, Introduction, presents the objectives of the LRI and presents the LRI report organization.
- Section 2.0, Site Background and History, discusses the site location, layout, history and response actions, and previous investigations.
- Section 3.0, LRI Activities, describes the field activities conducted during the LRI.
- Section 4.0, Physical Setting, presents information on population and land use, physiography, climate, soil types, and regional and site-specific geology, and regional and site-specific hydrogeology.
- Section 5.0, Nature and Extent of Contamination, discusses sampling results and the types and levels of contaminants detected in the various environmental media sampled.
- Section 6.0, Conclusions and Recommendations, summarizes the data collected during the LRI and presents PRC's recommendations for future site work.
- Section 7.0, References, lists all sources of information cited within the text of this report.

Volume II of the LRI report contains the appendixes. The Volume II appendixes include the following:

- Appendix A, Land Survey Report
- Appendix B, Geophysical Survey Report
- Appendix C, PRC Standard Operating Procedures (SOP)
- Appendix D, Boring Logs
- Appendix E, Monitoring Well Completion Diagrams

- Appendix F, Contract Laboratory Program (CLP) Data Summary and Data
- Appendix G, PRC's Close Support Laboratory (CSL) Data Summary and Method Detection Limits

## **2.0 SITE BACKGROUND AND HISTORY**

Background information about the Pig's Eye site and site history are presented in this section. Background information includes information about the site location and layout. Site history information includes the site history and response actions and summarizes previous investigations conducted at the Pig's Eye site.

### **2.1 SITE LOCATION**

The Pig's Eye site is an inactive dump located approximately 3 miles southeast of downtown St. Paul in Ramsey County, Minnesota. The original, leased property of the dump covers about 320 acres and is situated in Sections 3, 4, and 10 of Township 22 North, Range 16 West. The actual filled area measures approximately 250 acres. The site is bordered to the north and east by the Soo Line rail yard and an unnamed access road, to the south by Pig's Eye Lake, and to the west by Pig's Eye Lake Road. Figure 2-1 shows the Pig's Eye site location.

### **2.2 SITE LAYOUT**

The Pig's Eye site is undeveloped except for a small area in the western portion of the site. This area is occupied by the City of St. Paul's Wood Recycling Facility. This facility covers about 10 to 15 acres and consists of a small one-room building containing an office, equipment for chipping and shredding, piles of wood and wood chips, and stock piled trees.

The remainder of the site consists of wooded and grassy areas. During wet times of the year, standing water is present in the low-lying areas, especially in the middle and southern portions of the site. The northern portion of the site is moderately wooded. A study of historical aerial photographs shows that areas of the site were composed of wetlands and small lakes before dumping operations took place. Battle Creek enters the site at its eastern boundary, flows west across the site, and then bends to the south and enters Pig's Eye Lake. Small ponds are now present in the southwest and southeast portions of the site.

Most of the waste at the site is covered with soil. In some areas, however, waste is not fully covered and protrudes through surface soil. Numerous unpaved roads cross the site. During wet times of the year, many of the roads are passable only with four-wheel drive, off-road vehicles. The Metropolitan Waste Control Commission (MWCC) has installed a sewer line across the site. The site is not fenced; therefore, access to the site is not restricted.

### **2.3 SITE HISTORY AND RESPONSE ACTIONS**

The following discussion pertaining to site history and response actions is based on information obtained from MPCA's screening site inspection (SSI) and expanded site inspection (ESI) reports (MPCA 1989 and 1992).

The Pig's Eye site operated as a dump from about 1956 until 1972. The dump property was owned and operated by the City of St. Paul. Because the dump operated before the inception of MPCA, it was not a permitted landfill. The dump was closed in 1972 by order of MPCA, mainly as a result of its location in the Mississippi River flood plain. The dump accepted both municipal and industrial wastes from the City of St. Paul and surrounding communities. The dump is estimated to have accepted 8.23 million cubic yards of waste material during its 16 years of operation.

From 1977 through 1985, MWCC disposed of sewage sludge ash in the southern part of the site under a permit from MPCA. About 236,642 cubic yards of ash was placed on 31 acres of the site. After the ash was placed on site, it was covered with 6 inches of soil cover.

In July 1988, the site caught fire near the wood recycling facility. The ignition source of this aboveground fire is unknown. An emergency response contractor of MPCA's detected hydrogen cyanide in the smoke plume from this fire. Information from the City of St. Paul indicates that portions of the site also caught fire at other times in the past.



In 1981, EPA received a Notification of Hazardous Waste Site form from a local hauler indicating that barrels of solvents and paint sludges were transported to the Pig's Eye site (EPA 1981). The Pig's Eye site was then placed on EPA's Comprehensive Environmental Response, Compensation, and Liability Information System (CERCLIS) inventory of potential hazardous waste sites.

In 1983, a preliminary assessment (PA) was performed at the site (EPA 1983). In December 1988 and January 1989, MPCA staff conducted an SSI at the site (MPCA 1989). During the SSI, six soil samples, six groundwater samples, two surface water samples, and one residential well sample were collected. Three permanent monitoring wells were also installed (MPCA 1989).

Analysis of the soil samples, which were collected from borings through fill material, revealed lead, mercury, endrin, ketone, and bis (2-ethylhexyl)phthalate at levels of greater than three times those in off-site soil samples. Naphthalene and 2-methylnaphthalene also were detected, but at levels less than CLP contract required quantitation limits (CRQL). Specific concentrations are presented in the SSI report prepared by MPCA (MPCA 1989).

Groundwater samples were collected from three temporary monitoring wells installed in on-site soil borings. Analysis of groundwater samples collected from these wells revealed the following organic compounds at levels greater than CRQLs: methylene chloride; naphthalene; 2-methylnaphthalene; 1,2-dichlorobenzene (DCB); and Arochlor 1016. The following inorganic compounds were also detected at levels greater than CRQLs: cobalt, mercury, vanadium, and cyanide. The samples, however, were noted as being very turbid and potentially not representative of actual groundwater concentrations.

Groundwater samples were also collected from permanent on-site monitoring wells MW-1, MW-2, and MW-3. Analysis of these groundwater samples revealed arsenic, chromium, cyanide, lead, mercury, cobalt, and vanadium at concentrations of greater than three times those from an off-site monitoring well. Analysis of surface water samples did not document an observed release.


After the completion of the SSI, the Pig's Eye site was placed on the State of Minnesota's Permanent List of Priorities (PLP) in December 1989.

Because the data obtained during the SSI documents a release of hazardous substances, MPCA determined that additional data was needed to further assess potential environmental impacts from the site. Therefore, an ESI was conducted to collect data to develop a more refined Hazard Ranking System (HRS) score and to assess the likelihood of the site to qualify for the National Priorities List (NPL) (MPCA 1992). The ESI involved collecting three surface soil samples, nine sediment samples, and nonsampling data.

The three surface soil samples were collected in the area where MWCC disposed of sewage sludge ash. Analysis of the samples revealed cadmium, chromium, copper, lead, nickel, silver, and zinc at levels greater than CRQLs. Specific concentrations are presented in the ESI report prepared by MPCA (MPCA 1992).

Sediment samples were collected during the ESI from Battle Creek and Pig's Eye Lake and at two background locations in Battle Creek upstream from the site. Analysis of the sediment samples from Battle Creek revealed arsenic, beryllium, cadmium, chromium, copper, nickel, and zinc at concentrations greater than those in samples from background locations in Battle Creek. Several organic compounds also were detected in sediment samples from Battle Creek. Chlorobenzene, bis (2-ethylhexyl)phthalate, indeno (1,2,3-cd) pyrene, and chlordane were detected in creek sediment samples but not in background samples. Endrin also was detected in a creek sediment sample at a concentration of greater than three times background.

Analysis of the sediment samples collected from Pig's Eye Lake revealed cadmium, lead, mercury, and zinc at concentrations higher than those in background samples. Several organic compounds including bis (2-ethylhexyl)phthalate, indeno (1,2,3-cd) pyrene, and Arochlor 1254 were detected in the lake sediment samples.



### **3.0 LRI ACTIVITIES**

The following sections describe the LRI activities conducted by PRC as directed by MPCA (MPCA 1994). The LRI activities included a land survey, geophysical survey, soil gas survey and groundwater sampling using PRC's Geoprobe™, monitoring well groundwater and surface water sampling and elevation measurements, sediment sampling, and trenching.

#### **3.1 LAND SURVEY**

PRC subcontracted Enviroscience Inc. (Enviroscience) of Eden Prairie, Minnesota, to conduct a land survey at the Pig's Eye site. The objective of the land survey was to provide a grid on which to conduct the LRI activities listed below. Enviroscience surveyed the grid at the site during the week of March 21, 1994. The grid consisted of surveyed points 180 feet apart in the northwest to southeast direction and 200 feet apart in the southwest to northeast direction. Grid points were marked with wooden stakes and labeled with permanent marker. The survey points were tied into the Minnesota State Plane Coordinate System. The grid was then used to identify geophysical points and soil gas, groundwater, sediment, and surface water sampling locations. Appendix A of the report discusses the land survey in detail.

#### **3.2 GEOPHYSICAL SURVEY**

PRC contracted Fromm Applied Technology (Fromm) of Mequon, Wisconsin, to conduct a geophysical survey of the Pig's Eye site. The objective of the geophysical survey was to identify the extent of fill material at the site. Fromm conducted the geophysical survey the week of March 28, 1994. The specific equipment and methods used by Fromm are presented in Appendix B of this report.

#### **3.3 SOIL GAS SURVEY**

PRC conducted a soil gas survey to locate potential source areas of VOCs in the shallow fill material at the site. The soil gas survey was conducted by PRC during the weeks of April 18 and April 25, 1994. PRC collected soil gas samples at 105 locations at depths of between 3 to 10 feet below

ground surface (bgs) (see Figure 3-1). Because of extremely wet conditions near the north-central portion of the site, soil gas sampling was limited to the northwest, south, and southeast portions of the site. The depth at which individual soil gas samples were collected depended on the depth to groundwater at each specific location.

Soil gas samples were collected using the post-run tubing (PRT) method. This method consists of driving a Geoprobe™ rod to the sampling depth and then withdrawing the rod about 6 inches to dislodge the expendable point. A vacuum is then applied to purge the polyethylene tubing, which extends down to the end of the rod. PRC purged about 2 liters of air through the tubing to ensure that all stagnant air was removed and that the sample was representative of soil gas conditions in the fill material. After purging, PRC collected a soil gas sample in a glass bulb.

A total of 105 samples were collected and analyzed by PRC's CSL for 16 chlorinated VOCs, eight polynuclear aromatic hydrocarbons (PAH), and other VOCs. PRC's CSL also analyzed several types of quality assurance and quality control (QA/QC) samples, including laboratory duplicates and equipment blanks. Sampling depths at each sampling location are presented in Table 3-1. All soil gas sampling procedures were conducted in accordance with PRC SOP No. 054, Using the Geoprobe™ System (see Appendix C). A discussion of soil gas survey results is presented in Section 5.0.

### **3.4 GROUNDWATER SAMPLING USING PRC'S GEOPROBE™**

PRC collected groundwater samples using its Geoprobe™ to obtain information regarding the nature and extent of groundwater contamination beneath the fill material and to help determine the locations of permanent monitoring wells. PRC personnel collected the groundwater samples during the weeks of April 25 and May 2, 1994. PRC collected groundwater samples at 40 locations across the site (see Figure 3-2). Because of extremely wet conditions near the north-central portion of the site, soil gas sampling was limited to the northwest, south, and southeast portions of the site. The groundwater samples were collected at depths of 4 to 18 feet bgs.

To ensure that an adequate water column was available for sampling, PRC drove a slotted, 2-foot long Geoprobe™ rod to a depth at least several feet below the groundwater surface. The groundwater

for the VOC analysis was collected by drawing the groundwater inside the Geoprobe™ rod with flexible polyethylene tubing. The 40-milliliter (mL) sample vials were filled directly from the polyethylene tubing. Groundwater for the remainder of the analyses was collected by attaching a peristaltic pump to the polyethylene tubing inside the Geoprobe™ rod and pumping the groundwater directly from the tubing into the sample containers. After collecting groundwater samples, all geoprobe holes were pressure-grouted with a bentonite slurry to the ground surface.

A total of 52 samples, including six duplicates and three matrix spike/matrix spike duplicate (MS/MSD) pairs, were collected and analyzed by the CLP laboratory for VOCs; semivolatile organic compounds (SVOC); pesticides and polychlorinated biphenyls (PCB); and metals, including cyanide. PRC's CSL also analyzed the groundwater samples for 27 VOCs. Sampling depths at each sampling location are provided in Table 3-2. All groundwater sampling procedures were conducted in accordance with PRC SOP No. 054, Using the Geoprobe™ System (see Appendix C). A discussion of the analytical results for groundwater sampling is presented in Section 5.0.

### **3.5 MONITORING WELL INSTALLATION, GROUNDWATER SAMPLING, AND MONITORING WELL SURVEY AND GROUNDWATER LEVEL MEASUREMENT ACTIVITIES**

The following sections describe the monitoring well installation, groundwater sampling, and monitoring well survey and groundwater level measurement activities conducted during the LRI.

#### **3.5.1 Monitoring Well Installation**

Based on the results of the groundwater sampling using PRC's Geoprobe™, 12 permanent monitoring wells, MW-4 through MW-15, were installed at the site. Ten of the wells were screened at the interface between the fill material and native soil beneath the fill material (shallow monitoring wells), and the other two wells were screened in the sand below the organic silt and peat unit (deep monitoring wells). The location of the monitoring wells is shown in Figure 3-3. The monitoring wells were installed by Huntingdon Engineering & Environmental Inc. (Huntingdon) under subcontract to MPCA during the weeks of August 15 and August 22, 1994.

The 10 shallow monitoring wells (MW-4 through MW-13) were installed using 4.5-inch inside diameter (ID) hollow-stem augers. The two deep monitoring wells (MW-14 and MW-15) were installed using 6.5-inch ID hollow-stem augers. Monitoring wells were numbered at the Pig's Eye site using the already established MPCA monitoring well numbering system. Huntingdon collected continuous split-spoon samples to aid in its preparation of the borings logs, which are presented in Appendix D. These samples were not submitted for chemical analysis. All drilling operations were supervised by a geologist from MPCA or PRC who was responsible for conducting health and safety monitoring, logging samples using the unified soil classification system (USCS), checking split-spoon samples for visual signs of contamination, and screening soil and groundwater samples using a photoionization detector (PID).

The shallow monitoring wells were constructed of 2-inch ID stainless-steel casing with flush joints and stainless-steel screens. Deep monitoring well MW-15 was constructed of 4-inch ID stainless-steel casing with flush joints and a stainless steel screen. Although a 4-inch ID casing and screen were planned for use at MW-14, bedrock was encountered at a shallow depth, and the well was therefore constructed with a 2-inch ID casing and screen.

The slot size of the screens was 0.010 inch (slot size No. 10) for all wells. The 5-foot long screens used for the shallow monitoring wells and MW-14 were manufactured by Johnson Filtration System, Inc. (screen and casing type 304). The screen used for MW-15 was 10 feet long and also manufactured by Johnson Filtration System, Inc. (also screen type 304).

Huntingdon placed silica filter sand (Ottawa sand type 10-20) from the bottom of the screen to approximately 3 feet above the top of the screen. A minimum of 1 foot of bentonite pellets was placed above the silica filter sand. A 1-foot thick concrete seal was placed above the bentonite to the ground surface at all monitoring wells. All wells were completed above grade with locking protective outer casings and concrete pads. Because of the location of the Pig's Eye site within the Mississippi River flood plain, the top of the outer casing of each well was sealed with a water-tight cap below the locking protective cap. Three protective posts were placed around each well. The top of the inner casing of each well was sealed with a water-tight cap. Monitoring well construction details for each well are presented in Appendix E.

Pumping and bailing methods were used to develop all newly installed wells. All monitoring well development was performed by Huntingdon. The monitoring wells were developed until the water discharge became relatively constant for three consecutive measurements of pH, specific conductance, temperature, and turbidity. Most of the shallow monitoring wells were developed by removing 20 to 30 well volumes of water. Development water was disposed of on site and discharged to the ground surface as directed by MPCA.

### **3.5.2 Groundwater Sampling**

After the 12 new monitoring wells were installed, developed, and stabilized, PRC collected groundwater samples from the wells during the week of August 29, 1994. At this time, PRC also collected groundwater samples from two wells, MW-1 and MW-2, which were previously installed at the site by the MPCA. A third well, MW-3, was also previously installed by the MPCA; however, this well was not included in the groundwater sampling at the request of the MPCA. Because all groundwater samples from the new wells were collected within 24 hours of well development and because parameters for discharge stabilization had been met, purging and parameter measurement was not required. The two previously existing wells, however, were purged. All groundwater were samples were collected with disposable bailers in accordance with PRC SOP No. 010, Groundwater Sampling (see Appendix C).

A total of 15 samples, including one duplicate and one MS/MSD pair, were collected and analyzed by the CLP laboratory for VOCs; SVOCs; pesticides and PCBs; and metals, including cyanide. A discussion of the analytical results of groundwater sampling is presented in Section 5.0.

### **3.5.3 Monitoring Well Survey and Groundwater Level Measurement**

To ensure the accurate location of sampling points and the delineation of contaminated areas, each new monitoring well was surveyed to determine its horizontal location, the elevation of the ground surface, and the elevation to the top of the inner well casing. Well locations were surveyed to within 0.1 foot for horizontal location. Elevations of the ground surface and top of the inner casing were surveyed to within 0.01 foot. The survey was completed in September 1994 by Enviroscience. All surveyed locations were tied into the Minnesota State Plane Coordinate System.



PRC and MPCA staff measured the depth to groundwater in each of the monitoring wells on September 14, October 4, and October 15, 1994. The depth to groundwater was measured using an electronic water level indicator. All measurements were made to the top of the inner casing, and the water level indicator was decontaminated before use in each well. The depth to groundwater in each of the wells is presented in Tables 4-1, 4-2, and 4-3.

### **3.6 SURFACE WATER SAMPLING AND ELEVATION MEASUREMENTS**

With the assistance of MPCA technical staff, PRC collected surface water samples to characterize water from Battle Creek, an unnamed ditch on the east side of the site, a pond on the south part of the site, and Pig's Eye Lake. Surface water sample E1600S was collected from the pond on the south end of the site near the battery disposal area. Surface water samples were collected from five locations (see Figure 3-4). PRC and MPCA collected the surface water samples the week of June 6, 1994.

A total of eight samples, including one duplicate and one MS/MSD pair, were collected and analyzed by the CLP laboratory for VOCs; SVOCs; pesticides and PCBs; and metals, including cyanide. All surface water sampling procedures were conducted in accordance with PRC SOP No. 009, Sampling Surface Water (see Appendix C). A discussion of the surface water sampling analytical results is presented in Section 5.0.

PRC and MPCA also installed stream gages at four locations to measure the changes in surface water elevation. Two of the gages were placed in Battle Creek, one gage was placed in Pig's Eye Lake, and one gage was placed in the unnamed ditch on the east side of the site. The locations of the stream gages is presented in Figure 3-3. A discussion of the measurement results is presented in Section 4.0.

### **3.7 SEDIMENT SAMPLING**

With the assistance of MPCA technical staff, PRC collected sediment samples on May 5, 1994 to characterize sediment from Battle Creek, an unnamed ditch on the east side of the site, a pond on the south part of the site, and Pig's Eye Lake. Sediment samples were collected from five locations with

a core sampler (see Figure 3-5). Sediment samples (SED-1 and SED-2) were also collected on September 14, 1994 from the pond located along the southwest edge of the dump site. SED-1 was collected near the northwest edge of the pond and SED-2 was collected near the middle of the pond. Both of these samples were collected using an Ekman grab.

The sediment samples, including two duplicates and two MS/MSD pairs, were analyzed by the CLP laboratory for VOCs; SVOCs; metals, including cyanide; pesticides; and PCBs. All sediment sampling procedures were conducted in accordance with PRC SOP No. 006, Sampling Sludge and Sediment (Appendix C). A discussion of sediment sampling analytical results is presented in Section 5.0.

### **3.8 TRENCHING**

PRC contracted Columbia Building Services, Inc., of Minneapolis, Minnesota, to conduct trenching at the Pig's Eye site. The objective of the trenching was to visually identify the composition of the fill material. On October 12 and 13, 1994, Columbia Building Services, Inc., excavated four trenches, T-1 through T-4, each approximately 30 feet long, 3 feet wide, and 12 feet deep. The locations of the trenches are shown in Figure 3-6. PRC and MPCA personnel oversaw trenching activities. One soil sample was collected from each of trenches T-2 and T-3 and analyzed by the CLP laboratory for VOCs, SVOCs, metals including cyanide, and pesticides and PCBs.




FIG-1117.DWG - 11/23/94 - CER - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994




FIG-1117.DWG - 11/23/94 - GTR - 080-080404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994





FIG-1117.DWG - 11/23/94 - GTR - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994



80-1117.DWG - 11/23/94 - CTR - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994






FIG-1117.DWG - 11/23/94 - GFR - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994




FIG-1117.DWG - 11/23/94 - CTR - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994



**TABLE 3-1**  
**SOIL GAS SURVEY SAMPLING DEPTHS**

| Sample No. | Sampling Depth<br>(feet bgs) |
|------------|------------------------------|
| B-1000N    | 7.0                          |
| B-800N     | 7.0                          |
| B-600N     | 7.5                          |
| B-400N     | 7.5                          |
| B-200N     | 7.0                          |
| B-00       | 7.5                          |
| B-600S     | 7.5                          |
| B-800S     | 6.0                          |
| C-400N     | 7.5                          |
| C-200N     | 7.0                          |
| C-00       | 7.0                          |
| C-400S     | 5.0                          |
| C-600S     | 5.0                          |
| D-3600N    | 5.5                          |
| D-3400N    | 6.0                          |
| D-3200N    | 6.5                          |
| D-3000N    | 5.5                          |
| D-200N     | 7.0                          |
| D-00       | 6.0                          |
| D-200S     | 8.5                          |
| D-400S     | 8.5                          |
| D-600S     | 4.0                          |
| D-800S     | 3.0                          |
| D-1000S    | 4.5                          |
| D-1200S    | 4.0                          |
| D-1400S    | 4.0                          |

| Sample No. | Sampling Depth<br>(feet bgs) |
|------------|------------------------------|
| E-3800N    | 5.5                          |
| E-3000N    | 7.5                          |
| E-2600N    | 6.0                          |
| E-200N     | 7.5                          |
| E-00       | 6.0                          |
| E-200S     | 4.5                          |
| E-400S     | 7.0                          |
| E-600S     | 8.0                          |
| E-1000S    | 4.0                          |
| F-3600N    | 6.5                          |
| F-3200N    | 7.0                          |
| F-3000N    | 6.0                          |
| F-400S     | 7.0                          |
| F-600S     | 7.0                          |
| F-800S     | 6.0                          |
| F-1200S    | NR <sup>a</sup>              |
| G-3400N    | 6.5                          |
| G-3200N    | 5.0                          |
| G-00       | 7.5                          |
| G-200S     | 7.5                          |
| G-400S     | 7.5                          |
| G-600S     | 6.0                          |
| G-800S     | 6.0                          |
| G-1000S    | 6.0                          |
| G-1200S    | 5.5                          |
| G-1400S    | 3.0                          |

**TABLE 3-1 (Continued)**  
**SOIL GAS SURVEY SAMPLING DEPTHS**

| Sample No. | Sampling Depth<br>(feet bgs) |
|------------|------------------------------|
| H-3000N    | 8.0                          |
| H-2600N    | 5.5                          |
| H-2200N    | 8.0                          |
| H-1800N    | 5.5                          |
| H-00       | 7.5                          |
| H-200S     | 7.5                          |
| H-400S     | 7.5                          |
| H-600S     | 7.5                          |
| H-800S     | 7.5                          |
| H-1000S    | 7.5                          |
| H-1200S    | 7.5                          |
| H-1400S    | 4.0                          |
| I-2800N    | NR                           |
| I-2600N    | 7.0                          |
| I-2400N    | 4.0                          |
| I-2000N    | 7.0                          |
| I-1800N    | 7.0                          |
| I-1400N    | NR                           |
| I-1200N    | 6.0                          |
| I-1000N    | 7.5                          |
| I-00       | 6.5                          |
| I-200S     | 7.5                          |
| I-400S     | 7.5                          |
| I-600S     | 7.5                          |
| I-800S     | 7.5                          |
| I-1000S    | 7.5                          |

| Sample No. | Sampling Depth<br>(feet bgs) |
|------------|------------------------------|
| I-1200S    | 7.5                          |
| I-1400S    | 7.0                          |
| J-2200S    | 5.5                          |
| J-2015N    | 5.5                          |
| J-1800N    | 7.0                          |
| J-1400N    | 7.0                          |
| J-1200N    | 9.5                          |
| J-1000N    | 9.0                          |
| J-800N     | 8.0                          |
| J-600S     | 7.0                          |
| J-800S     | 6.0                          |
| J-1000S    | 6.0                          |
| J-1200S    | 5.0                          |
| K-2200N    | 6.0                          |
| K-2000N    | 6.0                          |
| K-1800N    | 7.0                          |
| K-1600N    | 8.0                          |
| K-1400N    | 7.0                          |
| K-1200N    | 7.5                          |
| K-1000N    | 7.5                          |
| K-800N     | 6.0                          |
| L-2000N    | 5.5                          |
| L-1800N    | 7.0                          |
| L-1400N    | 7.0                          |
| L-1200N    | 7.0                          |
| L-1000N    | 5.5                          |
| L-800N     | 5.0                          |

Note:

<sup>a</sup> NR = Not Recorded

**TABLE 3-2**  
**GEOPROBE™ GROUNDWATER SAMPLING DEPTHS**

| Sample No. | Sampling Interval<br>(feet bgs) |
|------------|---------------------------------|
| A-800N     | 4.0 - 6.0                       |
| A-400N     | NR <sup>a</sup>                 |
| B-2600N    | 10.0 - 12.0                     |
| B-1800N    | 10.0 - 12.0                     |
| B-1400N    | 7.0 - 9.0                       |
| B-00       | 10.0 - 12.0                     |
| B-400S     | 10.0 - 12.0                     |
| B-800S     | 7.0 - 9.0                       |
| B-1200S    | 9.5 - 11.5                      |
| B-1600S    | 9.5 - 11.5                      |
| B-2000S    | NR                              |
| C-2200N    | 10.0 - 12.0                     |
| C-800N     | 13.0 - 15.0                     |
| C-400N     | 12.5 - 14.5                     |
| D-3600N    | 11.0 - 13.0                     |
| D-3000N    | 16.0 - 18.0                     |
| D-1400N    | 16.0 - 18.0                     |
| D-1600S    | 6.5 - 8.5                       |
| E-2600N    | 16.0 - 18.0                     |
| E-600N     | 7.0 - 9.0                       |

| Sample No. | Sampling Interval<br>(feet bgs) |
|------------|---------------------------------|
| E-00       | 13.0 - 15.0                     |
| E-600S     | 7.0 - 9.0                       |
| E-1200S    | 7.5 - 9.5                       |
| F-3600N    | 9.5 - 11.5                      |
| F-3000N    | 12.5 - 14.5                     |
| F-2200N    | 12.5 - 14.5                     |
| F-1600N    | 13.0 - 15.0                     |
| F-1000N    | 8.0 - 10.0                      |
| F-1600S    | 6.5 - 8.5                       |
| H-2800N    | 11.0 - 13.0                     |
| H-600N     | 5.0 - 7.0                       |
| H-1600S    | 6.5 - 8.5                       |
| I-1200N    | 11.5 - 13.5                     |
| I-00       | 8.0 - 10.5                      |
| J-800N     | 7.0 - 9.0                       |
| J-600S     | 10.5 - 12.5                     |
| J-1400S    | 6.5 - 8.5                       |
| J-2400N    | 15.5-17.5                       |
| K-1600N    | 14.0 - 16.0                     |
| L-1200N    | 9.0 - 11.0                      |

Note:

<sup>a</sup> NR = Not Recorded

## **4.0 PHYSICAL SETTING**

This section presents local and regional information about the physical setting of the Pig's Eye site from published literature and the results of field investigation activities conducted during the LRI. The following physical characteristics were assessed to evaluate current site conditions and to assist in the determination of the need for additional remedial investigation activities:

- Population and land use
- Physiography
- Climate
- Soil types
- Geology
- Hydrogeology

The sections below contain detailed discussions of the results of the LRI study.

### **4.1 POPULATION AND LAND USE**

The Pig's Eye site is located 3 miles southeast of downtown St. Paul in Ramsey County, Minnesota (see Figure 4-1). The site is mostly vacant land bordered by industrial property to the north and west. The nearest residential area is east of the site on the bluffs overlooking the Mississippi River valley. Railroad facilities and tracks owned by Soo Line and Canadian Pacific are located north and east of the site, and Burlington Northern railroad facilities and tracks and numerous industrial facilities are located west of the site along the Mississippi River. A wood recycling facility owned by the City of St. Paul is located in the southwest portion of the site. Pig's Eye Lake borders the southern end of the site.

The Pig's Eye site is part of a diverse ecological system. The site is located within the boundaries of the Mississippi National River and Recreation Area and within habitats of the bald eagle and peregrine falcon. A heron rookery managed by the Minnesota Department of Natural Resources (MDNR) is located along the western shore of Pig's Eye Lake south of the site. Pig's Eye Lake recreational park is located south of the site. The population density of Ramsey County is estimated

at 3,117.9 people per square mile (Bureau of Census 1990). About 40,000 people are located within a 4-mile radius of the Pig's Eye site (MPCA 1989).

## **4.2                    PHYSIOGRAPHY**

The Pig's Eye site is located within the Mississippi Bottomland geomorphic region of the Mississippi River lowland (Patterson 1992; see Figure 4-2). This geomorphic region is typically flat and resulted from postglacial deposition of slackwater sediments in flood plains of the Mississippi River.

The Mississippi River is located about 0.5 mile west of the Pig's Eye site. Most of the Pig's Eye site lies within the 50-year flood plain of the Mississippi River, and the southeastern portion of the site lies within the 10-year flood plain. The 50-year and 10-year flood plain elevations are at 704 and 699 feet above mean sea level (MSL), respectively. The elevation of the Pig's Eye site ranges from 687 to about 705 feet above MSL. The slope between the site and the Mississippi River is less than 1 percent in all directions.

Several perennial surface water bodies are present throughout the site. Battle Creek flows generally north to south through the site and empties into Pig's Eye Lake. As a result of dumping, the original course of Battle Creek was altered to its present course. An unnamed pond is present in the southwestern portion of the site, and an unnamed drainage ditch parallels the eastern boundary of the site next to Soo Line railroad property. This drainage ditch empties into Pig's Eye Lake from the east. Pig's Eye Lake itself borders the site to the south. Numerous other small water bodies with areas of typically less than 1 acre are also located on site.

## **4.3                    CLIMATE**

The information in this section was derived from the *Soil Survey of Washington and Ramsey Counties, Minnesota* (USDA 1980). In the Minneapolis and St. Paul area, winters are cold, and the summers tend to be short and warm. The prevailing wind direction is from the northwest. The average wind speed is 12 miles per hour and is highest in April. The percentage of sunshine is 67 percent in the summer and 50 percent in the winter.

The average temperature in winter is 17 °F, and the average daily minimum temperature is 8 °F. The average summer temperature is 70 °F, and the average daily maximum temperature is 80 °F. Temperature extremes range from 97 °F to -35 °F.

Precipitation is distributed relatively evenly throughout the year and peaks in the summer months. The average total annual precipitation is 29 inches, 71 percent of which falls from April through September. Snow covers the ground from late fall through early spring. The average seasonal snowfall is 46 inches. Soils typically freeze to a depth of 1 to several feet bgs, depending on the amount of snow cover.

#### **4.4 SOIL TYPES**

The information in this section was derived from the *Soil Survey of Washington and Ramsey Counties, Minnesota* (USDA 1980). Soils in the vicinity of the Pig's Eye site consist mainly of the Udorthent, wet substratum-Algansee complex. Figure 4-3 represents the soil types present in Ramsey County. The Udorthent, wet substratum soils are nearly level to very gently sloping. The texture and composition of the soils vary but generally reflect the characteristics of nearby soils. Much of the soil is mixed with fill material at the Pig's Eye site and with other material dredged from the Mississippi River.

Algansee soils are poorly drained, nearly level, coarse textured soils. The surface layer is usually dark loamy sand underlain by mottled sands, indicating sluggish water movement. The Udorthent, wet substratum-Algansee complex soils have slopes from 0 to 4 percent. These soils are also highly susceptible to flooding and have a high seasonal water table.

#### **4.5 GEOLOGY**

Regional geologic data were obtained from published maps and reports. Site-specific stratigraphic and hydrogeologic data were obtained from detailed geologic logs of monitoring well borings. Regional and site-specific geology are discussed below.

#### 4.5.1

#### Regional Geology

Most of the Minneapolis and St. Paul area is covered with unconsolidated glacial deposits directly overlying bedrock. The glacial deposits generally consist of those deposited directly by an active ice mass and those deposited by melt water discharging from the ice mass. Glacial debris deposited directly at or under the active ice margin is broadly referred to as "till," an unsorted mixture of clay, silt, sand, and gravel. Material deposited by flowing melt water discharging from the ice mass is referred to as "outwash" and consists of sorted and stratified sand and gravel. Other englacial and proglacial deposits such as lake deposits, eskers, and debris flows are also common. The unconsolidated glacial material in the Minneapolis and St. Paul area ranges in thickness from 0 to about 400 feet depending on the depth to the eroded bedrock surface.

Bedrock that underlies the unconsolidated deposits in the Minneapolis and St. Paul area is comprised of Paleozoic Era strata of the Late Cambrian and Early to Middle Ordovician ages. Figure 4-4 represents a stratigraphic column of southeastern Minnesota.

Bedrock underlying the glacial deposits in the Minneapolis and St. Paul area, from the oldest to youngest, is composed of the Late Cambrian age St. Lawrence Formation; the Late Cambrian age Jordan Sandstone; the Early Ordovician age Prairie du Chien Group; the Middle Ordovician age St. Peter Sandstone; the Middle Ordovician age Glenwood and Platteville Formations; and the Middle Ordovician age Decorah Shale. Older strata, such as the St. Lawrence Formation and Jordan Sandstone, subcrop beneath buried valleys where erosion has removed younger strata. The bedrock geology of Ramsey County is presented in Figure 4-5.

Jordan Sandstone ranges from fine-grained, feldspathic sandstone in its lower portion to medium- to coarse-grained quartz sandstone in its upper portion. It is underlain by the St. Lawrence Formation, a dolomitic shale and siltstone, and has a sharp upper contact with the overlying Prairie du Chien Group. The Jordan Sandstone does not outcrop in the Minneapolis and St. Paul area, but it does subcrop beneath Quaternary Period deposits, particularly in some of the deeper buried valleys. The Jordan Sandstone has an maximum thickness of 115 feet in the Minneapolis and St. Paul area (Mossler 1987).

The Prairie du Chien Group consists of medium to massive bedded dolostone at its base and grades upward into a thinbedded, sandy and oolitic dolostone. Thin beds of sandstone and chert are also common in its upper portion. No outcrops of the Prairie du Chien Group are present in the region, but it is the first bedrock unit encountered beneath Quaternary Period deposits over much of the Minneapolis and St. Paul area. The Prairie du Chien Group is 100 to 300 feet thick (Mossler 1987).

The St. Peter Sandstone is massive, fine- to medium-grained, well rounded, well sorted quartz sandstone. Mudstone and siltstone beds, some of which are laterally extensive across the region and can be identified through geophysical logs, are present at the base of the St. Peter Sandstone. The basal contact with the Prairie du Chien Group is a regionally extensive unconformity. The St. Peter Sandstone crops out in bluffs along the Mississippi River and other dissected river valleys in the region. The St. Peter Sandstone averages 155 feet thick in the Minneapolis and St. Paul area (Mossler 1987).

The Glenwood Formation is brownish gray, calcareous, sandy, phosphatic shale with a characteristic blocky fracture pattern. Phosphate nodules are as large as 1 inch in diameter. The Glenwood Formation has a maximum thickness in the Minneapolis and St. Paul area of 16 feet. (Mossler 1987)

The Platteville Formation is generally gray, thin-bedded, dolostone and dolomitic limestone with thin shale and sandstone interbeds. The contact with the underlying Glenwood Formation is a well defined, sharp contact with carbonate overlying shale. The maximum thickness of the Platteville Formation in the Minneapolis and St. Paul area is about 30 feet (Mossler 1987).

Decorah Shale is typically grayish green, fossiliferous shale with thin limestone interbeds. Its underlying contact with the Platteville Formation is gradational. The Decorah Shale attains a maximum thickness of 80 feet in the Minneapolis and St. Paul area (Mossler 1987).

#### **4.5.2 Site-Specific Geology**

The Pig's Eye site is underlain by 30 to more than 200 feet of Late Wisconsinan- to Holocene-aged unconsolidated deposits. These deposits consist mostly of melt water sands and gravel that filled the Phalen Channel, the precursor to the modern Mississippi River (Mossler and Cleland 1992). As the



glaciers began their final retreat from the Minneapolis and St. Paul area, the Phalen Channel was eroded to great depths and formed the major drainage pathway for meltwater. As the ice mass continued its retreat northwest, the Phalen Channel was eventually cut off by the modern Mississippi River channel (Mossler and Cleland 1992). This new channel flowed on the west side of the bedrock high, on which MWCC's wastewater treatment facility is now located. The western part of the Pig's Eye site lies east of this bedrock high in the center of the buried Phalen Channel. After avulsion of the old Phalen Channel, the Pig's Eye site became a backwater slough of the Mississippi River and filled up with slackwater sediments and organic deposits.

The upper part of these sediments consists of recent deposits of sands, silts, clays, and organic material. According to bedrock maps of the region, bedrock underlying the central portion of Pig's Eye site is Jordan Sandstone (Mossler and Bloomgren 1992). Based on detailed descriptions of the unconsolidated sediments and bedrock encountered during field activities, the following units, from highest to lowest, have been defined at the Pig's Eye site:

- Fill material consisting of thin to absent soil cover and dump debris
- Organic silt and peat consisting of dark brown to black, clayey silt with a high content of organic matter
- Sand consisting of moist to saturated, light to dark gray, fine- to very coarse-grained sand with silty and clayey layers
- Bedrock consisting of gray and red, brecciated, sandy dolomite with vuggy porosity

The vertical and lateral stratigraphic relationships of these units are shown in the cross sections indexed by Figure 4-6. The generalized cross sections themselves are shown in Figures 4-7 and 4-8. These cross sections were constructed from site specific boring logs, which are presented in Appendix D. Information on actual subsurface conditions is available only at specific soil boring locations.

The lowermost unit encountered at the site is the upper weathered portion of the Prairie du Chien Group. Deeper in the buried Phalen Channel under the western part of the site, the Prairie du Chien Group has probably been removed, and Jordan Sandstone is most likely subcropping beneath the glacial deposits. The only monitoring well at which bedrock was encountered is monitoring well

MW-14. Here, the Prairie du Chien Group was encountered at 27 feet bgs. Fragments of bedrock collected in a split-spoon sample indicate a red, brecciated, sandy dolomite with abundant vuggy porosity. At monitoring well MW-15, bedrock was not encountered, indicating that the deeper part of the buried Phalen Channel may be under monitoring well MW-15. The boring for monitoring well MW-15 was ended at 52 feet bgs. According to geologic maps of Ramsey County, bedrock underlying the deeper parts of the channel probably consists of Jordan Sandstone (Mossler and Bloomgren 1992).

The unconsolidated sand unit directly overlies the bedrock and ranges from 5 to possibly more than 200 feet in thickness according to bedrock topographic maps of the region (Mossler 1992). It is a gray, moderately sorted, subangular to subrounded, fine- to very coarse-grained sand unit. In deep monitoring well MW-15, three fining-upward sequences were identified within the sand unit. Three clayey layers between 2 and 8 inches thick, are intercalated within the sand units at the tops of the fining-upward sequences. The clay layers contain organic material and probably represent lacustrine deposition during damming of the Phalen Channel. The clay layers are probably laterally extensive within the buried valley and most likely pinch out toward the valley walls. The sand unit also contains gastropod shells and small clam shells.

The organic silt and peat unit directly overlies the sand unit and varies in thickness across the site. It appears to be absent in much of the northwest portion of the site and is present in all monitoring well boreholes southeast of Battle Creek. The unit is dry to moist and has a thickness of 2 to 20 feet, with a maximum thickness in the vicinity of monitoring well MW-14.

Fill material varies from approximately 5 to 15 feet in thickness and consists of construction debris and mixed household and industrial wastes. Plastic, cellophane, paper, and metal products were abundant in much of the well cuttings and trenching debris. Visual observation of the fill material indicated little or no degradation.

## 4.6

## HYDROGEOLOGY

Regional and site-specific hydrogeology information pertinent to the Pig's Eye site LRI are presented in the sections below.

### 4.6.1

### Regional Hydrogeology

Major sources of groundwater in the Minneapolis and St. Paul area include the Mt. Simon Aquifer, the Prairie du Chien-Jordan Aquifer, and thick sequences of unconsolidated sand and gravel in the buried valleys. The St. Peter Aquifer and the Franconia-Ironton-Galesville Aquifer are also sources of groundwater in the area. The principal source of groundwater in the region is the Prairie du Chien-Jordan Aquifer. About 210 residential wells are located within a 3-mile radius of the Pig's Eye site (MPCA 1989). Some of the municipal water supplies, however, use the Mississippi River as a source of drinking water.

The Mt. Simon Aquifer underlies all of Ramsey County. Limited groundwater elevation data show that the groundwater movement of the Mt. Simon Aquifer differs from that of overlying aquifers. The Mt. Simon Aquifer appears to flow east to west toward heavy pumping areas in Hennepin County. The Mt. Simon Aquifer is not hydraulically connected to the shallow groundwater system or to major waterways. Groundwater in the Mt. Simon Aquifer is derived from leakage from overlying units or from recharge outside Ramsey County (Kanivetsky and Cleland 1992).

The Franconia-Ironton-Galesville Aquifer underlies all of Ramsey County. Groundwater moves from areas of high hydraulic head in northern Ramsey County toward the Mississippi River. The Franconia-Ironton-Galesville Aquifer is separated from the underlying Mt. Simon Aquifer by the Eau Claire Confining Unit (Kanivetsky and Cleland 1992).

The Prairie du Chien-Jordan Aquifer is the most heavily used aquifer in the county. This aquifer is present throughout Ramsey County except in deeper parts of bedrock valleys. Groundwater movement in the Prairie du Chien Group occurs mainly through fractures, joints, and solution cavities, whereas groundwater movement in the Jordan Sandstone is through intergranular pore space. The Prairie du Chien Group and the Jordan Sandstone function as a single aquifer because of the

absence of a regionally extensive confining unit. Groundwater flows from areas of high hydraulic head in northern Ramsey County toward the Mississippi River. The Prairie du Chien-Jordan Aquifer is mostly confined throughout the county except just south of the Pig's Eye site. The Prairie du Chien-Jordan Aquifer is highly prolific in the region, with yields as high as 2,000 gallons per minute (gpm). The Prairie du Chien-Jordan Aquifer is separated from the underlying Franconia-Ironton-Galesville Aquifer by the St. Lawrence Confining Unit (Kanivetsky and Cleland 1992).

The St. Peter Aquifer underlies about 75 percent of Ramsey County. It is absent in northwestern Ramsey County and in deeper bedrock valleys such as the one underlying the Pig's Eye site. Groundwater in the St. Peter Aquifer flows from areas of high hydraulic head in northern Ramsey County toward the Mississippi River. Regionally extensive mudstone and siltstone beds at the base of the St. Peter Aquifer act as confining units between the St. Peter Aquifer and the underlying Prairie du Chien-Jordan Aquifer (Kanivetsky and Cleland 1992).

Groundwater from the Glenwood, Platteville, and Galena Formations are rarely used as sources of drinking water in the Minneapolis and St. Paul area (Kanivetsky and Cleland 1992).


#### **4.6.2 Site-Specific Hydrogeology**


Two shallow water-bearing units were identified at the Pig's Eye site during monitoring well installation. An upper, unconfined unit is present at the interface of the fill material and the organic silt and peat unit. A deeper confined or semiconfined unit is present in the sand unit below the organic silt and peat unit. Although well nests were not installed during the LRI, it appears that the organic silt and peat unit acts as a local confining unit southeast of Battle Creek, especially at monitoring well MW-14. During soil boring drilling at monitoring well MW-14, two separate water-bearing units were encountered above and below the organic silt and peat unit. Both of these water-bearing units, however, are considered part of the larger unconsolidated valley fill aquifer that fills the buried Phalen Channel. Because the sand unit lies directly over bedrock, the shallow water-bearing units below the site are also in direct hydrogeologic contact with the underlying Prairie du Chien-Jordan Aquifer.

Groundwater from the Prairie du Chien-Jordan Aquifer is the principal source of private drinking water in the area around the Pig's Eye site. Although the unconsolidated deposits along the Mississippi River are capable of high yields, they typically are not used for drinking water supplies.

Groundwater elevation data were collected for the monitoring wells at the Pig's Eye site on September 14, October 4, and October 15, 1994 (see Tables 4-1, 4-2, and 4-3). Stream gage measurements were recorded on October 15, 1994 (see Table 4-4). Figures 4-9, 4-10, and 4-11 present the groundwater elevation data collected on September 14, October 4, and October 15, 1994, and approximate groundwater contours. The figures indicate that a mounding effect is present both northwest and southeast of Battle Creek. Battle Creek also acts as a discharge point for shallow groundwater at the site. Northwest of Battle Creek, groundwater also appears to flow toward the Mississippi River.

Monitoring wells MW-14 and MW-15 have lower groundwater elevations than nearby shallow monitoring wells screened above the organic silt and peat unit. This indicates that a downward vertical hydraulic gradient exists between the water-bearing units above and below the organic silt and peat units. Additional hydrogeological data, such as installation of monitoring well nests, would verify this assumption.





**LEGEND**


- 1 ST. CROIX MORaine COMPLEX
- 2 ST. PAUL TILL PLAIN
- 3 NORTH RAMSEY MOUNDS
- 4 ANOKA SAND PLAIN
- 5 ST. PAUL SAND FLATS
- 6 MISSISSIPPI BOTTOMLAND

NOT TO SCALE

SOURCE: MODIFIED FROM PATTERSON 1992

|   |
|---|
| PIG'S EYE DUMP<br>ST. PAUL, MINNESOTA                           |
| <b>FIGURE 4-2</b><br><b>GEOMORPHIC REGIONS OF RAMSEY COUNTY</b> |
| <b>PRC</b> ENVIRONMENTAL MANAGEMENT, INC.                       |






### SOIL LEGEND\*

- SOILS FORMED DOMINANTLY IN OUTWASH**
- 1 Zimmerman—Urban Land—Rifle: Level to gently rolling, excessively drained and very poorly drained, coarse textured soils and organic soils and Urban land; on uplands
  - 2 Urban Land—Chetek—Mahtomedi: Urban land and nearly level to very steep, somewhat excessively drained and excessively drained, moderately coarse textured and coarse textured soils; on uplands
  - 3 Urban Land—Waukegan—Chetek: Urban land and nearly level to moderately steep, well drained and somewhat excessively drained, medium textured and moderately coarse textured soils; on uplands
- SOILS FORMED DOMINANTLY IN LACUSTRINE SEDIMENTS**
- 4 Barronett—Grays: Level to gently sloping, poorly drained and moderately well drained, medium textured soils; on glacial lake plains
- SOILS FORMED DOMINANTLY IN GLACIAL TILL**
- 5 Hayden—Urban Land: Undulating to steep, well drained, moderately coarse textured soils and Urban land; on uplands
  - 6 Kingsley—Urban Land: Undulating to steep, well drained, moderately coarse textured soils and Urban land; on uplands
- SOILS FORMED DOMINANTLY IN LOAMY SEDIMENTS OVER BEDROCK**
- 7 Urban Land—Copaston: Urban land and level to moderately sloping, well drained, medium textured soils; on uplands
- SOILS FORMED DOMINANTLY IN GLACIAL TILL OR OUTWASH**
- 8 Kingsley—Mahtomedi: Undulating to very steep, well drained and excessively drained, moderately coarse textured and coarse textured soils; on uplands
- SOILS FORMED DOMINANTLY IN RECENT ALLUVIUM**
- 9 Udothents, wet substratum—Alganssee: Nearly level to very gently sloping, variably textured fill material and nearly level, somewhat poorly drained, coarse textured soils; on flood plains

Compiled 1978

\* Terms describing texture refer to the surface layer of the major soils in each map unit.



FIG'S EYE DUMP  
ST. PAUL, MINNESOTA


FIGURE 4-3  
SOIL MAP OF RAMSEY COUNTY

PRC ENVIRONMENTAL MANAGEMENT, INC.









## DESCRIPTION OF BEDROCK UNITS

- Od** **Decorah Shale**—Green, calcareous shale; thin limestone interbeds. In a few places capped by thin (less than 20 feet) erosional remnants of limestone of overlying Galena Group (not shown on map). Largely restricted to south half of county. Unit crops out in bluffs of Mississippi River in south and west St. Paul. Formerly mined in south St. Paul above Pickerel Lake for clay to make brick and tile.
- Opg** **Platteville and Glenwood Formations**—Fine-grained dolostone and limestone of Platteville underlain by thin, green, sandy shale (3–5.5 feet thick) of Glenwood. Extensive outcrops in bluffs along Mississippi River in St. Paul. Platteville formerly quarried for rock aggregate and building stone in bedrock terraces of south St. Paul.
- Osp** **St. Peter Sandstone**—Upper half to two-thirds: fine- to medium-grained, quartz sandstone; generally massive to thick bedded. Lower part: multicolored beds of mudstone, siltstone, and shale; interbeds of very coarse sandstone. Basal contact is erosional surface. Unit crops out in bluffs along Mississippi River. Formerly mined for glass sand for the Ford Motor Company plant in west St. Paul. Man-made caves in St. Peter, within the bluffs along Mississippi River in south St. Paul, formerly used for raising mushrooms.
- Opc** **Prairie du Chien Group**—Upper half to two-thirds: commonly sandy or oolitic and thin-bedded dolostone; thin beds of sandstone and chert; thin beds of intraclastic (conglomeratic) dolostone. Lower part: generally massive or thick bedded dolostone; not oolitic or sandy, except for thin, sandy, transitional zone at base. Upper part of Prairie du Chien dolostone may contain karst solution cavities, particularly where overlying St. Peter Sandstone removed by erosion. No outcrops of Prairie du Chien Group in county; however, it is first bedrock encountered beneath Quaternary deposits over large part of county; extensive outcrops found in adjacent northern Dakota and southern Washington Counties.
- Cj** **Jordan Sandstone**—Upper part: medium- to coarse-grained, friable, quartzose sandstone. Lower part: primarily fine-grained, feldspathic sandstone. Sharp upper contact with Prairie du Chien Group. No outcrops of Jordan in county; subcrops beneath Quaternary deposits along some buried valleys.



PIG'S EYE DUMP  
ST. PAUL, MINNESOTA

**FIGURE 4-5**  
**BEDROCK GEOLOGY OF RAMSEY COUNTY**  
**PRC ENVIRONMENTAL MANAGEMENT, INC.**








FIG-1117.DWG - 11/23/94 - CTR - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994



CS-AA.DWG - 11/24/94 - CRR - 080-000404




SCALES:  
HORIZONTAL: 1" = 400'  
VERTICAL: 1" = 5'

PIG'S EYE DUMP  
ST. PAUL, MINNESOTA

**FIGURE 4-7**  
CROSS SECTION A-A'

**PRC** ENVIRONMENTAL MANAGEMENT, INC.



# LEGEND

- FILL
- SAND
- ORGANIC SILT AND PEAT
- BEDROCK

SCALES:  
 HORIZONTAL: 1" = 400'  
 VERTICAL: 1" = 10'

PIG'S EYE DUMP  
 ST. PAUL, MINNESOTA

FIGURE 4-8  
 CROSS SECTION B-B'

**PRC** ENVIRONMENTAL MANAGEMENT, INC.







FIG-1117.DWG - 11/23/94 - GFR - 080-000404

SOURCE: MODIFIED FROM RAMSEY COUNTY GIS DATABASE MAP 1994










FIG-1117.DWG - 11/23/94 - CDR - 080-000404



**TABLE 4-1**  
**GROUNDWATER ELEVATIONS ON SEPTEMBER 14, 1994<sup>a</sup>**

| Monitoring Well No. | Top of Riser Elevation <sup>a</sup> | Depth to Groundwater <sup>b</sup> | Groundwater Elevation <sup>a</sup> |
|---------------------|-------------------------------------|-----------------------------------|------------------------------------|
| MW-1                | 708.19                              | 16.13                             | 692.06                             |
| MW-2                | 703.37                              | Not Measured                      | Not Measured                       |
| MW-4                | 705.80                              | 12.61                             | 693.19                             |
| MW-5                | 703.82                              | 13.62                             | 690.20                             |
| MW-6                | 705.29                              | 14.97                             | 690.32                             |
| MW-7                | 706.30                              | 12.90                             | 693.40                             |
| MW-8                | 705.15                              | 11.99                             | 693.16                             |
| MW-9                | 702.54                              | 10.21                             | 692.33                             |
| MW-10               | 702.17                              | 10.10                             | 692.07                             |
| MW-11               | 704.43                              | 12.51                             | 691.92                             |
| MW-12               | 703.09                              | 11.11                             | 691.98                             |
| MW-13               | 699.25                              | 8.87                              | 690.38                             |
| MW-14               | 695.98                              | 6.94                              | 689.04                             |
| MW-15               | 702.55                              | 14.89                             | 687.66                             |

Notes:

<sup>a</sup> Presented in feet above MSL

<sup>b</sup> Measured in feet bgs

**TABLE 4-2**  
**GROUNDWATER ELEVATIONS ON OCTOBER 4, 1994**

| Monitoring Well No. | Top of Riser Elevation <sup>a</sup> | Depth to Groundwater <sup>b</sup> | Groundwater Elevation <sup>a</sup> |
|---------------------|-------------------------------------|-----------------------------------|------------------------------------|
| MW-1                | 708.19                              | 16.23                             | 691.96                             |
| MW-2                | 703.37                              | 11.18                             | 692.19                             |
| MW-4                | 705.80                              | 12.63                             | 693.17                             |
| MW-5                | 703.82                              | 13.64                             | 690.18                             |
| MW-6                | 705.29                              | 14.93                             | 690.36                             |
| MW-7                | 706.30                              | 12.90                             | 693.40                             |
| MW-8                | 705.15                              | 11.99                             | 693.16                             |
| MW-9                | 702.54                              | 10.26                             | 692.28                             |
| MW-10               | 702.17                              | 9.88                              | 692.29                             |
| MW-11               | 704.43                              | 12.40                             | 692.03                             |
| MW-12               | 703.09                              | 11.10                             | 691.99                             |
| MW-13               | 699.25                              | 8.67                              | 690.58                             |
| MW-14               | 695.98                              | 7.17                              | 688.81                             |
| MW-15               | 702.55                              | 15.20                             | 687.35                             |

Notes:

<sup>a</sup> Presented in feet above MSL

<sup>b</sup> Measured in feet bgs

**TABLE 4-3**  
**GROUNDWATER ELEVATIONS ON OCTOBER 15, 1994**

| Monitoring Well No. | Top of Riser Elevation <sup>a</sup> | Depth to Groundwater <sup>b</sup> | Groundwater Elevation <sup>a</sup> |
|---------------------|-------------------------------------|-----------------------------------|------------------------------------|
| MW-1                | 708.19                              | 16.20                             | 691.99                             |
| MW-2                | 703.37                              | 11.09                             | 692.28                             |
| MW-4                | 705.80                              | 12.49                             | 693.31                             |
| MW-5                | 703.82                              | 13.65                             | 690.17                             |
| MW-6                | 705.29                              | 14.59                             | 690.70                             |
| MW-7                | 706.30                              | 12.54                             | 693.76                             |
| MW-8                | 705.15                              | 11.85                             | 693.30                             |
| MW-9                | 702.54                              | 10.33                             | 692.21                             |
| MW-10               | 702.17                              | 9.95                              | 692.22                             |
| MW-11               | 704.43                              | 12.45                             | 691.98                             |
| MW-12               | 703.09                              | 10.83                             | 692.26                             |
| MW-13               | 699.25                              | 8.57                              | 690.68                             |
| MW-14               | 695.98                              | 7.15                              | 688.83                             |
| MW-15               | 702.55                              | 14.66                             | 687.89                             |

Notes:

<sup>a</sup> Presented in feet above MSL

<sup>b</sup> Measured in feet bgs

**TABLE 4-4**  
**SURFACE WATER ELEVATIONS ON OCTOBER 15, 1994**

| Stream<br>Gage | Reference<br>Elevation <sup>b</sup> | Depth of<br>Surface Water <sup>c</sup> | Surface Water<br>Elevation <sup>a</sup> |
|----------------|-------------------------------------|--|---|
| SG-1           | 692.56                              | 0.91                                   | 690.47                                  |
| SG-2           | 687.22                              | 3.22                                   | 687.44                                  |
| SG-3           | 692.39                              | 1.91                                   | 691.30                                  |
| SG-4           | 692.75                              | 1.54                                   | 691.29                                  |

Notes:

- <sup>a</sup> Presented in feet above MSL
  - <sup>b</sup> Measured at 3.0 foot mark on gage
  - <sup>c</sup> Measured in feet
-

## **5.0 NATURE AND EXTENT OF CONTAMINATION**

This section discusses the nature and extent of contamination in the soil gas, groundwater, surface water, and sediment at the Pig's Eye site based on the analysis of samples collected during the LRI activities.

The results of the soil gas survey, groundwater analysis, surface water analysis, and sediment analysis are discussed below. The analytical data presented in this section are from analyses performed by the CLP laboratory unless otherwise indicated. The data reported by the CLP laboratory performing the analyses were validated by PRC. Analytes detected above laboratory method detection limits are summarized in tables in this section. Complete CLP analytical results and a data summary are included in Appendix F.

### **5.1 SOIL GAS SURVEY RESULTS**

The purpose of the soil gas survey was to determine if VOCs are present in the fill material soil gas and to provide data to plan additional field activities such as Geoprobe™ groundwater sampling, monitoring well installation, and trenching. Soil gas samples were collected from 105 locations at the Pig's Eye site during the weeks of April 18 and April 25, 1994. The sampling locations are shown in Figure 3-1. The depths at which the soil gas samples were collected is presented in Table 3-1. The samples were analyzed by PRC's CSL for chlorinated VOCs and for aromatic and other VOCs. These compounds and their method detection limits are presented in Appendix G. The QA/QC procedures for PRC's CSL data are also discussed in the data summary of Appendix G.

Trichlorofluoromethane; 1,1-dichloroethene (DCE); methylene chloride; trans-1,2-DCE; 1,1-dichloroethane (DCA); cis-1,2-DCE; chloroform; 1,1,1-trichloroethane (TCA); carbon tetrachloride; trichloroethene (TCE); perchloroethene (PCE); and 1,1,1,2-perchloroethane (PCA) were detected above laboratory method detection limits. Tables 5-1 and 5-2 summarize the analytical results for the chlorinated VOCs and the aromatic and other VOCs, respectively. The concentrations are presented in parts per billion (ppb). Figures 5-1A and 5-1B of the Attachment show the concentrations of each chlorinated VOC at each sampling location at which they were detected. Figure 5-2 of the Attachment shows the concentrations of each aromatic or other VOC at each

sampling location at which they were detected.

TCE and PCE were the two most commonly detected chlorinated VOCs in the soil gas. Methyl tert-butyl ether, benzene, methyl isobutyl ketone (MIBK), ethylbenzene, and total xylenes are the most commonly detected aromatic or other VOCs. In general, the detection of these compounds was widely dispersed throughout the sampling area.

## **5.2 GEOPROBE™ GROUNDWATER SAMPLING RESULTS**

Groundwater samples were collected using PRC's Geoprobe™ at 40 locations during the weeks of April 25 and May 2, 1994. The locations of the samples are shown in Figure 3-2. The depths at which these samples were collected are shown in Table 3-2. Forty-four samples, including four duplicate samples, were analyzed by the CLP laboratory for VOCs. Forty-three samples, including four duplicate samples were analyzed by the CLP laboratory for SVOCs, metals (including cyanide), pesticides, and PCBs. The analytical results for each analyte group are discussed below. The CLP analytical results were compared to the Minnesota Department of Health's (MDH) Recommended Allowable Limits for Drinking Water Contaminants (RAL) (MDH 1992). All but one of the samples (J2400N) were also analyzed by PRC's CSL for VOCs. PRC's CSL analyzed the samples to get real-time data to help guide future field activities. The DCBs were analyzed as a SVOC by the CLP laboratory and as a VOC by PRC's CSL.

### **5.2.1 VOC Analytical Results**

Seventeen VOCs were detected above laboratory method detection limits in samples analyzed by the CLP laboratory. The analytical results for VOCs detected in groundwater are presented in Table 5-3. Table 5-3 also includes total VOC concentrations, VOC tentatively identified compounds (TIC) grouped by chemical class, and total VOC TIC concentrations.

The VOC concentrations detected were compared to the RALs (MDH 1992). Of VOCs having an RAL assigned, benzene and 1,1-DCE are the only compounds detected at concentrations exceeding their respective RALs at a minimum of one sampling location. Benzene was detected above its RAL of 10 ppb in 16 samples and 1,1-DCE was detected above its RAL of 6 ppb in one sample. Several

VOC TICs were detected above laboratory method detection limits in the groundwater samples collected. In general, most of the TICs detected appear to be hydrocarbon related. Figure 5-3 of the Attachment shows the concentrations of benzene; 1,1-DCE; total VOCs; and total VOC TICs at each sampling location at which they were detected.

Thirteen VOCs were detected above laboratory method detection limits by PRC's CSL. PRC's CSL analytical results are presented in Table 5-4. The laboratory method detection limits for these analytes are included in Appendix G. Of VOCs having an RAL, benzene and 1,4-DCB are the only compounds detected at concentrations exceeding their respective RALs at a minimum of one sampling location. Benzene was detected above its RAL in 10 samples. Benzene was also detected above its RAL by the CLP laboratory. The 1,4-DCB was detected above its RAL of 10 ppb in seven samples. Figure 5-4 of the Attachment shows the concentrations of benzene and 1,4-DCB at each sampling location at which they were detected.

#### **5.2.2 SVOC Analytical Results**

Thirty-six SVOCs were detected above laboratory method detection limits in the Geoprobe™ groundwater samples analyzed by the CLP laboratory. The analytical results are summarized in Table 5-5. Also included in Table 5-5 are the results for total SVOC concentrations, SVOC TICs grouped by chemical class, and total SVOC TIC concentrations.

Of SVOCs having a RAL, bis (2-chloroethyl) ether; 1,4-DCB; nitrobenzene; and naphthalene were detected at concentrations exceeding their respective RALs at a minimum of one sampling location. Bis (2-chloroethyl) ether was detected above its RAL of 0.3 ppb in one sample. The 1,4-DCB was detected above its RAL of 10 ppb in one sample. Nitrobenzene was detected above its RAL of 3 ppb in eight samples. Naphthalene was detected above its RAL of 30 ppb in seven samples. Several SVOC TICs were detected in the groundwater samples collected. In general, most of the TICs detected appear to be hydrocarbon related. Figure 5-5 of the Attachment shows the locations at which these compounds were detected above laboratory method detection limits, along with the total SVOC and total SVOC TIC concentrations.

### **5.2.3 Metal Analytical Results**

Eighteen metals were detected above laboratory detection limits in the Geoprobe™ groundwater samples analyzed by the CLP laboratory. The analytical results are presented in Table 5-6.

Of analytes having an RAL, seven of the analytes detected above laboratory method detection limits were detected at concentrations exceeding their respective RALs at a minimum of one sampling location. They include antimony, arsenic, cobalt, manganese, mercury, nickel, and thallium. Arsenic and manganese were the most frequently detected metals exceeding their RALs. Arsenic exceeded its RAL of 1.0 ppb in 23 samples, and manganese exceeded its RAL of 300 ppb in 20 samples. Antimony exceeded its RAL of 1.0 ppb in four samples. Cobalt exceeded its RAL of 1.0 ppb in eight samples. Mercury, nickel, and thallium exceeded their respective RALs of 1.0, 70, and 0.3 ppb in one sample each. The concentrations of the seven metals exceeding RALs at each sampling location are shown in Figure 5-6 of the Attachment.

### **5.2.4 Pesticide Analytical Results**

Five pesticides were detected above laboratory method detection limits in the Geoprobe™ groundwater samples collected from the Pig's Eye site. They include delta-BHC; alpha chlordane; gamma chlordane; 4,4-DDT; and 4,4-DDD. Delta-BHC and alpha chlordane were each detected at one sampling location only. Gamma chlordane and 4,4-DDT were detected at two sampling locations. At three sampling locations, 4,4-DDD was detected. Table 5-7 presents a summary of the analytical results. Figure 5-7 of the Attachment shows the concentrations of the five pesticides detected above laboratory method detection limits at each of the sampling locations at which they were detected.

### **5.2.5 PCB Analytical Results**

The PCBs detected above laboratory method detection limits in Geoprobe™ groundwater samples included Aroclor 1221, Aroclor 1242, Aroclor 1254, and Aroclor 1260. Aroclor 1242 was the most commonly detected PCB (detected in eight samples). Aroclor 1221 and Aroclor 1260 were each detected in two samples. Aroclor 1254 was detected in one sample. Table 5-8 presents a summary of PCB analytical results. The concentrations of each Aroclor species are shown by sampling location



in Figure 5-8 of the Attachment.

### **5.3 MONITORING WELL GROUNDWATER SAMPLING RESULTS**

Seventeen groundwater samples, including two duplicate samples, were collected from the 15 on-site groundwater monitoring wells during the week of August 29, 1994. The samples were analyzed by the CLP laboratory for VOCs, SVOCs, metals (including cyanide), pesticides, and PCBs. Because the pesticide/PCB sample from monitoring well MW-8 was lost during extraction, monitoring well MW-8 was sampled again on September 14, 1994, and the sample was submitted to the CLP laboratory and analyzed for pesticides and PCBs. The analytical results for each analyte group are discussed below.

#### **5.3.1 VOC Analytical Results**

Twelve VOCs were detected above laboratory method detection limits in the groundwater samples collected from the Pig's Eye site. Analytical results are presented in Table 5-9. Table 5-9 also presents total VOC concentrations, VOC TICs grouped by chemical class, and total VOC TIC concentrations.

VOC concentrations were compared to MDH RALs (MDH 1992). Of those VOCs having a RAL, benzene was the only compound detected at concentrations exceeding its RAL at a minimum of one sampling location. Benzene was detected above its RAL of 10 ppb in six monitoring wells (MW-1, MW-4, MW-6, MW-8, MW-9, and MW-13). Several VOC TICs were detected in the groundwater samples collected. Most of the TICs detected appear to be hydrocarbon related. Figure 5-9 of the Attachment shows the concentrations of benzene, total VOCs, and total VOC TICs at each sampling location at which they were detected.

#### **5.3.2 SVOC Analytical Results**

Fifteen SVOCs were detected above laboratory method detection limits in the groundwater samples collected at the Pig's Eye site. The analytical results are presented in Table 5-10. Table 5-10 also presents total SVOC concentrations, SVOC TICs grouped by chemical class, and total SVOC TIC

concentrations.

Analytical results were compared to MDH RALs (MDH 1992). None of the compounds detected above laboratory method detection limits that also have an RAL were detected at concentrations exceeding their RALs. Several SVOC TICs were detected in the groundwater samples collected. Most of the TICs detected appear to be hydrocarbon related. Figure 5-10 of the Attachment shows total SVOC and total SVOC TIC concentrations at each sampling location at which SVOCs were detected.

### **5.3.3 Metal Analytical Results**

Twenty-one metals were detected above laboratory method detection limits in the groundwater samples collected from the Pig's Eye site. The analytical results are presented in Table 5-11. Seven metals, including antimony, cobalt, manganese, nickel, selenium, thallium, and zinc, were detected at concentrations exceeding the RALs. Antimony exceeded its RAL of 1.0 ppb in three samples. Cobalt exceeded its RAL of 1.0 ppb in 10 samples. Manganese exceeded its RAL of 300 ppb in 12 samples. Nickel exceeded its RAL of 70 ppb in one sample. Selenium exceeded its RAL of 10 ppb in seven samples. Thallium exceed its RAL of 0.3 ppb in one sample. Zinc exceeded its RAL of 700 ppb in one sample. Figure 5-11 of the Attachment shows the total concentrations of metals that exceed their respective RALs at a minimum of one sampling location.

### **5.3.4 Pesticide Analytical Results**

Aldrin was the only pesticide detected above laboratory method detection limits in the groundwater samples collected from the on-site groundwater monitoring wells. Aldrin was detected in monitoring well MW-7 at a concentration of 0.069 ppb. This concentration exceeds aldrin's RAL of 0.02 ppb.

### **5.3.5 PCB Analytical Results**

Aroclor 1242 was the only PCB detected above laboratory method detection limits in the groundwater samples collected. Aroclor 1242 was detected in monitoring well MW-8 at a concentration of 3.9 ppb.

## **5.4**

## **SURFACE WATER SAMPLING RESULTS**

Six surface water samples, including one duplicate sample, were collected from five locations at the Pig's Eye site during the week of June 6, 1994. The samples were analyzed by the CLP laboratory for VOCs, SVOCs, metals (including cyanide), pesticides, and PCBs. The analytical results were compared to Ambient Water Quality Criteria (AWQC) (EPA 1992). The analytical results for each analyte group are discussed below.

### **5.4.1 VOC Analytical Results**

Nine VOCs were detected above laboratory method detection limits in any of the six samples analyzed. Analytical results are presented in Table 5-12. Table 5-12 presents total VOC concentrations, VOC TICs by chemical class, and total VOC TIC concentrations. None of the compounds detected have been assigned an AWQC value. Total VOC and VOC TIC concentrations at each sampling location are presented in Figure 5-12 of the Attachment.

### **5.4.2 SVOC Analytical Results**

Twelve SVOCs were detected above laboratory method detection limits in the six samples analyzed. Analytical results are presented in Table 5-13. Table 5-13 presents total SVOC concentrations, SVOC TICs by chemical class, and total SVOC TIC concentrations. None of the compounds detected have been assigned an AWQC value. Total SVOC and total SVOC TIC concentrations detected at each sampling location are presented in Figure 5-12 of the Attachment.

### **5.4.3 Metal Analytical Results**

Twenty-one metals were detected above laboratory method detection limits in the six surface water samples. Analytical results are presented in Table 5-14. All but two of the metals were detected above laboratory method detection limits in sample E1600S. Surface water sample E1600S was collected near the battery disposal area. Of analytes having an AWQC value, cadmium, copper, iron, lead, mercury, nickel, zinc, and cyanide were detected at concentrations exceeding their AWQCs at a minimum of one sampling location.

Cadmium was detected at a concentration exceeding its AWQC of 1.1 ppb in one sample. Copper was detected at a concentration greater than its AWQC of 12 ppb in one sample. Iron was detected at a concentration exceeding its AWQC of 1,000 ppb in all six samples. Lead was detected at a concentration exceeding its AWQC of 3.2 ppb in three samples. Mercury, nickel, and zinc each exceeded their AWQCs of 0.012, 160, and 110 ppb, respectively in one sample. Cyanide was detected at a concentration exceeding its AWQC of 5.2 ppb in three samples. The concentrations of these eight metals at each sampling location are presented in Figure 5-13 of the Attachment.

#### **5.4.4 Pesticide Analytical Results**

One pesticide was detected above its laboratory method detection limit by the CLP laboratory in the surface water samples collected from the Pig's Eye site. Beta BHC was detected at a concentration of 0.026 ppb at sampling location H1800S.

#### **5.4.5 PCB Analytical Results**

PCBs were not detected above laboratory method detection limits in the six samples analyzed.

### **5.5 SEDIMENT SAMPLING RESULTS**

Six sediment samples, including one duplicate sample, were collected from five locations at the Pig's Eye site on May 5, 1994. In addition, two sediment samples were collected on September 14, 1994 from the pond located along the southwest edge of the dump site. The samples were analyzed by the CLP laboratory for VOCs, SVOCs, total metals (including cyanide), pesticides, and PCBs.

Analytical results for sediment samples were compared to the toxicity characteristic leaching procedure (TCLP) standard multiplied by a factor of 20. The TCLP standard times 20 represents a minimum concentration at which leachate from the sediment sample has the potential to exceed the TCLP standard. The analytical results for each analyte group are discussed below.

### **5.5.1 VOC Analytical Results**

Seven VOCs were detected above laboratory method detection limits in the six samples collected on May 5, 1994. Four VOCs were detected above laboratory method detection limits in the two samples collected on September 14, 1994. Analytical results for the May 5, 1994 and September 14, 1994 sampling events are presented in Table 5-15 and Table 5-16, respectively. Table 5-15 and 5-16 also presents total VOC concentrations detected in each sample. Of analytes having a TCLP standard, none were detected at concentrations exceeding the TCLP standard times 20. Total VOC and total VOC TIC concentrations for each sampling event at each sampling location are presented in Figure 5-14 of the Attachment.

### **5.5.2 SVOC Analytical Results**

Nineteen SVOCs were detected above laboratory method detection limits in the six samples collected on May 5, 1994. Bis(2-ethylhexyl)phthalate was the only SVOC detected above laboratory method detection limits in the samples collected on September 14, 1994; specifically in sample S-2 only. The analytical results for the May 5, 1994 and the September 14, 1994 sampling events are presented in Table 5-17 and 5-18, respectively. Both tables also present the concentrations of total SVOCs, SVOC TICs by chemical class, and total SVOC TICs. Only two of the SVOCs detected in the May 5 samples have been assigned a TCLP standard (1,4-DCB and naphthalene); however, these analytes were not detected at concentrations exceeding the TCLP standard times 20. A TCLP limit has not been assigned to bis(2-ethylhexyl)phthalate. The SVOC TICs appear to be hydrocarbon related. Figure 5-14 of the Attachment shows the concentrations of total SVOCs and total SVOC TICs detected at each sampling location for each sampling event.

### **5.5.3 Metal Analytical Results**

Twenty-one metals were detected above laboratory method detection limits in the samples collected on May 5, 1994. Twenty-three metals, including cyanide, were detected above laboratory method detection limits in the samples collected on September 14, 1994. Analytical results for the May 5, 1994 and the September 14, 1994 sampling events are presented in Table 5-19 and Table 20, respectively. Of metals having a TCLP standard, only chromium and lead were detected at

concentrations exceeding their TCLP standard times 20 in the samples collected May 5, 1994; chromium at one sampling location, and lead at three. Cadmium, chromium, and lead were detected above the TCLP limit times 20 in the samples collected September 14, 1994. The concentrations of cadmium, chromium, and lead detected at each sampling location for each sampling event are shown in Figure 5-15 of the Attachment.

#### **5.5.4 Pesticide Analytical Results**

Five pesticides were detected above laboratory method detection limits in the six samples collected on May 5, 1994. They include 4,4-DDE; 4,4-DDT; 4,4-DDD; aldrin; and gamma chlordane. Analytical results are presented in Table 5-21. Pesticides, however, were not detected above laboratory method detection limits in the samples collected on September 14, 1994. None of the analytes detected in the May 5, 1994 samples have been assigned a TCLP standard. The concentrations of the pesticides detected above laboratory method detection limits in the May 5, 1994 samples are shown by sampling location in Figure 5-16 of the Attachment.

#### **5.5.5 PCB Analytical Results**

PCBs were not detected above laboratory method detection limits in any of the six samples collected on May 5, 1994. However, Aroclor 1248 and 1254 were detected above laboratory method detection limits in sample SED-1 collected on September 14, 1994. The analytical results are presented in Table 5-22.

### **5.6 TRENCH SOIL SAMPLING RESULTS**

Soil samples, T2-1 and T3-1, were collected from trenches T-2 and T-3, respectively. The samples were collected from fill material stockpiled next to the trenches and represented soil at a depth of approximately 10 to 12 feet below ground surface. The samples were analyzed by the CLP laboratory for VOCs, SVOCs, total metals (including cyanide), pesticides, and PCBs. Analytical results for sediment samples were compared to the toxicity characteristic leaching procedure (TCLP) standard multiplied by a factor of 20. The TCLP standard times 20 represents a minimum concentration at which leachate from the sediment sample has the potential to exceed the TCLP

standard. The analytical results for each analyte group are discussed below.

#### **5.6.1 VOC Analytical Results**

Six VOCs were detected above laboratory method detection limits in the samples collected. The analytical results are presented in Table 5-23. Where only acetone was detected in sample T3-1, all six VOCs were detected in sample T2-1 or its duplicate. Of the VOCs detected, only chlorobenzene has been assigned a TCLP limit. However, chlorobenzene, detected in T2-1 and its duplicate sample, were not detected at concentrations greater than the TCLP limit times 20. Total VOC, VOC TICs by classification, and total VOC TIC concentrations are also presented in Table 5-23. The TICs identified in the samples appear to be hydrocarbon related.

#### **5.6.2 SVOC Analytical Results**

Eighteen SVOCs were detected above laboratory method detection limits in the samples collected. The analytical results are presented in Table 5-24. Of the SVOCs detected, only 1,4-DCB has been assigned a TCLP limit. The concentrations of 1,4-DCB detected in sample T2-1 and its duplicate sample were detected at concentrations greater than its TCLP limit times 20 (150 ppb). 1,4-DCB was not detected above laboratory method detection limits in sample T3-1. Total VOC, VOC TICs by classification, and total VOC TIC concentrations are also presented in Table 5-23. The TICs identified in the samples appear to be hydrocarbon related.

#### **5.6.3 Metal Analytical Results**

Twenty-three metals were detected above laboratory method detection limits in the samples collected. The analytical results are presented in Table 5-25. Of the metals assigned a TCLP standard, three metals, including cadmium, chromium, and lead, were detected at concentrations exceeding their TCLP limit times 20. All three of the metals detected at concentrations exceeding their TCLP limit times 20 were detected in sample T3-1.

#### **5.6.4 Pesticide Analytical Results**

Pesticides were not detected above laboratory method detection limits in the trench soil samples collected.

#### **5.6.5 PCB Analytical Results**

Three PCBs were detected above laboratory method detection limits in the samples collected. The analytical results are presented in Table 5-26. Aroclor 1016, 1254, and 1260 were detected above laboratory method detection limits in sample T3-1. Only Aroclor 1254 was detected above laboratory method detection limits in sample T2-1.

### **5.7 TRENCHING OBSERVATIONS**

Four trenches, T-1 through T-4, were dug at locations as depicted in Figure 3-6. Each trench was approximately 3 feet x 30 feet x 12 feet deep. All four trenches were backfilled upon completion. Below is a discussion of our observations during trenching operations.

#### **5.7.1 Trench T-1**

Trench T-1 was dug near grid location F3000N. Groundwater began entering the trench when the depth of the trench reached approximately 10 feet bgs. The trench was dug to a depth at which the fill material ended (approximately 12 feet). The fill observed was comprised predominantly of household waste. A newspaper dated 1967 was identified in the refuse. Some of the items observed included, but were not limited to, a few tires, spray paint cans, a few battery casings, paint cans, and a crushed five-gallon pail containing a solidified black tar-like substance.

#### **5.7.2 Trench T-2**

Trench T-2 was dug near grid location E200N. The fill observed was comprised predominantly of household and industrial waste to a depth of approximately 12 feet bgs. A newspaper dated March 12, 1972 was found within the top five feet of the fill. Some of the items observed included, but



were not limited to, a tires, tree stumps and logs, plastic ribbon which appeared to be for commercial or industrial purposes, medical waste including a plastic bag containing an unknown liquid and used syringes, paint cans, a few battery casings, a spray can with the ingredient "methylene chloride" written on it, and several circuit boards.

#### **5.7.3           Trench T-3**

Trench T-3 was dug near grid location H400S. The fill observed was comprised predominantly of industrial and household waste to a depth of approximately 12 feet bgs. A newspaper dated December 31, 1971 and was identified in the refuse. Some of the items observed included, but were not limited to, battery casings, a large roll of paper approximately three feet in diameter, a vial of clinical strips for glucose testing, a document with "St. Paul Insurance Co." on it, a document with "Western Insurance Co." on it, and a cardboard box with an address label reading "3M" on it.

#### **5.7.4           Trench T-4**

Trench T-4 was dug near grid location C400S. The fill observed was comprised predominantly of building debris and some household waste. A newspaper dated June 13, 1971 was identified in the refuse. Some of the items observed included, but were not limited to, lumber, paint cans, an empty can of radiator antifreeze and waterpump lubricant, and two crushed drums with no identifiable labels, writing, or contents.

TABLE 5-1

**CHLORINATED VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Vinyl Chloride   | Trichloro-fluoro-methane | 1,1-DCE | Methylene Chloride | trans-1,2-DCE | 1,1-DCA | cis-1,2-DCE | Chloroform | 1,1,1-TCA | Carbon Tetrachloride | 1,2-DCA | TCE   | 1,1,2-TCA | PCE  | 1,1,1,2-PCA | 1,1,2,2-PCA |
|---------------|------------------|--------------------------|---------|--------------------|---------------|---------|-------------|------------|-----------|----------------------|---------|-------|-----------|------|-------------|-------------|
| B-1000N       | BDL <sup>a</sup> | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 19.8  | BDL       | 5.11 | BDL         | BDL         |
| B-800N        | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 9.00  | BDL       | 16.4 | BDL         | BDL         |
| B-600N        | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | 6.62 | BDL         | BDL         |
| B-400N        | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | BDL  | BDL         | BDL         |
| B-200N        | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 19.6       | BDL       | BDL                  | BDL     | BDL   | BDL       | BDL  | BDL         | BDL         |
| B-00          | BDL              | 154                      | BDL     | BDL                | BDL           | BDL     | BDL         | 21.8       | BDL       | BDL                  | BDL     | 13.2  | BDL       | 17.1 | BDL         | BDL         |
| B-600S        | BDL              | 10.3                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 10.9  | BDL       | 12.2 | BDL         | BDL         |
| B-800S        | BDL              | 3.07                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | 30.8 | BDL         | BDL         |
| C-400N        | BDL              | 198                      | 415     | 7,180              | BDL           | 2,550   | 6,600       | 35.3       | 1,630     | BDL                  | BDL     | 2,680 | BDL       | 303  | BDL         | BDL         |
| C-200N        | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | 12.3 | BDL         | BDL         |
| C-00          | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 44.6       | BDL       | BDL                  | BDL     | BDL   | BDL       | BDL  | BDL         | BDL         |
| C-400S        | BDL              | 1.91                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 35.6  | BDL       | 27.2 | BDL         | BDL         |
| C-600S        | BDL              | 43.8                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 87.3  | BDL       | 32.3 | BDL         | BDL         |
| D-3600N       | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | 2.30 | BDL         | BDL         |
| D-3400N       | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | 4.28 | BDL         | BDL         |
| D-3200N       | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 3.74       | BDL       | BDL                  | BDL     | 3.60  | BDL       | 2.16 | BDL         | BDL         |
| D-3000N       | BDL              | 206                      | BDL     | BDL                | BDL           | BDL     | BDL         | 8.56       | BDL       | 3.38                 | BDL     | 38.0  | BDL       | 12.6 | BDL         | BDL         |
| D-200N        | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | BDL  | BDL         | BDL         |
| D-00          | BDL              | 38.3                     | BDL     | BDL                | BDL           | BDL     | BDL         | 20.8       | BDL       | BDL                  | BDL     | 13.3  | BDL       | 12.1 | BDL         | BDL         |
| D-200S        | BDL              | 1,060                    | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 37.2  | BDL       | 24.3 | BDL         | BDL         |
| D-400S        | BDL              | 202                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 16.6  | BDL       | 34.1 | BDL         | BDL         |
| D-600S        | BDL              | 10.1                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 12.8  | BDL       | 32.6 | BDL         | BDL         |
| D-800S        | BDL              | 21.8                     | BDL     | BDL                | BDL           | BDL     | BDL         | 186        | BDL       | BDL                  | BDL     | 166   | BDL       | 8.56 | BDL         | BDL         |
| D-1000S       | BDL              | 2,250                    | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 11.8  | BDL       | 4.63 | BDL         | BDL         |
| D-1200S       | BDL              | 185                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL   | BDL       | BDL  | BDL         | BDL         |
| D-1400S       | BDL              | 6.34                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 33.9  | BDL       | 10.9 | BDL         | BDL         |
| E-3800N       | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 12.5  | BDL       | 3.47 | BDL         | BDL         |
| E-3000N       | BDL              | 5.20                     | BDL     | BDL                | BDL           | BDL     | BDL         | 39.5       | BDL       | BDL                  | BDL     | 96.3  | BDL       | 31.5 | BDL         | BDL         |
| E-2600N       | BDL              | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 18.1  | BDL       | BDL  | BDL         | BDL         |

TABLE 5-1 (Continued)

**CHLORINATED VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Vinyl Chloride | Trichloro-fluoro-methane | 1,1-DCE | Methylene Chloride | trans-1,2-DCE | 1,1-DCA | cis-1,2-DCE | Chloroform | 1,1,1-TCA | Carbon Tetrachloride | 1,2-DCA | TCE  | 1,1,2-TCA | PCE  | 1,1,1,2-PCA | 1,1,2,2-PCA |
|---------------|----------------|--------------------------|---------|--------------------|---------------|---------|-------------|------------|-----------|----------------------|---------|------|-----------|------|-------------|-------------|
| E-200N        | BDL            | 10,010                   | BDL     | BDL                | BDL           | BDL     | BDL         | 24.4       | BDL       | BDL                  | BDL     | 130  | BDL       | 317  | BDL         | BDL         |
| E-00          | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 10.2       | BDL       | BDL                  | BDL     | 59.0 | BDL       | 19.9 | BDL         | BDL         |
| E-200S        | BDL            | 2,880                    | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 19.5 | BDL       | 105  | BDL         | BDL         |
| E-400S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 52.0       | BDL       | BDL                  | BDL     | BDL  | BDL       | 9.03 | BDL         | BDL         |
| E-600S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| E-1000S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 2.89 | BDL         | BDL         |
| F-3600N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 11.2 | BDL         | BDL         |
| F-3200N       | BDL            | 690                      | BDL     | BDL                | BDL           | BDL     | BDL         | 15.4       | BDL       | BDL                  | BDL     | 29.8 | BDL       | 40.5 | BDL         | BDL         |
| F-3000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| F-400S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 19.4       | BDL       | BDL                  | BDL     | BDL  | BDL       | 6.68 | BDL         | BDL         |
| F-600S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 12.0       | BDL       | BDL                  | BDL     | BDL  | BDL       | 7.33 | BDL         | BDL         |
| F-800S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 2.06 | BDL         | BDL         |
| F-1200S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 20.1       | BDL       | BDL                  | BDL     | 10.8 | BDL       | BDL  | BDL         | BDL         |
| G-3400N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 50.2 | BDL       | 14.9 | BDL         | BDL         |
| G-3200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 8.26 | BDL       | 2.76 | BDL         | BDL         |
| G-00          | BDL            | 334                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 229  | BDL       | 36.4 | BDL         | BDL         |
| G-200S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| G-400S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| G-600S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| G-800S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 10.8 | BDL         | BDL         |
| G-1000S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| G-1200S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| G-1400S       | BDL            | 453                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 37.7 | BDL       | 107  | BDL         | BDL         |
| H-3000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | 25.4      | BDL                  | BDL     | 254  | BDL       | 439  | BDL         | BDL         |
| H-2600N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 13.7 | BDL       | 4.59 | BDL         | BDL         |
| H-2200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 21.5 | BDL       | 3.31 | BDL         | BDL         |
| H-1800N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 10.6       | BDL       | BDL                  | BDL     | 7.58 | BDL       | BDL  | BDL         | BDL         |
| H-00          | BDL            | 42.0                     | BDL     | BDL                | BDL           | 14,200  | BDL         | BDL        | BDL       | BDL                  | BDL     | 95.2 | BDL       | 5.20 | BDL         | BDL         |

TABLE 5-1 (Continued)

**CHLORINATED VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Vinyl Chloride | Trichloro-fluoro-methane | 1,1-DCE | Methylene Chloride | trans-1,2-DCE | 1,1-DCA | cis-1,2-DCE | Chloroform | 1,1,1-TCA | Carbon Tetrachloride | 1,2-DCA | TCE  | 1,1,2-TCA | PCE  | 1,1,1,2-PCA | 1,1,2,2-PCA |
|---------------|----------------|--------------------------|---------|--------------------|---------------|---------|-------------|------------|-----------|----------------------|---------|------|-----------|------|-------------|-------------|
| H-200S        | BDL            | 9.35                     | 745     | BDL                | 6,980         | BDL     | 6,990       | 55.0       | BDL       | BDL                  | BDL     | 32.2 | BDL       | 10.0 | BDL         | BDL         |
| H-400S        | BDL            | 103                      | 12,600  | BDL                | BDL           | 25,320  | 71,220      | BDL        | BDL       | BDL                  | BDL     | 15.1 | BDL       | 10.9 | BDL         | BDL         |
| H-600S        | BDL            | 2.03                     | BDL     | BDL                | BDL           | BDL     | BDL         | 39.2       | BDL       | BDL                  | BDL     | 72.1 | BDL       | 55.4 | BDL         | BDL         |
| H-800S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 28.4       | BDL       | BDL                  | BDL     | 21.3 | BDL       | 4.36 | BDL         | BDL         |
| H-1000S       | BDL            | 1.24                     | BDL     | BDL                | BDL           | BDL     | BDL         | 28.0       | BDL       | BDL                  | BDL     | 12.9 | BDL       | 11.8 | BDL         | BDL         |
| H-1200S       | BDL            | 19.3                     | BDL     | BDL                | BDL           | BDL     | BDL         | 12.1       | BDL       | BDL                  | BDL     | 16.2 | BDL       | 18.6 | BDL         | BDL         |
| H-1400S       | BDL            | 166                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | 5.81      | BDL                  | BDL     | 50.2 | BDL       | 15.8 | BDL         | BDL         |
| I-2800N       | BDL            | 263                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | 21.1      | BDL                  | BDL     | 65.5 | BDL       | 24.8 | BDL         | BDL         |
| I-2600N       | BDL            | 8.86                     | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 15.0 | BDL       | 12.9 | BDL         | BDL         |
| I-2400N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| I-2000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 71.6       | BDL       | BDL                  | BDL     | 20.9 | BDL       | 14.6 | BDL         | BDL         |
| I-1800N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 58.3       | BDL       | BDL                  | BDL     | 20.2 | BDL       | 2.15 | BDL         | BDL         |
| I-1400N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 16.9       | BDL       | BDL                  | BDL     | 12.4 | BDL       | 19.9 | BDL         | BDL         |
| I-1200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| I-1000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 117        | BDL       | BDL                  | BDL     | 57.6 | BDL       | BDL  | BDL         | BDL         |
| I-00          | BDL            | 9.03                     | 411     | BDL                | BDL           | 3,640   | 9,100       | 21.5       | BDL       | BDL                  | BDL     | 35.1 | BDL       | 13.1 | BDL         | BDL         |
| I-200S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 25.6 | BDL       | 7.06 | BDL         | BDL         |
| I-400S        | BDL            | 7.90                     | BDL     | BDL                | BDL           | BDL     | BDL         | 22.5       | BDL       | BDL                  | BDL     | 30.3 | BDL       | 38.9 | BDL         | BDL         |
| I-600S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 19.7       | BDL       | BDL                  | BDL     | 11.3 | BDL       | 7.56 | BDL         | BDL         |
| I-800S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| I-1000S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 10.2       | BDL       | BDL                  | BDL     | 17.3 | BDL       | 12.4 | BDL         | BDL         |
| I-1200S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 4.91 | BDL         | BDL         |
| I-1400S       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 7.04 | BDL         | BDL         |
| J-2200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 2.22 | BDL         | BDL         |
| J-2015N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 11.8 | BDL       | 10.6 | BDL         | BDL         |
| J-1800N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 125        | BDL       | BDL                  | BDL     | 31.1 | BDL       | 5.91 | BDL         | BDL         |
| J-1400N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | 6.56      | BDL                  | BDL     | BDL  | BDL       | 27.9 | BDL         | BDL         |
| J-1200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |

TABLE 5-1 (Continued)

**CHLORINATED VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Vinyl Chloride | Trichloro-fluoro-methane | 1,1-DCE | Methylene Chloride | trans-1,2-DCE | 1,1-DCA | cis-1,2-DCE | Chloroform | 1,1,1-TCA | Carbon Tetrachloride | 1,2-DCA | TCE  | 1,1,2-TCA | PCE  | 1,1,1,2-PCA | 1,1,2,2-PCA |
|---------------|----------------|--------------------------|---------|--------------------|---------------|---------|-------------|------------|-----------|----------------------|---------|------|-----------|------|-------------|-------------|
| J-1000N       | BDL            | BDL                      | 198     | BDL                | 1,680         | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 7.70 | BDL         | BDL         |
| J-800N        | BDL            | BDL                      | BDL     | 1,990              | BDL           | BDL     | 2,700       | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 11.6 | 34.3        | BDL         |
| J-600S        | BDL            | 82.9                     | BDL     | BDL                | BDL           | BDL     | BDL         | 127        | BDL       | BDL                  | BDL     | 27.0 | BDL       | 22.6 | BDL         | BDL         |
| J-800S        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | 5.68      | BDL                  | BDL     | 300  | BDL       | 175  | BDL         | BDL         |
| J-1000S       | BDL            | 12.0                     | BDL     | BDL                | BDL           | BDL     | BDL         | 47.1       | BDL       | BDL                  | BDL     | 14.2 | BDL       | 12.6 | BDL         | BDL         |
| J-1200S       | BDL            | 382                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 17.6 | BDL       | 11.9 | BDL         | BDL         |
| K-2200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 7.37 | BDL       | 14.2 | BDL         | BDL         |
| K-2000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| K-1800N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| K-1600N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| K-1400N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | 15.0       | BDL       | BDL                  | BDL     | 45.9 | BDL       | 3.42 | BDL         | BDL         |
| K-1200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 2.58 | BDL         | BDL         |
| K-1000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 3.14 | BDL         | BDL         |
| K-800N        | BDL            | 1.94                     | BDL     | BDL                | BDL           | BDL     | BDL         | 57.9       | BDL       | BDL                  | BDL     | 39.3 | BDL       | 2.21 | BDL         | BDL         |
| L-2000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 8.80 | BDL         | BDL         |
| L-1800N       | BDL            | 1.45                     | BDL     | BDL                | BDL           | BDL     | BDL         | 32.1       | BDL       | BDL                  | BDL     | BDL  | BDL       | 17.5 | BDL         | BDL         |
| L-1400N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |
| L-1200N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | 12.3 | BDL       | 6.57 | BDL         | BDL         |
| L-1000N       | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | 4.76 | BDL         | BDL         |
| L-800N        | BDL            | BDL                      | BDL     | BDL                | BDL           | BDL     | BDL         | BDL        | BDL       | BDL                  | BDL     | BDL  | BDL       | BDL  | BDL         | BDL         |

Note:

<sup>a</sup> BDL = Below laboratory method detection limits

TABLE 5-2

**AROMATIC AND OTHER VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Methyl tert-Butyl Ether | Methyl Ethyl Ketone | Benzene | MIBK  | Toluene | Chlorobenzene | Ethylbenzene | Total Xylenes |
|---------------|-------------------------|---------------------|---------|-------|---------|---------------|--------------|---------------|
| B-1000N       | BDL <sup>a</sup>        | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | 8,040         |
| B-800N        | 823                     | BDL                 | BDL     | 931   | 91.0    | BDL           | 393          | 2,460         |
| B-600N        | 737                     | BDL                 | 288     | 6,920 | 347     | BDL           | 1,240        | 6,120         |
| B-400N        | 302                     | BDL                 | BDL     | 4,620 | BDL     | 640           | BDL          | 2,290         |
| B-200N        | 336                     | BDL                 | 1,240   | 1,610 | 11,400  | BDL           | 2,280        | 6,950         |
| B-00          | 665                     | BDL                 | 774     | 2,000 | 99.5    | BDL           | 1,100        | 5,060         |
| B-600S        | BDL                     | BDL                 | 264     | 1,600 | 394     | BDL           | 313          | 908           |
| B-800S        | 547                     | BDL                 | 145     | 382   | 275     | BDL           | 117          | 404           |
| C-400N        | 204                     | BDL                 | 932     | 787   | 4,880   | BDL           | 678          | 2,030         |
| C-200N        | BDL                     | BDL                 | 161     | 1,210 | 116     | 798           | 214          | 1,330         |
| C-00          | BDL                     | BDL                 | 1,080   | 9,190 | BDL     | BDL           | 2,400        | 23,390        |
| C-400S        | 647                     | BDL                 | 1,320   | 4,490 | BDL     | BDL           | 557          | 2,180         |
| C-600S        | BDL                     | BDL                 | BDL     | 542   | BDL     | BDL           | 427          | 162           |
| D-3600N       | BDL                     | BDL                 | BDL     | 260   | BDL     | BDL           | 195          | 530           |
| D-3400N       | BDL                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | BDL           |
| D-3200N       | 180                     | BDL                 | 452     | 2,660 | 222     | BDL           | 838          | 3,550         |
| D-3000N       | 220                     | BDL                 | 1,270   | 7,870 | 1,710   | BDL           | 2,560        | 7,130         |
| D-200N        | BDL                     | BDL                 | 1,070   | BDL   | 220     | 9,200         | BDL          | 1,110         |
| D-00          | 722                     | BDL                 | 1,280   | 8,890 | 236     | BDL           | BDL          | 11,050        |
| D-200S        | 287                     | BDL                 | 3,100   | 5,870 | 5,600   | BDL           | 9,070        | 22,160        |
| D-400S        | 169                     | BDL                 | 396     | 831   | 315     | BDL           | 684          | 1,610         |
| D-600S        | BDL                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | BDL           |
| D-800S        | 4,710                   | BDL                 | 4,580   | 1,490 | 451     | BDL           | 297          | 825           |
| D-1000S       | 183                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | 351           |

TABLE 5-1 (Continued)

**AROMATIC AND OTHER VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Methyl tert-Butyl Ether | Methyl Ethyl Ketone | Benzene | MIBK   | Toluene | Chlorobenzene | Ethylbenzene | Total Xylenes |
|---------------|-------------------------|---------------------|---------|--------|---------|---------------|--------------|---------------|
| D-1200S       | 783                     | BDL                 | 194     | 1,390  | 189     | BDL           | 489          | 1,810         |
| D-1400S       | BDL                     | BDL                 | 172     | 422    | 866     | BDL           | 277          | 1,870         |
| E-3800N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | 294           |
| E-3000N       | 2,050                   | BDL                 | 4,290   | 7,640  | 715     | BDL           | 4,010        | 10,910        |
| E-2600N       | BDL                     | BDL                 | 149     | 414    | 90.5    | BDL           | 246          | 884           |
| E-200N        | BDL                     | BDL                 | 2,670   | 20,870 | 8,400   | BDL           | 16,670       | 78,500        |
| E-00          | 777                     | 385                 | 1,320   | 4,960  | 2,450   | BDL           | 6,180        | 17,500        |
| E-200S        | 221                     | BDL                 | 123     | 1,990  | 1,140   | BDL           | 345          | 1,350         |
| E-400S        | BDL                     | BDL                 | 689     | 7,060  | BDL     | BDL           | 355          | 5,640         |
| E-600S        | 1,230                   | BDL                 | 1,440   | 2,730  | 226     | BDL           | 2,140        | 5,300         |
| E-1000S       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| F-3600N       | BDL                     | BDL                 | BDL     | 5,950  | 450     | BDL           | 1,410        | 8,150         |
| F-3200N       | BDL                     | BDL                 | 740     | 2,920  | 918     | BDL           | 1,930        | 7,520         |
| F-3000N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | 125          | 404           |
| F-400S        | 537                     | BDL                 | 441     | 3,200  | 222     | 362           | 506          | 1,920         |
| F-600S        | 2,270                   | BDL                 | 4,500   | 7,860  | 626     | BDL           | 6,170        | 15,610        |
| F-800S        | BDL                     | BDL                 | 107     | 597    | BDL     | BDL           | 273          | 1,070         |
| F-1200S       | 377                     | BDL                 | 490     | 2,160  | 199     | BDL           | 3,100        | 9,390         |
| G-3400N       | 222                     | BDL                 | 254     | 1,480  | 807     | BDL           | 600          | 2,120         |
| G-3200N       | BDL                     | BDL                 | 135     | 885    | 140     | BDL           | 188          | 459           |
| G-00          | 810                     | BDL                 | 4,790   | 1,550  | 19,650  | BDL           | 4,960        | 13,350        |
| G-200S        | 894                     | BDL                 | 470     | 1,050  | 69.4    | BDL           | BDL          | 674           |

TABLE 5-1 (Continued)

**AROMATIC AND OTHER VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Methyl tert-Butyl Ether | Methyl Ethyl Ketone | Benzene | MIBK   | Toluene | Chlorobenzene | Ethylbenzene | Total Xylenes |
|---------------|-------------------------|---------------------|---------|--------|---------|---------------|--------------|---------------|
| G-400S        | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| G-600S        | 382                     | BDL                 | 363     | 1,530  | 65.9    | BDL           | 143          | 696           |
| G-800S        | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| G-1000S       | BDL                     | BDL                 | 840     | 1,280  | 258     | BDL           | 156          | 751           |
| G-1200S       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | 130          | 395           |
| G-1400S       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| H-3000N       | 235                     | BDL                 | 762     | 1,300  | 1,100   | BDL           | 906          | 4,220         |
| H-2600N       | 535                     | BDL                 | 926     | BDL    | 4,200   | BDL           | 1,130        | 10,700        |
| H-2200N       | 834                     | BDL                 | 2,120   | 4,610  | 1,170   | BDL           | 2,620        | 15,020        |
| H-1800N       | 1,280                   | BDL                 | 2,190   | 2,770  | 491     | BDL           | BDL          | 1,460         |
| H-00          | 869                     | BDL                 | 2,510   | 2,300  | 65.0    | BDL           | 375          | 1,490         |
| H-200S        | 5,860                   | BDL                 | 3,380   | 1,230  | BDL     | BDL           | 212          | 1,110         |
| H-400S        | 1,180                   | BDL                 | 3,310   | 4,100  | 956     | BDL           | 2,350        | 9,100         |
| H-600S        | BDL                     | BDL                 | 3,260   | 9,990  | 17,370  | BDL           | 9,860        | 38,200        |
| H-800S        | 431                     | BDL                 | 565     | 2,360  | 158     | 2,770         | 1,620        | 3,240         |
| H-1000S       | BDL                     | BDL                 | 2,200   | 3,490  | 9,940   | BDL           | 3,130        | 8,940         |
| H-1200S       | BDL                     | BDL                 | BDL     | 14,010 | 1,260   | BDL           | 9,340        | 32,480        |
| H-1400S       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | 279          | 821           |
| I-2800N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| I-2600N       | 526                     | BDL                 | 261     | BDL    | BDL     | BDL           | BDL          | 184           |
| I-2400N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| I-2000N       | 612                     | BDL                 | 396     | 297    | 76.4    | BDL           | 106          | 155           |



TABLE 5-1 (Continued)

**AROMATIC AND OTHER VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Methyl tert-Butyl Ether | Methyl Ethyl Ketone | Benzene | MIBK   | Toluene | Chlorobenzene | Ethylbenzene | Total Xylenes |
|---------------|-------------------------|---------------------|---------|--------|---------|---------------|--------------|---------------|
| I-1800N       | 1,140                   | BDL                 | 2,010   | 1,360  | 138     | BDL           | 155          | 408           |
| I-1400N       | 1,190                   | BDL                 | BDL     | 3,710  | BDL     | BDL           | 1,670        | 3,690         |
| I-1200N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| I-1000N       | 523                     | BDL                 | 2,910   | 1,410  | 100     | 1,290         | BDL          | BDL           |
| I-00          | 612                     | BDL                 | 1,130   | 1,710  | BDL     | BDL           | 2,050        | 4,410         |
| I-200S        | BDL                     | BDL                 | BDL     | 3,420  | BDL     | BDL           | 1,500        | 2,390         |
| I-400S        | BDL                     | BDL                 | 4,490   | 4,570  | 434     | BDL           | 6,240        | 4,980         |
| I-600S        | BDL                     | BDL                 | BDL     | 4,690  | 831     | BDL           | 567          | 1,920         |
| I-800S        | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | 254           |
| I-1000S       | BDL                     | BDL                 | 3,750   | 7,360  | BDL     | BDL           | BDL          | 11,800        |
| I-1200S       | BDL                     | BDL                 | 1,020   | 4,950  | 1,040   | BDL           | 24,300       | 113,700       |
| I-1400S       | BDL                     | BDL                 | BDL     | 2,060  | BDL     | BDL           | 956          | 2,160         |
| J-2200N       | BDL                     | BDL                 | 190     | BDL    | BDL     | BDL           | 108          | 72.8          |
| J-2015N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| J-1800N       | 1,900                   | BDL                 | 2,510   | 1,530  | 134     | BDL           | 120          | 205           |
| J-1400N       | 1,420                   | BDL                 | BDL     | 4,430  | BDL     | BDL           | 739          | 2,170         |
| J-1200N       | BDL                     | BDL                 | BDL     | BDL    | BDL     | BDL           | BDL          | BDL           |
| J-1000N       | 1,170                   | BDL                 | BDL     | 454    | BDL     | BDL           | 184          | 413           |
| J-800N        | BDL                     | BDL                 | 4,700   | 1,690  | BDL     | BDL           | BDL          | 354           |
| J-600S        | 1,320                   | BDL                 | 2,540   | 12,490 | 2,520   | BDL           | 12,100       | 36,050        |
| J-800S        | 734                     | BDL                 | 2,520   | BDL    | 12,120  | BDL           | 3,460        | 8,470         |
| J-1000S       | BDL                     | BDL                 | 995     | 5,470  | 4,550   | BDL           | 4,770        | 13,460        |

TABLE 5-2 (Continued)

**AROMATIC AND OTHER VOC CONCENTRATIONS IN SOIL GAS**  
(Results in ppb)

| Sample Number | Methyl tert-Butyl Ether | Methyl Ethyl Ketone | Benzene | MIBK  | Toluene | Chlorobenzene | Ethylbenzene | Total Xylenes |
|---------------|-------------------------|---------------------|---------|-------|---------|---------------|--------------|---------------|
| J-1200S       | 351                     | BDL                 | 251     | 2,740 | 1,980   | BDL           | 1,130        | 4,110         |
| K-2200N       | BDL                     | BDL                 | 339     | 1,550 | 108     | BDL           | 658          | 5,480         |
| K-2000N       | 438                     | BDL                 | BDL     | 1,330 | 453     | BDL           | 220          | 838           |
| K-1800N       | BDL                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | BDL           |
| K-1600N       | BDL                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | BDL           |
| K-1400N       | 2,020                   | BDL                 | 3,340   | 5,240 | 725     | 1,340         | BDL          | 1,170         |
| K-1200N       | BDL                     | BDL                 | 1,510   | 5,110 | 362     | 1,720         | BDL          | 1,730         |
| K-1000N       | BDL                     | BDL                 | 385     | 1,060 | BDL     | 304           | BDL          | 1,150         |
| K-800N        | 414                     | BDL                 | 2,720   | 805   | BDL     | BDL           | BDL          | 111           |
| L-2000N       | BDL                     | BDL                 | BDL     | 2,340 | 429     | BDL           | 282          | 1,770         |
| L-1800N       | 382                     | BDL                 | 79.0    | 691   | 56.2    | BDL           | BDL          | 165           |
| L-1400N       | BDL                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | BDL           |
| L-1200N       | BDL                     | BDL                 | 1,270   | 7,910 | 6,900   | BDL           | 7,440        | 35,600        |
| L-1000N       | 3,190                   | BDL                 | 455     | 3,160 | BDL     | BDL           | 1,060        | 10,400        |
| L-800N        | BDL                     | BDL                 | BDL     | BDL   | BDL     | BDL           | BDL          | BDL           |

Note:

<sup>a</sup> BDL = Below laboratory method detection limits

TABLE 5-3

**VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CLP DATA**  
**(Results in ppb)**

| VOC                            | A800N            | A400N | B2600N             | B1800N | B1800ND | B1400N           | B00   | B00D  | B400S | B800S | B1200S | B1600S | B2000S | RAL             |
|--------------------------------|------------------|-------|--------------------|--------|---------|------------------|-------|-------|-------|-------|--------|--------|--------|-----------------|
| Chloroethane                   | BDL <sup>a</sup> | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | 20    | BDL    | BDL    | BDL    | .. <sup>b</sup> |
| Methylene chloride             | BDL              | BDL   | 10 UJ <sup>c</sup> | BDL    | 10 UJ   | BDL              | 10 UJ | 10 UJ | 10 UJ | 10 UJ | 10 UJ  | 10 UJ  | BDL    | 50              |
| Acetone                        | 10 UJ            | 75 UJ | BDL                | 27 UJ  | BDL     | 20 UJ            | 15 UJ | BDL   | 16 UJ | 17 UJ | 12 UJ  | 14 UJ  | 15 UJ  | 700             |
| Carbon disulfide               | BDL              | BDL   | BDL                | BDL    | BDL     | 1 J <sup>d</sup> | 2 J   | 2 J   | BDL   | BDL   | BDL    | BDL    | BDL    | 700             |
| 1,1-DCE                        | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | 9 J*   | 6               |
| 1,1-DCA                        | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | 70              |
| 1,2-DCE(total)                 | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | --              |
| 2-Butanone                     | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | 300             |
| 1,1,1-TCA                      | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | 600             |
| TCE                            | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | 30              |
| Benzene                        | BDL              | BDL   | 10 UJ              | BDL    | BDL     | BDL              | 10    | 11    | 18    | 38    | 23     | 27     | BDL    | 10              |
| 4-Methyl-2-pentanone           | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | 300             |
| 2-Hexanone                     | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | --              |
| Toluene                        | 10 UJ            | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | 4 J   | 1 J    | 2 J    | BDL    | 1,000           |
| Chlorobenzene                  | BDL              | BDL   | 3 J                | BDL    | BDL     | BDL              | 51    | 54    | BDL   | BDL   | BDL    | 12     | BDL    | 100             |
| Ethylbenzene                   | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | 10    | BDL    | 50     | BDL    | 700             |
| Xylenes (total)                | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | 79    | BDL    | 35     | BDL    | 1,000           |
| Total VOCs                     | BDL              | BDL   | 3                  | BDL    | BDL     | 1                | 63    | 67    | 18    | 151   | 24     | 126    | 9      |                 |
| TIC                            |                  |       |                    |        |         |                  |       |       |       |       |        |        |        |                 |
| Hydrocarbons                   | 6 J              | 12 J  | BDL                | 11 J   | BDL     | BDL              | 7 J   | 8 J   | 28 J  | 14 J  | 7 J    | BDL    | 10 J   |                 |
| Oxygenated hydrocarbons        | BDL              | 26 J  | BDL                | BDL    | BDL     | 8 J              | 18 J  | 18 J  | 44 J  | 79 J  | BDL    | BDL    | BDL    |                 |
| Alkylaromatic hydrocarbons     | BDL              | 6 J   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | 17 J  | 12 J  | 17 J   | 260 J  | BDL    |                 |
| Cyclic oxygenated hydrocarbons | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    |                 |
| Oxygenated aromatics           | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | 7 J    | 220 J  | BDL    |                 |
| Amides and amines              | 7 J              | 13 J  | BDL                | 5 J    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | 5 J    | BDL    | BDL    |                 |
| Halogenated aromatics          | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    |                 |
| PAHs                           | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | 490 J  | BDL    | BDL    |                 |
| Nitriles                       | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | 9 J   | 8 J   | 5 J   | BDL   | BDL    | BDL    | BDL    |                 |
| Heterocyclic aromatics         | BDL              | BDL   | BDL                | BDL    | BDL     | BDL              | BDL   | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    |                 |
| Total TICs                     | 13               | 57    | BDL                | 16     | BDL     | 8                | 34    | 34    | 94    | 105   | 526    | 480    | 10     |                 |

TABLE 5-3 (Continued)

**VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CLP DATA**  
**(Results in ppb)**

| VOC                            | C2200N | C800N | C400N | D3600N | D3000N | D1400N | D1600S | E2600N | E600N | E00   | E600S | E1200S | F3600N | RAL    |
|--------------------------------|--------|-------|-------|--------|--------|--------|--------|--------|-------|-------|-------|--------|--------|--------|
| Chloroethane                   | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | —      |
| Methylene chloride             | BDL    | 31 UJ | BDL   | 10 UJ  | 10 UJ  | BDL    | BDL    | BDL    | 10 UJ | BDL   | 10 UJ | 12 UJ  | BDL    | 50     |
| Acetone                        | 17 UJ  | 32 UJ | 20 UJ | 15 UJ  | 20 UJ  | 41 UJ  | 17 UJ  | 29 UJ  | BDL   | 10 UJ | 10 UJ | BDL    | 10 UJ  | 700    |
| Carbon disulfide               | 1 J    | 2 J   | 1 J   | 1 J    | 3 J    | 1 J    | 2 J    | 3 J    | BDL   | BDL   | BDL   | BDL    | 2 J    | 700    |
| 1,1-DCE                        | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 6      |
| 1,1-DCA                        | BDL    | 4 J   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 70     |
| 1,2-DCE(total)                 | BDL    | 12    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | 7 J   | BDL   | BDL    | BDL    | —      |
| 2-Butanone                     | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 300    |
| 1,1,1-TCA                      | BDL    | 4 J   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 600    |
| TCE                            | BDL    | 11    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | 2 J   | BDL   | BDL    | BDL    | 30     |
| Benzene                        | 8 J    | 12    | 8 J   | 6 J    | 8 J    | 2 J    | 13     | 6 J    | 10 UJ | 10 UJ | 10 UJ | 12 UJ  | 14     | 10     |
| 4-Methyl-2-pentanone           | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 300    |
| 2-Hexanone                     | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | —      |
| Toluene                        | BDL    | 43    | BDL   | BDL    | 4 J    | 1 J    | 2 J    | 2 J    | BDL   | 6 J   | BDL   | 5 J    | BDL    | 1,000  |
| Chlorobenzene                  | 4 J    | BDL   | BDL   | 15     | BDL    | BDL    | BDL    | BDL    | 1 J   | 2 J   | 3 J   | 11 J   | BDL    | 100    |
| Ethylbenzene                   | BDL    | 3 J   | BDL   | BDL    | BDL    | BDL    | 7 J    | BDL    | BDL   | R     | BDL   | 73     | BDL    | 700    |
| Xylenes (total)                | 19     | 15    | BDL   | BDL    | 35     | BDL    | 5 J    | 28     | 1 J   | 32    | 8 J   | 300 J  | 12     | 10,000 |
| Total VOCs                     | 32     | 106   | 9     | 22     | 50     | 4      | 29     | 39     | 2     | 65    | 11    | 389    | 28     |        |
| TIC                            |        |       |       |        |        |        |        |        |       |       |       |        |        |        |
| Hydrocarbons                   | 8 J    | 36 J  | 7 J   | 80 J   | 750 J  | 17 J   | BDL    | 26 J   | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Oxygenated hydrocarbons        | 9 J    | 79 J  | 22 J  | BDL    | 210 J  | 12 J   | BDL    | 39 J   | BDL   | BDL   | BDL   | BDL    | 6 J    |        |
| Alkylaromatic hydrocarbons     | 7 J    | BDL   | 6 J   | 300 J  | 9 J    | BDL    | 6 J    | BDL    | BDL   | BDL   | BDL   | 63 J   | 56 J   |        |
| Cyclic oxygenated hydrocarbons | BDL    | BDL   | BDL   | BDL    | 11 J   | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Oxygenated aromatics           | BDL    | BDL   | BDL   | 100 J  | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Amides and amines              | BDL    | BDL   | 16 J  | BDL    | BDL    | 6 J    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Halogenated aromatics          | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | 15 J   | BDL    |        |
| PAHs                           | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | 20 J   | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Nitriles                       | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Heterocyclic aromatics         | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    |        |
| Total TICs                     | 24     | 115   | 51    | 480    | 980    | 35     | 26     | 65     | BDL   | BDL   | BDL   | 78     | 62     |        |

TABLE 5-3 (Continued)

**VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CLP DATA**  
**(Results in ppb)**

| VOC                            | F3000N | F3000N-D | F2200N | F1600N | F1000N | F1600S | H2800N | H600N | H1600S | I1200N | I00   | J2400N | J800N | RAI   |
|--------------------------------|--------|----------|--------|--------|--------|--------|--------|-------|--------|--------|-------|--------|-------|-------|
| Chloroethane                   | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | 2 J    | BDL   | BDL    | BDL    | 2 J   | BDL    | BDL   | --    |
| Methylene chloride             | BDL    | BDL      | 10 UJ  | BDL    | BDL    | BDL    | 10 UJ  | 14 UJ | 10 UJ  | BDL    | 10 UJ | BDL    | BDL   | 50    |
| Acetone                        | 77 UJ  | 28 UJ    | 52 UJ  | BDL    | 15 UJ  | 20 UJ  | BDL    | BDL   | 26 UJ  | 19 UJ  | 40 UJ | 23 UJ  | 32 UJ | 700   |
| Carbon disulfide               | 2 J    | 2 J      | 2 J    | BDL    | BDL    | BDL    | BDL    | 1 J   | BDL    | BDL    | BDL   | 1 J    | BDL   | 700   |
| 1,1-DCE                        | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | 6     |
| 1,1-DCA                        | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | 70    |
| 1,2-DCE(total)                 | 10     | 14       | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | --    |
| 2-Butanone                     | 27 UJ  | BDL      | 77 UJ  | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | 300   |
| 1,1,1-TCA                      | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | 600   |
| TCE                            | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | 30    |
| Benzene                        | 12     | 12       | 10     | 10     | 16     | 1 J    | 11     | 5     | 6 J    | 7 J    | 60    | 2 J    | BDL   | 10    |
| 4-Methyl-2-pentanone           | BDL    | BDL      | 14     | BDL    | BDL    | BDL    | 2 J    | BDL   | BDL    | BDL    | 3 J   | BDL    | 2 J   | 300   |
| 2-Hexanone                     | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | 3 J    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | --    |
| Toluene                        | 16     | 21       | 6      | BDL    | BDL    | BDL    | BDL    | 1 J   | 1 J    | BDL    | 7     | BDL    | BDL   | 1,000 |
| Chlorobenzene                  | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | 4 J    | BDL   | BDL    | BDL    | 2 J   | BDL    | BDL   | 100   |
| Ethylbenzene                   | 44     | 55       | 8      | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | 31    | BDL    | BDL   | 700   |
| Xylenes (total)                | 240    | 300      | 54     | BDL    | BDL    | BDL    | 69     | 21    | BDL    | BDL    | 168   | BDL    | BDL   | 1,000 |
| Total VOCs                     | 324    | 404      | 94     | 10     | 16     | 1      | 91     | 28    | 7      | 7      | 273   | 3      | 2     |       |
| TIC                            |        |          |        |        |        |        |        |       |        |        |       |        |       |       |
| Hydrocarbons                   | 65 J   | 35 J     | BDL    | 31 J   | 22 J   | BDL    | BDL    | 45 J  | 190 J  | BDL    | BDL   | 17 J   | BDL   |       |
| Oxygenated hydrocarbons        | 62 J   | 46 J     | 55 J   | 57 J   | 8 J    | 23 J   | BDL    | BDL   | BDL    | 14 J   | BDL   | 30 J   | BDL   |       |
| Alkylaromatic hydrocarbons     | 44 J   | 110 J    | 18 J   | 84 J   | BDL    | BDL    | 290 J  | 17 J  | 52 J   | 52 J   | 120 J | BDL    | BDL   |       |
| Cyclic oxygenated hydrocarbons | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   |       |
| Oxygenated aromatics           | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | 24 J   | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   |       |
| Amides and amines              | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | 58 J   | 9 J    | BDL   | 5 J    | 6 J   |       |
| Halogenated aromatics          | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   |       |
| PAHs                           | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   |       |
| Nitriles                       | BDL    | BDL      | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   |       |
| Heterocyclic aromatics         | BDL    | BDL      | BDL    | BDL    | 5 J    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   |       |
| Total TICs                     | 171    | 191      | 73     | 172    | 35     | 23     | 314    | 62    | 300    | 75     | 120   | 52     | 6     |       |

TABLE 5-2 (Continued)

VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CLP DATA  
(Results in ppb)

| VOC                            | J600S | J1400S | J1400S-D | K1600N | L1200N | RAL    |
|--------------------------------|-------|--------|----------|--------|--------|--------|
| Chloroethane                   | 2 J   | BDL    | BDL      | BDL    | BDL    | --     |
| Methylene chloride             | 10 UJ | BDL    | BDL      | BDL    | BDL    | 50     |
| Acetone                        | 51 UJ | 23 UJ  | 19 UJ    | 20 UJ  | 32 UJ  | 700    |
| Carbon disulfide               | BDL   | BDL    | BDL      | BDL    | 2 J    | 700    |
| 1,1-DCE                        | BDL   | BDL    | BDL      | BDL    | BDL    | 6      |
| 1,1-DCA                        | BDL   | BDL    | BDL      | BDL    | BDL    | 70     |
| 1,2-DCE(total)                 | BDL   | BDL    | BDL      | BDL    | BDL    | --     |
| 2-Butanone                     | 14 UJ | BDL    | BDL      | BDL    | BDL    | 300    |
| 1,1,1-TCA                      | BDL   | BDL    | BDL      | BDL    | BDL    | 600    |
| TCE                            | BDL   | BDL    | BDL      | BDL    | BDL    | 30     |
| Benzene                        | 21    | 9 J    | 11       | 3 J    | 22     | 10     |
| 4-Methyl-2-pentanone           | BDL   | 7 J    | BDL      | BDL    | BDL    | 300    |
| 2-Hexanone                     | BDL   | BDL    | BDL      | BDL    | BDL    | --     |
| Toluene                        | 15    | BDL    | BDL      | 1 J    | 2 J    | 1,000  |
| Chlorobenzene                  | 1 J   | BDL    | 4 J      | BDL    | 27     | 100    |
| Ethylbenzene                   | 18    | BDL    | BDL      | BDL    | 7 J    | 700    |
| Xylenes (total)                | 106   | BDL    | BDL      | BDL    | 46     | 10,000 |
| Total VOCs                     | 163   | 16     | 15       | 4      | 106    |        |
| TIC                            |       |        |          |        |        |        |
| Hydrocarbons                   | BDL   | 6 J    | BDL      | 13 J   | BDL    |        |
| Oxygenated hydrocarbons        | BDL   | 14 J   | 25 J     | 5 J    | 7 J    |        |
| Alkylaromatic hydrocarbons     | 49 J  | 55 J   | 72 J     | BDL    | 70 J   |        |
| Cyclic oxygenated hydrocarbons | BDL   | BDL    | BDL      | BDL    | 8 J    |        |
| Oxygenated aromatics           | BDL   | BDL    | BDL      | BDL    | BDL    |        |
| Amides and amines              | BDL   | BDL    | BDL      | 7 J    | BDL    |        |
| Halogenated aromatics          | BDL   | BDL    | BDL      | BDL    | BDL    |        |
| PAHs                           | BDL   | BDL    | BDL      | BDL    | BDL    |        |
| Nitriles                       | BDL   | BDL    | BDL      | 10 J   | BDL    |        |
| Heterocyclic aromatics         | BDL   | BDL    | BDL      | BDL    | BDL    |        |
| Total TICs                     | 49    | 75     | 97       | 35     | 85     |        |

TABLE 5-5 (Continued)

VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CLP DATA  
(Results in ppb)

Notes:

- a BDL = Below laboratory method detection limits
  - b -- = RAL not assigned to analyte
  - c UJ = Estimated quantitation limit
  - d J = Estimated concentration value
  - e **Shaded bold values** indicate that concentration exceeds RAL
-

TABLE 5-4

**VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CSL DATA**  
**(Results in ppb)**

| Sample Number | Trichloro-fluoromethane | trans-1,2-DCE | 1,1,1-TCA | TCE  | PCE | Benzene           | Toluene | Chloro-benzene | Ethyl-benzene | Total Xylenes | 1,3-DCB | 1,4-DCB | 1,2-DCB |
|---------------|-------------------------|---------------|-----------|------|-----|-------------------|---------|----------------|---------------|---------------|---------|---------|---------|
| RAL           | 2,000                   | 100           | 600       | 30   | 7   | 10                | 1,000   | 100            | 700           | 10,000        | 600     | 10      | 600     |
| A-400N        | BDL <sup>a</sup>        | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| A-800N        | BDL                     | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| B-2600N       | BDL                     | BDL           | BDL       | BDL  | BDL | 2.05              | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| B-1800N       | BDL                     | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| B-1400N       | BDL                     | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| B-00          | BDL                     | BDL           | BDL       | BDL  | BDL | 8.73              | BDL     | 47.3           | BDL           | 3.70          | BDL     | BDL     | BDL     |
| B-400S        | BDL                     | BDL           | BDL       | BDL  | BDL | 18.5 <sup>b</sup> | BDL     | 2.82           | BDL           | 2.94          | BDL     | BDL     | BDL     |
| B-800S        | BDL                     | BDL           | BDL       | BDL  | BDL | 41.1              | 3.06    | BDL            | 9.09          | 82.5          | BDL     | BDL     | BDL     |
| B-1200S       | 9.27                    | BDL           | BDL       | BDL  | BDL | 25.6              | 2.98    | 9.50           | BDL           | 5.04          | 10.9    | 25.0    | BDL     |
| B-1600S       | 1.79                    | BDL           | BDL       | BDL  | BDL | 29.1              | BDL     | 9.17           | 22.4          | 18.8          | 21.3    | 46.4    | 32.0    |
| B-2000S       | BDL                     | 12.9          | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| C-2200N       | BDL                     | BDL           | BDL       | BDL  | BDL | 4.23              | BDL     | BDL            | BDL           | 3.43          | BDL     | BDL     | BDL     |
| C-800N        | BDL                     | BDL           | BDL       | BDL  | BDL | 6.27              | BDL     | 2.25           | BDL           | BDL           | BDL     | BDL     | BDL     |
| C-400N        | BDL                     | BDL           | 1.70      | 1.53 | BDL | 8.63              | 8.23    | BDL            | BDL           | 2.87          | BDL     | BDL     | BDL     |
| D-3600N       | BDL                     | BDL           | BDL       | BDL  | BDL | 3.89              | BDL     | 13.4           | BDL           | BDL           | BDL     | BDL     | BDL     |
| D-3000N       | BDL                     | BDL           | BDL       | BDL  | BDL | 6.49              | BDL     | 5.74           | BDL           | 11.5          | BDL     | 6.19    | BDL     |
| D-1400N       | BDL                     | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| D-1600S       | BDL                     | BDL           | BDL       | BDL  | BDL | 8.77              | BDL     | BDL            | BDL           | 15.2          | BDL     | BDL     | BDL     |
| E-2600N       | BDL                     | BDL           | BDL       | BDL  | BDL | 6.09              | BDL     | 3.68           | BDL           | 19.4          | 6.38    | 8.65    | BDL     |
| E-600N        | BDL                     | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| E-00          | BDL                     | BDL           | BDL       | BDL  | BDL | 5.20              | 3.13    | BDL            | 4.99          | 12.0          | BDL     | BDL     | BDL     |
| E-600S        | BDL                     | BDL           | BDL       | BDL  | BDL | 4.37              | BDL     | BDL            | BDL           | 6.07          | BDL     | BDL     | BDL     |
| E-1200S       | BDL                     | BDL           | BDL       | BDL  | BDL | 9.67              | 4.88    | 14.0           | 83.2          | 349           | 31.2    | 70.0    | BDL     |
| F-3600N       | BDL                     | BDL           | BDL       | BDL  | BDL | 5.00              | BDL     | 2.65           | BDL           | 12.6          | BDL     | BDL     | BDL     |
| F-3000N       | BDL                     | BDL           | BDL       | BDL  | BDL | BDL               | BDL     | BDL            | BDL           | BDL           | BDL     | BDL     | BDL     |
| F-2200N       | BDL                     | BDL           | BDL       | BDL  | BDL | 9.82              | 44.8    | 2.81           | 4.99          | 38.5          | 6.70    | BDL     | BDL     |
| F-1600N       | BDL                     | BDL           | BDL       | BDL  | BDL | 6.83              | BDL     | BDL            | BDL           | 3.60          | 11.1    | BDL     | BDL     |



TABLE 5-1 (Continued)

**VOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES - CSL DATA**  
(Results in ppb)

| Sample Number | Trichloro-fluoromethane | trans-1,2-DCE | 1,1,1-TCA | TCE | PCE | Benzene     | Toluene | Chloro-benzene | Ethyl-benzene | Total Xylenes | 1,3-DCB | 1,4-DCB     | 1,2-DCB |
|---------------|-------------------------|---------------|-----------|-----|-----|-------------|---------|----------------|---------------|---------------|---------|-------------|---------|
| F-1000N       | BDL                     | BDL           | BDL       | BDL | BDL | <b>10.4</b> | BDL     | BDL            | BDL           | BDL           | BDL     | BDL         | BDL     |
| F-1600S       | BDL                     | BDL           | BDL       | BDL | BDL | BDL         | BDL     | BDL            | BDL           | BDL           | BDL     | BDL         | BDL     |
| H-2800N       | BDL                     | BDL           | BDL       | BDL | BDL | <b>12.6</b> | BDL     | 7.28           | BDL           | 67.8          | BDL     | <b>61.5</b> | BDLS    |
| H-600N        | BDL                     | BDL           | BDL       | BDL | BDL | 4.53        | BDL     | BDL            | BDL           | 12.8          | 42.8    | <b>17.2</b> | BDL     |
| H-1600S       | BDL                     | BDL           | BDL       | BDL | BDL | 5.50        | BDL     | 2.55           | BDL           | BDL           | BDL     | 7.12        | BDL     |
| I-1200N       | BDL                     | BDL           | BDL       | BDL | BDL | 4.32        | BDL     | BDL            | BDL           | BDL           | BDL     | BDL         | BDL     |
| I-00          | BDL                     | BDL           | BDL       | BDL | BDL | <b>69.3</b> | 4.18    | 3.13           | 17.1          | 122           | 16.2    | <b>97.2</b> | BDL     |
| J-800N        | BDL                     | BDL           | BDL       | BDL | BDL | BDL         | BDL     | BDL            | BDL           | BDL           | BDL     | BDL         | BDL     |
| J-600S        | BDL                     | BDL           | BDL       | BDL | BDL | <b>27.9</b> | 13.9    | BDL            | BDL           | 140           | 20.6    | <b>40.1</b> | BDL     |
| J-1400S       | BDL                     | 13.9          | BDL       | BDL | BDL | <b>10.1</b> | BDL     | 3.70           | BDL           | 2.96          | BDL     | 8.03        | BDL     |
| K-1600N       | BDL                     | BDL           | BDL       | BDL | BDL | 1.21        | BDL     | BDL            | BDL           | BDL           | BDL     | BDL         | BDL     |
| L-1200N       | BDL                     | BDL           | BDL       | BDL | BDL | <b>17.0</b> | BDL     | 31.3           | 7.15          | 37.2          | BDL     | BDL         | BDL     |

Notes:

<sup>a</sup> BDL = Below laboratory method detection limits

<sup>b</sup> **Shaded bold values** indicate that concentration exceeds RAL

TABLE 5-5

**SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| SVOC                        | A800N            | A400N | B2600N | B1800N | B1800ND | B1400N | B00   | B00D  | B400S | B800S              | B1200S           | B1600S | B2000S | C2200N | C400N | C800N | RAL            |
|-----------------------------|------------------|-------|--------|--------|---------|--------|-------|-------|-------|--------------------|------------------|--------|--------|--------|-------|-------|----------------|
| Phenol                      | BDL <sup>a</sup> | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 4,000          |
| bis(2-Chloroethyl)ether     | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 0.3            |
| 1,4-DCB                     | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 3 J <sup>b</sup> | BDL    | BDL    | 2 J    | BDL   | BDL   | 10             |
| 1,2-DCB                     | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 600            |
| 2-Methylphenol              | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 30             |
| bis(2-Chloroisopropyl)ether | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 300            |
| 4-Methylphenol              | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | 20 J               | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 30             |
| Nitrobenzene                | BDL              | BDL   | BDL    | 2 J    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 3 J              | BDL    | BDL    | BDL    | BDL   | BDL   | 3              |
| Naphthalene                 | BDL              | 3 J   | BDL    | BDL    | BDL     | BDL    | 1 J   | 1 J   | BDL   | 7 J                | 59 <sup>c</sup>  | 350    | BDL    | BDL    | BDL   | BDL   | 30             |
| 2-Methylnaphthalene         | BDL              | 6 J   | BDL    | BDL    | BDL     | BDL    | 3 J   | 3 J   | 1 J   | 6 J                | 13 J             | 44 J   | BDL    | BDL    | 2 J   | 1 J   | — <sup>d</sup> |
| 2,4,6-Trichlorophenol       | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 30             |
| 2,4,5-Trichlorophenol       | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| 2-Chloronaphthalene         | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Acenaphthene                | BDL              | 22    | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 27 J             | 24 J   | BDL    | BDL    | BDL   | BDL   | 4,000          |
| Phenanthrene                | BDL              | 7 J   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 75               | 37 J   | BDL    | BDL    | BDL   | BDL   | —              |
| Dibenzofuran                | BDL              | 5 J   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 14 J             | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Diethyl phthalate           | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | 50 UJ <sup>e</sup> | 20 UJ            | BDL    | BDL    | BDL    | 10 UJ | BDL   | 6,000          |
| Fluorene                    | BDL              | 12    | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 17 J             | 16 J   | BDL    | BDL    | BDL   | BDL   | 300            |
| N-Nitrosodiphenylamine      | BDL              | BDL   | BDL    | 16     | 14      | 1 J    | 2 J   | 2 J   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | 3 J   | BDL   | 70             |
| Pentachlorophenol           | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 200            |
| Anthracene                  | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 14 J             | BDL    | BDL    | BDL    | BDL   | BDL   | 2,000          |
| Carbazole                   | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | 2 J   | 2 J   | 2 J   | BDL                | 20               | BDL    | BDL    | BDL    | BDL   | 3 J   | —              |
| Di-n-butyl phthalate        | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | 10 UJ | BDL   | 700            |
| Fluoranthene                | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 68               | BDL    | BDL    | BDL    | BDL   | BDL   | 300            |
| Pyrene                      | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 41 J             | BDL    | BDL    | BDL    | BDL   | BDL   | 200            |
| Butyl benzyl phthalate      | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | 100            |
| Benzo(a)anthracene          | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 16 J             | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Chrysene                    | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 24               | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Di-n-octyl phthalate        | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | BDL              | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| bis(2-Ethylhexyl)phthalate  | 10 UJ            | BDL   | 35 UJ  | 10 UJ  | 10 UJ   | 14 UJ  | 10 UJ | 10 UJ | 10 UJ | 50 UJ              | 20 UJ            | BDL    | 10 UJ  | 10 UJ  | 10 UJ | 10 UJ | —              |
| Benzo(b)fluoranthene        | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 17 J             | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Benzo(k)fluoranthene        | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 16 J             | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Benzo(a)pyrene              | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 18 J             | BDL    | BDL    | BDL    | BDL   | BDL   | —              |
| Indeno(1,2,3-cd)pyrene      | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL   | BDL   | BDL                | 13 J             | BDL    | BDL    | BDL    | BDL   | BDL   | —              |

**TABLE 5-5 (Continued)**  
**SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| SVOC                           | A800N | A400N | B2600N | B1800N | B1800ND | B1400N | B00   | B00D | B400S | B800S | B1200S | B1600S  | B2000S | C2200N | C400N | C800N | RAL |
|--------------------------------|-------|-------|--------|--------|---------|--------|-------|------|-------|-------|--------|---------|--------|--------|-------|-------|-----|
| Dibenzo(a,h)anthracene         | BDL   | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL  | BDL   | BDL   | 5 J    | BDL     | BDL    | BDL    | BDL   | BDL   | --  |
| Benzo(g,h,i)perylene           | BDL   | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL  | BDL   | BDL   | 14 J   | BDL     | BDL    | BDL    | BDL   | BDL   | --  |
| Total SVOCs                    | BDL   | 55    | BDL    | 18     | 14      | 1      | 8     | 8    | 3     | 33    | 477    | 471     | BDL    | 2      | 5     | 4     |     |
| TIC                            |       |       |        |        |         |        |       |      |       |       |        |         |        |        |       |       |     |
| Hydrocarbons                   | BDL   | BDL   | 24 J   | 13 J   | 25 J    | 10 J   | BDL   | 8 J  | BDL   | 54 J  | BDL    | 1,130 J | BDL    | 36 J   | BDL   | BDL   |     |
| Oxygenated hydrocarbons        | 2 J   | BDL   | 40 J   | 12 J   | 31 J    | 9 J    | 51 J  | 81 J | 81 J  | 810 J | 54 J   | 82 J    | 15 J   | 65 J   | 68 J  | 550 J |     |
| Alkylaromatic hydrocarbons     | 2 J   | BDL   | 5 J    | BDL    | BDL     | BDL    | 9 J   | 18 J | 14 J  | 22 J  | 17 J   | 81 J    | BDL    | 24 J   | 14 J  | 63 J  |     |
| Cyclic oxygenated hydrocarbons | BDL   | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL  | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    | BDL   | BDL   |     |
| Oxygenated aromatics           | BDL   | BDL   | 12 J   | 14 J   | 13 J    | 11 J   | 24 J  | 11 J | 84 J  | 42 J  | 34 J   | BDL     | 6 J    | 6 J    | 150 J | 90 J  |     |
| Heterocyclic aromatics         | 2 J   | BDL   | 10 J   | 50 J   | 40 J    | 10 J   | 130 J | 92 J | 32 J  | 25 J  | 19 J   | 21 J    | 10 J   | 17 J   | BDL   | 36 J  |     |
| Phosphoric acid esters         | BDL   | BDL   | BDL    | 6 J    | 5 J     | 5 J    | 45 J  | 38 J | 21 J  | BDL   | 24 J   | BDL     | 8 J    | 13 J   | BDL   | 26 J  |     |
| PAHs                           | 14 J  | 20 J  | BDL    | BDL    | BDL     | BDL    | BDL   | BDL  | BDL   | BDL   | 27 J   | 360 J   | 2 J    | BDL    | 8 J   | BDL   |     |
| Sulfur                         | BDL   | BDL   | 47 J   | BDL    | BDL     | 2 J    | BDL   | BDL  | BDL   | 64 J  | BDL    | 39 J    | 4 J    | BDL    | 26 J  | 150 J |     |
| Sulfonamides                   | BDL   | BDL   | 9 J    | 15 J   | 5 J     | 10 J   | 46 J  | 42 J | 38 J  | 20 J  | 24 J   | BDL     | 10 J   | 18 J   | 52 J  | 17 J  |     |
| Amines and amides              | BDL   | BDL   | BDL    | 9 J    | 2 J     | 4 J    | 10 J  | 10 J | BDL   | 570 J | BDL    | BDL     | BDL    | 8 J    | 8 J   | BDL   |     |
| Halogenated aromatics          | BDL   | BDL   | 7 J    | 2 J    | BDL     | BDL    | 7 J   | BDL  | BDL   | BDL   | BDL    | BDL     | BDL    | 8 J    | BDL   | BDL   |     |
| Nitriles                       | BDL   | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL  | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    | BDL   | BDL   |     |
| Miscellaneous                  | BDL   | BDL   | BDL    | BDL    | BDL     | BDL    | BDL   | BDL  | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    | BDL   | BDL   |     |
| Total TICs                     | 20    | 20    | 154    | 121    | 121     | 61     | 322   | 300  | 270   | 1,607 | 199    | 1,713   | 55     | 195    | 326   | 932   |     |

TABLE 5-5 (Continued)

**SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
(Results in ppb)

| SVOC                        | D3600N | D3000N | D1600S | E2600N | E600N | E00   | E600S | E1200S | F3600N | F3000N | F3000ND | F2200N | F1600N | F1000N | RAL   |
|-----------------------------|--------|--------|--------|--------|-------|-------|-------|--------|--------|--------|---------|--------|--------|--------|-------|
| Phenol                      | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 4,000 |
| bis(2-Chloroethyl)ether     | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 0.3   |
| 1,4-DCB                     | BDL    | BDL    | BDL    | 2 J    | BDL   | BDL   | BDL   | 11 J   | 2 J    | 2 J    | 2 J     | BDL    | 1 J    | BDL    | 10    |
| 1,2-DCB                     | BDL    | 2 J    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 2 J    | 2 J     | BDL    | BDL    | BDL    | 600   |
| 2-Methylphenol              | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 30    |
| bis(2-Chloroisopropyl)ether | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | 1 J    | BDL    | 300   |
| 4-Methylphenol              | BDL    | 7 J    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 30    |
| Nitrobenzene                | BDL    | BDL    | BDL    | 5 J    | BDL   | BDL   | BDL   | BDL    | 4 J    | BDL    | BDL     | BDL    | 12     | 21     | 3     |
| Naphthalene                 | BDL    | 6 J    | 8 J    | 3 J    | BDL   | 2 J   | 1 J   | 27     | BDL    | 5 J    | 5 J     | 4 J    | 1 J    | 1 J    | 30    |
| 2-Methylnaphthalene         | 160    | BDL    | BDL    | 1 J    | BDL   | BDL   | BDL   | 5 J    | 4 J    | 3 J    | 2 J     | 3 J    | 2 J    | BDL    | --    |
| 2,4,6-Trichlorophenol       | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 30    |
| 2,4,5-Trichlorophenol       | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| 2-Chloronaphthalene         | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | 3 J    | BDL    | BDL    | --    |
| Acenaphthene                | BDL    | BDL    | BDL    | 3 J    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 4,000 |
| Phenanthrene                | 6 J    | BDL    | BDL    | BDL    | BDL   | 1 J   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| Dibenzofuran                | 4 J    | BDL    | BDL    | 1 J    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| Diethyl phthalate           | BDL    | BDL    | BDL    | 10 UJ  | BDL   | BDL   | 10 UJ | BDL    | BDL    | 10 UJ  | 10 UJ   | 24 UJ  | 10 UJ  | 11 UJ  | 6,000 |
| Fluorene                    | 7 J    | BDL    | BDL    | 2 J    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 300   |
| N-Nitrosodiphenylamine      | BDL    | BDL    | 1 J    | BDL    | 2 J   | BDL   | 1 J   | BDL    | 3 J    | 2 J    | 2 J     | BDL    | 3 J    | BDL    | 70    |
| Pentachlorophenol           | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 200   |
| Anthracene                  | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 2,000 |
| Carbazole                   | BDL    | BDL    | 2 J    | BDL    | 1 J   | BDL   | 2 J   | BDL    | BDL    | BDL    | BDL     | BDL    | 1 J    | BDL    | --    |
| Di-n-butyl phthalate        | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 700   |
| Fluoranthene                | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 300   |
| Pyrene                      | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | 200   |
| Butyl benzyl phthalate      | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | 10 UJ  | 10 UJ   | BDL    | BDL    | BDL    | 100   |
| Benzo(a)anthracene          | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| Chrysene                    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| Di-n-octyl phthalate        | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| bis(2-Ethylhexyl)phthalate  | 40 UJ  | BDL    | 10 UJ  | 10 UJ  | 10 UJ | 10 UJ | 10 UJ | BDL    | 10 UJ  | 10 UJ  | 10 UJ   | BDL    | 10 UJ  | 13 UJ  | --    |
| Benzo(b)fluoranthene        | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| Benzo(k)fluoranthene        | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |
| Benzo(a)pyrene              | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --    |

**TABLE 5-5 (Continued)**  
**SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| SVOC                           | D3600N | D3000N | D1600S | E2600N | E600N | E00   | E600S | E1200S | F3600N | F3000N | F3000ND | F2200N | F1600N | F1000N | RAL |
|--------------------------------|--------|--------|--------|--------|-------|-------|-------|--------|--------|--------|---------|--------|--------|--------|-----|
| Indeno(1,2,3-cd)pyrene         | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --  |
| Dibenzo(a,h)anthracene         | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --  |
| Benzo(g,h,i)perylene           | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | BDL    | --  |
| Total SVOCs                    | 177    | 15     | 11     | 17     | 3     | 3     | 4     | 43     | 13     | 14     | 13      | 10     | 21     | 22     |     |
| TIC                            |        |        |        |        |       |       |       |        |        |        |         |        |        |        |     |
| Hydrocarbons                   | 140 J  | BDL    | 7 J    | BDL    | 19 J  | 15 J  | 11 J  | 80 J   | 14 J   | 3 J    | 4 J     | 210 J  | 18 J   | BDL    |     |
| Oxygenated hydrocarbons        | 46 J   | 58 J   | 23 J   | 270 J  | 70 J  | 360 J | 56 J  | 180 J  | 120 J  | 270 J  | 140 J   | 220 J  | 77 J   | 66 J   |     |
| Alkylaromatic hydrocarbons     | 23 J   | 6 J    | 3 J    | BDL    | BDL   | BDL   | 18 J  | 120 J  | 39 J   | 3 J    | 22 J    | 66 J   | 25 J   | BDL    |     |
| Cyclic oxygenated hydrocarbons | BDL    | 8 J    | BDL    | 14 J   | BDL   | BDL   | BDL   | 100 J  | BDL    | BDL    | BDL     | 19 J   | BDL    | BDL    |     |
| Oxygenated aromatics           | BDL    | 130 J  | 27 J   | 42 J   | 10 J  | 12 J  | 33 J  | 14 J   | 390 J  | 20 J   | BDL     | 140 J  | 11 J   | 140 J  |     |
| Heterocyclic aromatics         | BDL    | 76 J   | 74 J   | 190 J  | 58 J  | 19 J  | 24 J  | 41 J   | 36 J   | 23 J   | 29 J    | BDL    | 45 J   | 10 J   |     |
| Phosphoric acid esters         | BDL    | 21 J   | 27 J   | BDL    | 52 J  | BDL   | 29 J  | 31 J   | 19 J   | 18 J   | 21 J    | 34 J   | BDL    | BDL    |     |
| PAHs                           | 510 J  | BDL    | 3 J    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | 20 J   | BDL    |     |
| Sulfur                         | 52 J   | BDL    | 3 J    | 96 J   | 16 J  | 31 J  | 9 J   | BDL    | 20 J   | BDL    | BDL     | BDL    | 46 J   | 73 J   |     |
| Sulfonamides                   | BDL    | 21 J   | 32 J   | 81 J   | 49 J  | BDL   | 36 J  | 24 J   | 45 J   | 22 J   | 22 J    | 51 J   | 44 J   | 21 J   |     |
| Amines and amides              | BDL    | BDL    | 4 J    | BDL    | BDL   | BDL   | 5 J   | 25 J   | 10 J   | BDL    | 15 J    | BDL    | BDL    | 33 J   |     |
| Halogenated aromatics          | BDL    | 5 J    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | 33 J   |     |
| Nitriles                       | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL   | BDL    | BDL    | BDL    | BDL     | BDL    | BDL    | 10 J   |     |
| Miscellaneous                  | BDL    | BDL    | BDL    | BDL    | 7 J   | BDL   | BDL   | BDL    | BDL    | 50 J   | 35 J    | BDL    | BDL    | BDL    |     |
| Total TICs                     | 771    | 325    | 203    | 693    | 281   | 437   | 221   | 615    | 693    | 409    | 288     | 740    | 286    | 386    |     |

TABLE 5-5 (Continued)

**SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| SVOC                        | F1600S | H2800N | H600N | H1600S | I1200N | I00    | J2400N | J800N | J600S | J1400S | J1400S-D | K1600N | L1200N | RAI   |
|-----------------------------|--------|--------|-------|--------|--------|--------|--------|-------|-------|--------|----------|--------|--------|-------|
| Phenol                      | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | 2 J      | BDL    | BDL    | 4,000 |
| bis(2-Chloroethyl)ether     | BDL    | BDL    | BDL   | BDL    | BDL    | 4,000  | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 0.3   |
| 1,4-DCB                     | BDL    | BDL    | BDL   | 3 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | 2 J    | 3 J    | 10    |
| 1,2-DCB                     | BDL    | 2 J    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 600   |
| 2-Methylphenol              | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | 1 J   | BDL    | 8 J      | BDL    | BDL    | 30    |
| bis(2-Chloroisopropyl)ether | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 300   |
| 4-Methylphenol              | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | 6 J   | BDL    | BDL      | BDL    | BDL    | 30    |
| Nitrobenzene                | BDL    | BDL    | BDL   | BDL    | 14     | BDL    | 23     | BDL   | 2 J   | BDL    | BDL      | 11     | 5 J    | 3     |
| Naphthalene                 | BDL    | 36     | 2 J   | 11     | BDL    | BDL    | BDL    | BDL   | 20    | 6 J    | 6 J      | 1 J    | 17     | 30    |
| 2-Methylnaphthalene         | BDL    | 3 J    | 1 J   | 2 J    | BDL    | BDL    | BDL    | BDL   | 3 J   | 1 J    | 2 J      | BDL    | 3 J    | --    |
| 2,4,6-Trichlorophenol       | BDL    | BDL    | 1 J   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 30    |
| 2,4,5-Trichlorophenol       | BDL    | BDL    | 1 J   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |
| 2-Chloronaphthalene         | BDL    | BDL    | 1 J   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |
| Acenaphthene                | BDL    | BDL    | BDL   | 3 J    | BDL    | BDL    | BDL    | BDL   | 2 J   | BDL    | BDL      | BDL    | BDL    | 4,000 |
| Phenanthrene                | BDL    | BDL    | BDL   | 9 J    | BDL    | BDL    | BDL    | BDL   | 1 J   | BDL    | BDL      | BDL    | BDL    | --    |
| Dibenzofuran                | BDL    | BDL    | BDL   | 2 J    | BDL    | BDL    | BDL    | BDL   | 1 J   | BDL    | BDL      | BDL    | BDL    | --    |
| Diethyl phthalate           | BDL    | 10 UJ  | 10 UJ | BDL    | BDL    | 270 UJ | BDL    | BDL   | 10 UJ | 10 UJ  | 10 UJ    | 10 UJ  | 10 UJ  | 6,000 |
| Fluorene                    | BDL    | BDL    | BDL   | 2 J    | BDL    | BDL    | BDL    | BDL   | 2 J   | BDL    | BDL      | BDL    | BDL    | 300   |
| N-Nitrosodiphenylamine      | BDL    | 2 J    | 6 J   | 2 J    | BDL    | BDL    | BDL    | BDL   | BDL   | 1 J    | 1 J      | 2 J    | 2 J    | 70    |
| Pentachlorophenol           | BDL    | BDL    | 50    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 200   |
| Anthracene                  | BDL    | BDL    | BDL   | 2 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 2,000 |
| Carbazole                   | BDL    | BDL    | BDL   | 5 J    | BDL    | BDL    | BDL    | BDL   | 3 J   | 2 J    | 2 J      | BDL    | BDL    | --    |
| Di-n-butyl phthalate        | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 700   |
| Fluoranthene                | BDL    | BDL    | BDL   | 5 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 300   |
| Pyrene                      | BDL    | BDL    | BDL   | 3 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 200   |
| Butyl benzyl phthalate      | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | 100   |
| Benzo(a)anthracene          | BDL    | BDL    | BDL   | 1 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |
| Chrysene                    | BDL    | BDL    | BDL   | 2 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |
| Di-n-octyl phthalate        | BDL    | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | 10 UJ    | BDL    | BDL    | --    |
| bis(2-Ethylhexyl)phthalate  | BDL    | 10 UJ  | 10 UJ | 10 UJ  | BDL    | BDL    | BDL    | BDL   | 10 UJ | 10 UJ  | 16 UJ    | 10 UJ  | 10 UJ  | --    |
| Benzo(b)fluoranthene        | BDL    | BDL    | BDL   | 1 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |
| Benzo(k)fluoranthene        | BDL    | BDL    | BDL   | 1 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |
| Benzo(a)pyrene              | BDL    | BDL    | BDL   | 1 J    | BDL    | BDL    | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --    |

**TABLE 5-5 (Continued)**  
**SVOC CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| SVOC                           | F1600S | H2800N | H600N | H1600S | I1200N | I00   | J2400N | J800N | J600S | J1400S | J1400S-D | K1600N | L1200N | RAL |
|--------------------------------|--------|--------|-------|--------|--------|-------|--------|-------|-------|--------|----------|--------|--------|-----|
| Indeno(1,2,3-cd)pyrene         | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --  |
| Dibenzo(a,h)anthracene         | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --  |
| Benzo(g,h,i)perylene           | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    | --  |
| Total SVOCs                    | BDL    | 43     | 62    | 55     | 14     | 4,000 | 23     | BDL   | 41    | 10     | 21       | 16     | 30     |     |
| TIC                            |        |        |       |        |        |       |        |       |       |        |          |        |        |     |
| Hydrocarbons                   | BDL    | 7 J    | 20 J  | BDL    | 3 J    | BDL   | 12 J   | 9 J   | 17 J  | BDL    | 43 J     | 10 J   | 12 J   |     |
| Oxygenated hydrocarbons        | 150 J  | 87 J   | 45 J  | 140 J  | 90 J   | 510 J | 51 J   | 72 J  | 57 J  | 62 J   | 95 J     | 90 J   | 120 J  |     |
| Alkylaromatic hydrocarbons     | BDL    | 130 J  | 22 J  | 27 J   | BDL    |       | BDL    | 8 J   | 93 J  | 48 J   | 42 J     | 22 J   | 130 J  |     |
| Cyclic oxygenated hydrocarbons | BDL    | BDL    | 57 J  | BDL    | BDL    | 27 J  | BDL    | 14 J  | 88 J  | BDL    | BDL      | BDL    | BDL    |     |
| Oxygenated aromatics           | BDL    | 61 J   | 110 J | 13 J   | 26 J   | 660 J | 14 J   | 3 J   | 95 J  | 42 J   | BDL      | BDL    | 11 J   |     |
| Heterocyclic aromatics         | BDL    | 11 J   | 65 J  | 38 J   | 5 J    | BDL   | 17 J   | 5 J   | 45 J  | 43 J   | 37 J     | 35 J   | 29 J   |     |
| Phosphoric acid esters         | BDL    | 88 J   | 150 J | 49 J   | BDL    | 89 J  | 9 J    | BDL   | 56 J  | 30 J   | 23 J     | BDL    | BDL    |     |
| PAHs                           | BDL    | 7 J    | 60 J  | 6 J    | BDL    | BDL   | BDL    | 7 J   | BDL   | BDL    | 15 J     | BDL    | 12 J   |     |
| Sulfur                         | BDL    | BDL    | 12 J  | BDL    | 41 J   | BDL   | 19 J   | 6 J   | BDL   | BDL    | 17 J     | BDL    | 31 J   |     |
| Sulfonamides                   | BDL    | 23 J   | BDL   | 30 J   | BDL    | 110 J | 13 J   | BDL   | 140 J | 39 J   | 47 J     | 23 J   | 32 J   |     |
| Amines and amides              | BDL    | 36 J   | BDL   | 6 J    | 50 J   | 78 J  | 33 J   | BDL   | BDL   | 6 J    | BDL      | 60 J   | BDL    |     |
| Halogenated aromatics          | BDL    | BDL    | BDL   | BDL    | 34 J   | BDL   | BDL    | BDL   | BDL   | BDL    | BDL      | 18 J   | 17 J   |     |
| Nitriles                       | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    |     |
| Miscellaneous                  | BDL    | BDL    | BDL   | BDL    | BDL    | BDL   | BDL    | BDL   | BDL   | BDL    | BDL      | BDL    | BDL    |     |
| Total TICs                     | 150    | 450    | 541   | 309    | 249    | 1,474 | 168    | 124   | 591   | 270    | 319      | 258    | 394    |     |

Notes:

- a BDL = Below laboratory method detection limit
- b J = Estimated concentration value
- c **Shaded bold values** indicate that concentration exceeds RAL
- d -- = RAL not assigned to analyte
- e UJ = Estimated quantitation limit

**TABLE 5-6**  
**METAL CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| Metal     | A800N               | A400N   | B2600N  | B1800N  | B1800ND         | B1400N  | B00     | B00-D   | B400S   | B800S   | B1200S  | RAL             |
|-----------|---------------------|---------|---------|---------|-----------------|---------|---------|---------|---------|---------|---------|-----------------|
| Antimony  | BDL <sup>a</sup>    | BDL     | BDL     | BDL     | 83 <sup>b</sup> | BDL     | 88.4    | BDL     | 96.3    | BDL     | BDL     | 1               |
| Arsenic   | 1.2 J <sup>c</sup>  | 1.5 J   | BDL     | BDL     | BDL             | BDL     | BDL     | BDL     | 1.3 J   | BDL     | BDL     | 0.2             |
| Barium    | 242                 | 323     | 363     | 490     | 481             | 574     | 413     | 421     | 822     | 424     | 617     | 2,000           |
| Calcium   | 249,000             | 128,000 | 204,000 | 238,000 | 233,000         | 159,000 | 142,000 | 143,000 | 165,000 | 208,000 | 136,000 | -- <sup>d</sup> |
| Cobalt    | BDL                 | BDL     | BDL     | BDL     | 7.2 J           | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | 1               |
| Iron      | 57,200              | 64,700  | 24,200  | 25,200  | 24,800          | 32,600  | 54,800  | 53,300  | 50,000  | 79,000  | 73,000  | --              |
| Magnesium | 51,100              | 31,700  | 69,300  | 107,000 | 100,000         | 66,200  | 70,800  | 70,000  | 64,200  | 50,300  | 32,200  | --              |
| Manganese | 3,130               | 1,660   | 395     | 369     | 363             | 529     | 210     | 209     | 208     | 670     | 279     | 300             |
| Mercury   | 0.10 J              | 0.15 J  | 0.39    | BDL     | BDL             | 0.2     | BDL     | BDL     | BDL     | BDL     | BDL     | 1               |
| Nickel    | BDL                 | BDL     | BDL     | BDL     | BDL             | BDL     | 12.8 J  | 12.7 J  | 10.4 J  | 25.4 J  | BDL     | 70              |
| Potassium | 51,000              | 40,900  | 32,500  | 47,700  | 46,200          | 28,800  | 74,000  | 74,900  | 63,200  | 25,000  | 13,500  | --              |
| Selenium  | BDL                 | BDL     | BDL     | BDL     | BDL             | BDL     | 5.0 J   | BDL     | BDL     | BDL     | BDL     | 10              |
| Silver    | BDL                 | BDL     | BDL     | BDL     | BDL             | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | 10              |
| Sodium    | 147,000             | 58,100  | 54,300  | 88,500  | 87,200          | 60,600  | 268,000 | 270,000 | 98,100  | 39,700  | 19,500  | --              |
| Thallium  | BDL                 | BDL     | BDL     | BDL     | BDL             | 10.5 J  | BDL     | BDL     | BDL     | BDL     | BDL     | 0.3             |
| Vanadium  | 5.2 UJ <sup>e</sup> | BDL     | 8.7 J   | 7.1 J   | 9.3 J           | 7.8 J   | 6.2 J   | BDL     | BDL     | BDL     | BDL     | 20              |
| Zinc      | 6.0 J               | 3.5 J   | BDL     | BDL     | BDL             | BDL     | 16.1 J  | 12.7 J  | 284     | 43.7 J  | 52.2    | 700             |
| Cyanide   | BDL                 | BDL     | BDL     | BDL     | BDL             | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | 100             |



**TABLE 5-6 (Continued)**  
**METAL CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| Metal     | B1600S  | B2000S  | C2200N  | C800N   | C400N   | D3600N  | D3000N  | D1600S  | E2600N  | E600N   | E00     | E600S   | E1200S    | F3600N  | RAL  |
|-----------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|---------|-----------|---------|------|
| Antimony  | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | 93.9    | BDL     | BDL     | BDL       | BDL     | 1    |
| Arsenic   | BDL     | 2.1 J   | BDL     | BDL     | BDL     | BDL     | 1.9 J   | 3.9 J   | 1.3 J   | BDL     | BDL     | BDL     | 7.9 J     | 1.2 J   | 0.2  |
| Barium    | 346     | 277     | 606     | 684     | 800     | 778     | 383     | 591     | 792     | 358     | 559     | 570     | 41.9 J    | 488     | 2000 |
| Calcium   | 141,000 | 193,000 | 138,000 | 174,000 | 169,000 | 217,000 | 169,000 | 146,000 | 227,000 | 399,000 | 130,000 | 214,000 | 63,500    | 146,000 | --   |
| Cobalt    | BDL     | BDL     | BDL     | BDL     | 7.4 J   | BDL     | BDL     | 14.4 J  | BDL     | 8.3 J   | 8.3 J   | BDL     | BDL       | 11.8 J  | 1    |
| Iron      | 63,600  | 18,600  | 32,200  | 35,500  | 34,100  | 40,100  | 19,700  | 66,600  | 26,600  | 8,610   | 25,500  | 58,300  | 20,700    | 28,600  | --   |
| Magnesium | 50,500  | 34,400  | 99,700  | 94,300  | 93,300  | 54,200  | 97,500  | 44,000  | 164,000 | 88,000  | 144,000 | 68,300  | 47,500    | 110,000 | --   |
| Manganese | 193     | 477     | 91.6    | 141     | 166     | 497     | 419     | 206     | 304     | 1,690   | 142     | 448     | 105       | 204     | 300  |
| Mercury   | BDL     | BDL     | BDL     | BDL     | BDL     | 0.2     | BDL     | BDL     | 6.4     | BDL     | BDL     | BDL     | 0.16 J    | BDL     | 1    |
| Nickel    | BDL     | 9.2 J   | BDL     | 79.5    | 11.6 J  | BDL     | BDL     | 251     | 16.8 J  | BDL     | 29.2 J  | BDL     | 12.3 J    | BDL     | 70   |
| Potassium | 41,900  | 2,000   | 90,600  | 66,900  | 70,000  | 32,600  | 59,000  | 28,200  | 160,000 | 59,500  | 271,000 | 42,200  | 25,100    | 109,000 | --   |
| Selenium  | BDL     | 1.0 J   | BDL     | BDL     | BDL     | BDL     | 5.5 J   | BDL     | BDL     | BDL     | BDL     | BDL     | 7.0 J     | BDL     | 10   |
| Silver    | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL       | BDL     | 10   |
| Sodium    | 52,600  | 32,300  | 109,000 | 12,500  | 199,000 | 54,400  | 106,000 | 39,500  | 360,000 | 180,000 | 726,000 | 69,600  | 1,060,000 | 125,000 | --   |
| Thallium  | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL       | BDL     | 0.3  |
| Vanadium  | BDL     | BDL     | 8.1 J   | 8.2 J   | 5.2 J   | BDL     | BDL     | BDL     | 6.2 UJ  | 6.1 J   | 5.3 J   | 6.4 J   | BDL       | BDL     | 20   |
| Zinc      | 111     | 70.5    | BDL     | 17.2 J  | 14.9 J  | BDL     | BDL     | 92.7    | BDL     | BDL     | 11.8 J  | 29.2    | 22.7      | BDL     | 700  |
| Cyanide   | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | 31.7      | BDL     | 100  |

TABLE 5-6 (Continued)

**METAL CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
(Results in ppb)

| Metal     | F3000N  | F3000ND | F2200N  | F1600N  | F1000N  | F1600S  | H2800N  | H600N             | H1600S  | I00     | I1200N  | J2400N  | J800N   | RAL   |
|-----------|---------|---------|---------|---------|---------|---------|---------|-------------------|---------|---------|---------|---------|---------|-------|
| Antimony  | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL               | BDL     | BDL     | BDL     | BDL     | BDL     | 1     |
| Arsenic   | 2.1 J   | 1.8 J   | 1.6 J   | 1.3 J   | BDL     | BDL     | 1.4 J   | 1.8 J             | 1.3 J   | 1.0 J   | 3.6 J   | 1.7 J   | BDL     | 0.2   |
| Barium    | 1,310   | 1,290   | 1,050   | 676     | 1,100   | 295     | 411     | 1,530             | 422     | 560     | 890     | 326     | 312     | 2,000 |
| Calcium   | 161,000 | 161,000 | 130,000 | 144,000 | 266,000 | 168,000 | 169,000 | 217,000           | 142,000 | 308,000 | 121,000 | 138,000 | 345,000 | --    |
| Cobalt    | 36.0 J  | 32.0 J  | BDL     | BDL     | BDL     | BDL     | BDL     | BDL               | BDL     | BDL     | BDL     | BDL     | BDL     | 1     |
| Iron      | 68,500  | 70,400  | 26,800  | 43,500  | 44,300  | 46,500  | 35,400  | 34,600            | 51,900  | 146,000 | 29,900  | 15,500  | 5,450   | --    |
| Magnesium | 73,100  | 74,900  | 161,000 | 107,000 | 89,000  | 43,400  | 120,000 | 83,500            | 67,500  | 142,000 | 176,000 | 196,000 | 51,100  | --    |
| Manganese | 283     | 294     | 75      | 162     | 1,580   | 764     | 189     | 887               | 367     | 519     | 99.8    | 223     | 1,630   | 300   |
| Mercury   | BDL     | BDL     | BDL     | BDL     | 0.14 J  | BDL     | BDL     | 0.11 J            | BDL     | 0.2     | BDL     | BDL     | BDL     | 1     |
| Nickel    | 47.8    | 40.6    | 24.3 J  | 11.9 J  | BDL     | BDL     | BDL     | 9.9 J             | 10.1 J  | 49.9    | BDL     | 9.9 J   | BDL     | 70    |
| Potassium | 96,500  | 97,500  | 203,000 | 103,000 | 51,000  | 21,000  | 87,000  | 105,000           | 39,500  | 62,400  | 118,000 | 139,000 | 80,300  | --    |
| Selenium  | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL               | BDL     | BDL     | BDL     | BDL     | BDL     | 10    |
| Silver    | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL               | BDL     | 5.0 J   | BDL     | BDL     | BDL     | 10    |
| Sodium    | 138,000 | 139,000 | 816,000 | 156,000 | 35,400  | 127,000 | 241,000 | 23,000            | 150,000 | 165,000 | 167,000 | 289,000 | 29,000  | --    |
| Thallium  | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | 13 R <sup>f</sup> | BDL     | BDL     | BDL     | BDL     | BDL     | 0.3   |
| Vanadium  | 7.5 UJ  | BDL     | BDL     | BDL     | 10.6 J  | BDL     | BDL     | BDL               | BDL     | BDL     | BDL     | BDL     | BDL     | 20    |
| Zinc      | 6.3 J   | 13.4 J  | BDL     | BDL     | BDL     | 103     | BDL     | BDL               | 79.5    | 196     | BDL     | BDL     | BDL     | 700   |
| Cyanide   | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL     | BDL               | BDL     | BDL     | BDL     | BDL     | BDL     | 100   |

**TABLE 5-6 (Continued)**  
**METAL CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| Metal     | J600S   | J1400S       | J1400SD      | K1600N       | L1200N       | RAL   |
|-----------|---------|--------------|--------------|--------------|--------------|-------|
| Antimony  | BDL     | BDL          | BDL          | BDL          | BDL          | 1     |
| Arsenic   | BDL     | <b>1.2 J</b> | <b>1.0 J</b> | <b>1.2 J</b> | <b>2.1 J</b> | 0.2   |
| Barium    | 332     | 318          | 312          | 749          | 898          | 2,000 |
| Calcium   | 228,000 | 151,000      | 149,000      | 64,100       | 115,000      | --    |
| Cobalt    | BDL     | BDL          | BDL          | BDL          | BDL          | 1     |
| Iron      | 102,000 | 43,900       | 42,600       | 8,870        | 53,200       | --    |
| Magnesium | 36,700  | 74,900       | 73,200       | 181,000      | 126,000      | --    |
| Manganese | 516     | 287          | 286          | 103          | 160          | 300   |
| Mercury   | BDL     | BDL          | BDL          | BDL          | BDL          | 1     |
| Nickel    | 12.9 J  | 18.9 J       | 18.8 J       | BDL          | 9.2 J        | 70    |
| Potassium | 66,900  | 51,600       | 50,900       | 197,000      | 122,000      | --    |
| Selenium  | BDL     | BDL          | BDL          | BDL          | BDL          | 10    |
| Silver    | BDL     | BDL          | BDL          | BDL          | BDL          | 10    |
| Sodium    | 102,000 | 148,000      | 149,000      | 178,000      | 715,000      | --    |
| Thallium  | BDL     | BDL          | BDL          | BDL          | BDL          | 0.3   |
| Vanadium  | 5.8 J   | BDL          | 6.0 J        | BDL          | BDL          | 20    |
| Zinc      | 45.2    | 115          | 65.3         | BDL          | BDL          | 700   |
| Cyanide   | BDL     | BDL          | BDL          | BDL          | BDL          | 100   |

**Notes:**

- a BDL = Below detection limit
- b **Shaded bold values** indicate that concentration exceed RAL
- c J = Estimated concentration value
- d -- = RAL not assigned to analyte
- e UJ = Estimated quantitation limit
- f R = Rejected

**TABLE 5-7**  
**PESTICIDE CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| Pesticide       | A800N            | A400N | B2600N | B1800N | B1800ND | B1400N | B00 | B00D                | B400S   | B800S | B1200S | B1600S | B2000S |
|-----------------|------------------|-------|--------|--------|---------|--------|-----|---------------------|---------|-------|--------|--------|--------|
| delta-BHC       | BDL <sup>a</sup> | BDL   | BDL    | BDL    | BDL     | BDL    | BDL | BDL                 | BDL     | BDL   | BDL    | BDL    | BDL    |
| Alpha chlordane | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL | 0.039J <sup>b</sup> | BDL     | BDL   | BDL    | BDL    | BDL    |
| Gamma chlordane | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL | 0.047 J             | 0.026 J | BDL   | BDL    | BDL    | BDL    |
| 4,4'-DDT        | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL | BDL                 | BDL     | BDL   | BDL    | BDL    | BDL    |
| 4,4'-DDD        | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL | BDL                 | 0.089 J | BDL   | BDL    | BDL    | BDL    |

| Pesticide       | C2200N | C800N | C400N | D3600N | D3000N | D1600S | E2600N | E600N | E00 | E600S | E1200S | F3600N |
|-----------------|--------|-------|-------|--------|--------|--------|--------|-------|-----|-------|--------|--------|
| delta-BHC       | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | 0.14 J | BDL    |
| Alpha chlordane | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |
| Gamma chlordane | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |
| 4,4'-DDT        | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |
| 4,4'-DDD        | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |

| Pesticide       | F3000N | F3000ND | F2200N | F1600N | F1000N | F1600S | H2800N | H600N | H1600S | I1200N | I00 |
|-----------------|--------|---------|--------|--------|--------|--------|--------|-------|--------|--------|-----|
| delta-BHC       | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL |
| Alpha chlordane | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL |
| Gamma chlordane | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL |
| 4,4'-DDT        | 0.54   | 0.17    | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL |
| 4,4'-DDD        | 1.3    | 0.56    | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL |

**TABLE 5-7 (Continued)**

**PESTICIDE CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES  
(Results in ppb)**

| Pesticide       | J2400N | J800N | J600S | J1400S | J1400SD | K1600N | L1200N |
|-----------------|--------|-------|-------|--------|---------|--------|--------|
| delta-BHC       | BDL    | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |
| Alpha chlordane | BDL    | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |
| Gamma chlordane | BDL    | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |
| 4,4'-DDT        | BDL    | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |
| 4,4'-DDD        | BDL    | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |

Notes:

<sup>a</sup> BDL = Below laboratory method detection limits

<sup>b</sup> J = Estimated concentration value

**TABLE 5-8**  
**PCB CONCENTRATIONS IN GEOPROBE™ GROUNDWATER SAMPLES**  
**(Results in ppb)**

| PCB          | A800N            | A400N | B2600N | B1800N | B1800ND | B1400N | B00                | B00-D  | B400S | B800S  | B1200S | B1600S | B2000S |
|--------------|------------------|-------|--------|--------|---------|--------|--------------------|--------|-------|--------|--------|--------|--------|
| Aroclor 1221 | BDL <sup>a</sup> | BDL   | 5.4    | BDL    | BDL     | BDL    | BDL                | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    |
| Aroclor 1242 | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | 0.61J <sup>b</sup> | 0.95 J | BDL   | 0.65 J | BDL    | 2.0    | BDL    |
| Aroclor 1254 | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL                | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    |
| Aroclor 1260 | BDL              | BDL   | BDL    | BDL    | BDL     | BDL    | BDL                | BDL    | BDL   | BDL    | BDL    | BDL    | BDL    |

| PCB          | C2200N | C800N | C400N | D3600N | D3000N | D1600S | E2600N | E600N | E00 | E600S | E1200S | F3600N |
|--------------|--------|-------|-------|--------|--------|--------|--------|-------|-----|-------|--------|--------|
| Aroclor 1221 | 1.7 J  | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |
| Aroclor 1242 | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |
| Aroclor 1254 | BDL    | BDL   | BDL   | BDL    | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | BDL    | BDL    |
| Aroclor 1260 | BDL    | BDL   | BDL   | 0.86 J | BDL    | BDL    | BDL    | BDL   | BDL | BDL   | 6.7    | BDL    |

| PCB          | F3000N | F3000ND | F2200N | F1600N | F1000N | F1600S | H2800N | H600N | H1600S | I1200N | I00 | J2400N |
|--------------|--------|---------|--------|--------|--------|--------|--------|-------|--------|--------|-----|--------|
| Aroclor 1221 | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL | BDL    |
| Aroclor 1242 | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | 0.95 J | BDL    | BDL | BDL    |
| Aroclor 1254 | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL | BDL    |
| Aroclor 1260 | BDL    | BDL     | BDL    | BDL    | BDL    | BDL    | BDL    | BDL   | BDL    | BDL    | BDL | BDL    |

| PCB          | J800N | J600S | J1400S | J1400SD | K1600N | L1200N |
|--------------|-------|-------|--------|---------|--------|--------|
| Aroclor 1221 | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |
| Aroclor 1242 | BDL   | BDL   | 0.80 J | 0.51 J  | BDL    | 1.1    |
| Aroclor 1254 | BDL   | BDL   | BDL    | BDL     | BDL    | 0.72 J |
| Aroclor 1260 | BDL   | BDL   | BDL    | BDL     | BDL    | BDL    |

Notes:

<sup>a</sup> BDL = Below laboratory method detection limit  
<sup>b</sup> J = Estimated concentration value

TABLE 5-9

**VOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| VOC                            | MW-1               | MW-2             | MW-4  | MW-5  | MW-6  | MW-7  | MW-7D | MW-8   | RAL             |
|--------------------------------|--------------------|------------------|-------|-------|-------|-------|-------|--------|-----------------|
| Chloroethane                   | 5 J <sup>a</sup>   | BDL <sup>b</sup> | 5 J   | BDL   | BDL   | BDL   | BDL   | BDL    | -- <sup>c</sup> |
| Acetone                        | 16 UJ <sup>d</sup> | 16 UJ            | 45 UJ | 10 UJ | 45 UJ | 24 UJ | 16 UJ | 410 UJ | 700             |
| Carbon disulfide               | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | 700             |
| Chloroform                     | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | 60              |
| 2-Butanone                     | BDL                | BDL              | 11 UJ | 12 UJ | BDL   | 10 UJ | BDL   | BDL    | 300             |
| Bromodichloromethane           | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | 3               |
| Benzene                        | 53 <sup>e</sup>    | 5 J              | 11    | BDL   | 20    | 8 J   | 7 J   | 15 J   | 10              |
| 4-Methyl-2-pentanone           | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | 300             |
| Toluene                        | BDL                | BDL              | BDL   | BDL   | 10 UJ | BDL   | BDL   | BDL    | 1,000           |
| Chlorobenzene                  | 5 J                | BDL              | 3 J   | BDL   | 26    | 15    | 17    | 16 J   | 100             |
| Ethylbenzene                   | BDL                | BDL              | BDL   | BDL   | 8 J   | BDL   | BDL   | 5 J    | 700             |
| Xylenes (total)                | 6 J                | BDL              | 1 J   | BDL   | 24    | 4 J   | 3 J   | 120    | 10,000          |
| Total VOCs                     | 69                 | 5                | 20    | BDL   | 78    | 27    | 27    | 156    |                 |
| TICs                           |                    |                  |       |       |       |       |       |        |                 |
| Hydrocarbons                   | 14 J               | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Oxygenated hydrocarbons        | 9 J                | 75 J             | 20 J  | 50 J  | BDL   | BDL   | BDL   | BDL    |                 |
| Alkylaromatic hydrocarbons     | 31 J               | BDL              | 6 J   | BDL   | 25 J  | 14 J  | 28 J  | 25 J   |                 |
| Cyclic oxygenated hydrocarbons | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Oxygenated aromatics           | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Amides and amines              | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Halogenated aromatics          | 12 J               | BDL              | 5 J   | BDL   | 6 J   | 5 J   | BDL   | BDL    |                 |
| PAHs                           | BDL                | 6 J              | BDL   | BDL   | 22 J  | 10 J  | 10 J  | BDL    |                 |
| Nitriles                       | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Heterocyclic aromatics         | BDL                | BDL              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Unknowns                       | 23 J               | 7 J              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    |                 |
| Total TICs                     | 89                 | 88               | 31    | 50    | 53    | 29    | 38    | 25     |                 |

TABLE 5-9 (Continued)

**VOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| VOC                            | MW-9  | MW-10 | MW-11 | MW-12 | MW-13 | MW-14 | MW-14<br>D | MW-15 | RAL    |
|--------------------------------|-------|-------|-------|-------|-------|-------|------------|-------|--------|
| Chloroethane                   | 3 J   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   | --     |
| Acetone                        | 11 UJ | 15 UJ | 10 UJ | 10 UJ | 10 UJ | BDL   | 15 UJ      | 10 UJ | 700    |
| Carbon disulfide               | BDL   | 10 UJ | BDL   | BDL   | BDL   | BDL   | BDL        | 10 UJ | 700    |
| Chloroform                     | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | 1 J        | 16    | 60     |
| 2-Butanone                     | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | 10 UJ | 300    |
| Bromodichloromethane           | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | 2 J   | 3      |
| Benzene                        | 25    | 7 J   | BDL   | 10    | 15    | BDL   | BDL        | BDL   | 10     |
| 4-Methyl-2-pentanone           | BDL   | BDL   | BDL   | BDL   | 2 J   | BDL   | BDL        | BDL   | 300    |
| Toluene                        | 10 UJ | BDL   | BDL   | BDL   | 10 UJ | BDL   | BDL        | 10 UJ | 1,000  |
| Chlorobenzene                  | 1 J   | 2 J   | BDL   | 3 J   | 54    | BDL   | BDL        | BDL   | 100    |
| Ethylbenzene                   | 1 J   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   | 700    |
| Xylenes (total)                | 45    | 3 J   | BDL   | 1 J   | 2 J   | BDL   | BDL        | BDL   | 10,000 |
| Total VOCs                     | 75    | 12    | BDL   | 14    | 73    | BDL   | 1          | 18    |        |
| TICs                           |       |       |       |       |       |       |            |       |        |
| Hydrocarbons                   | 33 J  | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Oxygenated hydrocarbons        | 18 J  | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Alkylaromatic hydrocarbons     | 24 J  | BDL   | BDL   | 13 J  | 17 J  | BDL   | BDL        | BDL   |        |
| Cyclic oxygenated hydrocarbons | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Oxygenated aromatics           | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Amides and amines              | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Halogenated aromatics          | BDL   | BDL   | BDL   | BDL   | 10 J  | BDL   | BDL        | BDL   |        |
| PAHs                           | BDL   | BDL   | BDL   | 8 J   | 19 J  | BDL   | BDL        | BDL   |        |
| Nitriles                       | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Heterocyclic aromatics         | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL        | BDL   |        |
| Total TICs                     | 75    | BDL   | BDL   | 21    | 46    | BDL   | BDL        | BDL   |        |



TABLE 5-9 (Continued)

VOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES  
(Results in ppb)

Notes:

- a J = Estimated concentration value
  - b BDL = Below laboratory method detection limits
  - c -- = RAL not assigned to analyte
  - d UJ = Estimated quantitation limit
  - e **Shaded bold values** indicate that concentration exceeds RAL
-

TABLE 5-10

**SVOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| SVOC                       | MW-1               | MW-2             | MW-4  | MW-5 | MW-6  | MW-7 | MW-7D | MW-8  | RAL             |
|----------------------------|--------------------|------------------|-------|------|-------|------|-------|-------|-----------------|
| 1,4-DCB                    | 7 J <sup>a</sup>   | BDL <sup>b</sup> | BDL   | BDL  | BDL   | BDL  | BDL   | BDL   | 10              |
| 4-Methylphenol             | BDL                | BDL              | 22    | BDL  | BDL   | BDL  | BDL   | 28    | 30              |
| Nitrobenzene               | BDL                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | BDL   | 3               |
| Naphthalene                | 3 J                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | 16    | 30              |
| 2-Methylnaphthalene        | BDL                | BDL              | BDL   | BDL  | BDL   | 2 J  | BDL   | 4 J   | -- <sup>c</sup> |
| Acenaphthene               | BDL                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | 2 J   | 4,000           |
| Phenanthrene               | BDL                | BDL              | BDL   | BDL  | BDL   | 1 J  | BDL   | 3 J   | --              |
| Dibenzofuran               | BDL                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | BDL   | --              |
| Diethyl phthalate          | BDL                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | BDL   | 6,000           |
| N-Nitrosodiphenylamine     | BDL                | BDL              | BDL   | BDL  | 2 J   | BDL  | BDL   | BDL   | 70              |
| Anthracene                 | BDL                | BDL              | BDL   | BDL  | 1 J   | BDL  | BDL   | BDL   | 2,000           |
| Di-n-butyl phthalate       | 10 UJ <sup>d</sup> | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | 10 UJ | 700             |
| Butyl benzyl phthalate     | BDL                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | BDL   | 100             |
| Di-n-octyl phthalate       | BDL                | BDL              | BDL   | BDL  | BDL   | BDL  | BDL   | BDL   | --              |
| bis(2-Ethylhexyl)phthalate | 10 UJ              | 12 UJ            | 10 UJ | BDL  | 10 UJ | BDL  | BDL   | 10 UJ | --              |
| Total SVOCs                | 10                 | BDL              | 22    | BDL  | 3     | 2    | BDL   | 53    |                 |
| TICs                       |                    |                  |       |      |       |      |       |       |                 |
| Hydrocarbons               | BDL                | BDL              | BDL   | BDL  | 10 J  | BDL  | BDL   | BDL   |                 |
| Oxygenated hydrocarbons    | 72 J               | 256 J            | 39 J  | 6 J  | 11 J  | 8 J  | 26 J  | 249 J |                 |
| Alkylaromatic hydrocarbons | BDL                | BDL              | 34 J  | BDL  | 11 J  | BDL  | BDL   | 259 J |                 |
| Oxygenated aromatics       | 13 J               | BDL              | 32 J  | 3 J  | 46 J  | 91 J | 43 J  | 24 J  |                 |
| Heterocyclic aromatics     | 291 J              | BDL              | 12 J  | 4 J  | 29 J  | BDL  | 44 J  | 39 J  |                 |
| Phosphoric acid esters     | 80 J               | BDL              | 22 J  | BDL  | 10 J  | 10 J | BDL   | BDL   |                 |
| PAHs                       | BDL                | BDL              | BDL   | BDL  | 15 J  | 7 J  | BDL   | BDL   |                 |
| Sulfur                     | BDL                | BDL              | 25 J  | 11J  | BDL   | 19 J | 14 J  | BDL   |                 |
| Sulfonamides               | 99 J               | 12 J             | 13 J  | BDL  | 12 J  | 17 J | 16 J  | 18 J  |                 |

TABLE 5-10 (Continued)

**SVOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| SVOC                  | MW-1  | MW-2 | MW-4 | MW-5 | MW-6 | MW-7 | MW-7D | MW-8  | RAL |
|-----------------------|-------|------|------|------|------|------|-------|-------|-----|
| Amines and amides     | BDL   | BDL  | 35 J | 71 J | BDL  | BDL  | BDL   | BDL   |     |
| Halogenated aromatics | 11 J  | 14 J | BDL  | BDL  | BDL  | BDL  | BDL   | BDL   |     |
| Unknowns              | 263 J | 90 J | 79 J | 56 J | 67 J | 79 J | 102 J | 204 J |     |
| Total TICs            | 829   | 372  | 291  | 151  | 211  | 231  | 245   | 793   |     |

| SVOC                       | MW-9  | MW-10 | MW-11 | MW-12 | MW-13 | MW-14 | MW-14D | MW-15 | RAL   |
|----------------------------|-------|-------|-------|-------|-------|-------|--------|-------|-------|
| 1,4-DCB                    | BDL   | BDL   | BDL   | BDL   | 4 J   | BDL   | BDL    | BDL   | 10    |
| 4-Methylphenol             | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   | 30    |
| Nitrobenzene               | BDL   | BDL   | BDL   | BDL   | 3 J   | BDL   | BDL    | BDL   | 3     |
| Naphthalene                | 3 J   | BDL   | BDL   | BDL   | 8 J   | BDL   | BDL    | BDL   | 30    |
| 2-Methylnaphthalene        | BDL   | BDL   | BDL   | BDL   | 3 J   | BDL   | BDL    | BDL   | --    |
| Acenaphthene               | BDL   | 2 J   | BDL   | BDL   | 2 J   | BDL   | BDL    | BDL   | 4,000 |
| Phenanthrene               | BDL   | BDL   | BDL   | BDL   | 2 J   | BDL   | BDL    | BDL   | --    |
| Dibenzofuran               | BDL   | 1 J   | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   | --    |
| Diethyl phthalate          | 10 UJ | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   | 6,000 |
| N-Nitrosodiphenylamine     | BDL   | BDL   | BDL   | 3 J   | BDL   | BDL   | BDL    | BDL   | 70    |
| Anthracene                 | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   | 2,000 |
| Di-n-butyl phthalate       | BDL   | 10 UJ | 10 UJ | 10 UJ | 10 UJ | BDL   | BDL    | BDL   | 700   |
| Butyl benzyl phthalate     | BDL   | 10 UJ | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   | 100   |
| Di-n-octyl phthalate       | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | 10 UJ | --    |
| bis(2-Ethylhexyl)phthalate | 15 UJ | BDL   | 10 UJ | 10 UJ | 10 UJ | 10 UJ | 10 UJ  | 10 UJ | --    |
| Total SVOCs                | 3     | 3     | BDL   | 3     | 22    | BDL   | BDL    | BDL   |       |
| TICs                       |       |       |       |       |       |       |        |       |       |
| Hydrocarbons               | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   |       |

**TABLE 5-10 (Continued)**  
**SVOC CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| SVOC                       | MW-9  | MW-10 | MW-11 | MW-12 | MW-13 | MW-14 | MW-14D | MW-15 | RAL |
|----------------------------|-------|-------|-------|-------|-------|-------|--------|-------|-----|
| Oxygenated hydrocarbons    | 218 J | 14 J  | 59 J  | BDL   | 39 J  | BDL   | BDL    | BDL   |     |
| Alkylaromatic hydrocarbons | 15 J  | BDL   | BDL   | BDL   | 6 J   | BDL   | BDL    | BDL   |     |
| Oxygenated aromatics       | 156 J | 28 J  | 43 J  | 40 J  | 19 J  | BDL   | BDL    | BDL   |     |
| Heterocyclic aromatics     | 377 J | 98 J  | 23 J  | 80 J  | 44 J  | BDL   | BDL    | BDL   |     |
| Phosphoric acid esters     | 23 J  | BDL   | BDL   | 18 J  | 24 J  | BDL   | BDL    | BDL   |     |
| PAHs                       | BDL   | BDL   | 9 J   | BDL   | BDL   | BDL   | BDL    | BDL   |     |
| Sulfur                     | BDL   | 21 J  | 12 J  | BDL   | BDL   | BDL   | BDL    | BDL   |     |
| Sulfonamides               | 22 J  | BDL   | BDL   | 14 J  | 14 J  | BDL   | BDL    | BDL   |     |
| Amines and amides          | 73 J  | 118 J | BDL   | 121 J | BDL   | BDL   | BDL    | 4 J   |     |
| Halogenated aromatics      | BDL   | BDL   | BDL   | BDL   | BDL   | BDL   | BDL    | BDL   |     |
| Unknowns                   | 236 J | 164 J | 45 J  | 88 J  | 78 J  | 21 J  | 134 J  | 15 J  |     |
| Total TICs                 | 1,120 | 443   | 191   | 361   | 224   | 21    | 134    | 19    |     |

Notes:

<sup>a</sup> J = Estimated concentration value

<sup>b</sup> BDL = Below laboratory method detection limits

<sup>c</sup> -- = RAL not assigned to analyte

<sup>d</sup> UJ = Estimated quantitation limit

TABLE 5-11

**METAL CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| Metal     | MW-1                  | MW-2      | MW-4     | MW-5      | MW-6      | MW-7      | MW-7DUP   | MW-8      | RAL             |
|-----------|-----------------------|-----------|----------|-----------|-----------|-----------|-----------|-----------|-----------------|
| Aluminum  | BDL <sup>a</sup>      | BDL       | BDL      | 105 UJ    | BDL       | BDL       | BDL       | BDL       | -- <sup>b</sup> |
| Antimony  | 32.4 J <sup>c,d</sup> | BDL       | 39.5 J   | BDL       | BDL       | BDL       | 49.6 J    | BDL       | 1               |
| Arsenic   | 4.2 UJ <sup>e</sup>   | 9.4 UJ    | 5.0 UJ   | 3.0 UJ    | 6.0 UJ    | BDL       | BDL       | 1.8 UJ    | 0.2             |
| Barium    | 267                   | 519       | 613      | 152       | 702       | 451       | 452       | 421       | 2,000           |
| Beryllium | 0.43 UJ               | 0.42 UJ   | 0.56 UJ  | 0.42 UJ   | 0.35 UJ   | BDL       | BDL       | BDL       | 0.08            |
| Calcium   | 481,000               | 360,000   | 332,000  | 88,700    | 129,000   | 156,000   | 156,000   | 153,000   | --              |
| Chromium  | BDL                   | BDL       | BDL      | BDL       | BDL       | BDL       | BDL       | BDL       | 100             |
| Cobalt    | BDL                   | 6.1 J     | 9.3 J    | BDL       | 10.1 J    | 5.2 J     | 4.4 J     | 4.2 J     | 1               |
| Copper    | 18.2 UJ               | 17.6 UJ   | 11.8 UJ  | 19.9 UJ   | 13.4 UJ   | 2.1 UJ    | 2.1 UJ    | 2.1 UJ    | 1,000           |
| Iron      | 6,570                 | 28,200    | 1,730    | 1,350     | 18,400    | 116 UJ    | 131 UJ    | 472       | --              |
| Lead      | BDL                   | BDL       | BDL      | BDL       | BDL       | 1.6 UJ    | BDL       | BDL       | 20              |
| Magnesium | 231,000               | 123,000   | 96,600   | 259,000   | 156,000   | 161,000   | 162,000   | 128,000   | --              |
| Manganese | 621 J                 | 3,820 J   | 1,930 J  | 150 J     | 538 J     | 270 J     | 265 J     | 694 J     | 300             |
| Nickel    | 16.4 UJ               | 25.0 UJ   | 13.7 UJ  | BDL       | 17.0 UJ   | BDL       | BDL       | BDL       | 70              |
| Potassium | 77,100                | 3,780 UJ  | 65,900   | 154,000   | 129,000   | 97,800    | 96,800    | 95,400    | --              |
| Selenium  | 22.7                  | 18.5      | 23.9     | 4.4 J     | 2.8 J     | 25.4      | 24.4      | 23.2      | 10              |
| Sodium    | 191,000 J             | 174,000 J | 88,400 J | 283,000 J | 180,000 J | 159,000 J | 161,000 J | 138,000 J | --              |
| Thallium  | BDL                   | BDL       | BDL      | BDL       | BDL       | BDL       | BDL       | BDL       | 0.3             |
| Vanadium  | 28.0 UJ               | 29.3 UJ   | 22.3 UJ  | 19.2 UJ   | 21.7 UJ   | 5.6 UJ    | 6.6 UJ    | 5.9 UJ    | 20              |
| Zinc      | 60.2 UJ               | 12.9 UJ   | 7.6 UJ   | 527 J     | 37.4 UJ   | 47.0 UJ   | 5.2 UJ    | 54.0 UJ   | 700             |
| Cyanide   | BDL                   | 60.5 J    | BDL      | BDL       | 1.5 UJ    | 16.3 J    | 1.9 UJ    | 1.6 UJ    | 100             |

TABLE 5-11 (Continued)

**METAL CONCENTRATIONS IN GROUNDWATER MONITORING WELL SAMPLES**  
**(Results in ppb)**

| Metal     | MW-9         | MW-10        | MW-11          | MW-12        | MW-13          | MW-14        | MW-14DUP     | MW-15        | RAL   |
|-----------|--------------|--------------|----------------|--------------|----------------|--------------|--------------|--------------|-------|
| Aluminum  | 36.8 UJ      | BDL          | BDL            | 62.5 UJ      | 374            | BDL          | BDL          | 60.9 UJ      | --    |
| Antimony  | BDL          | BDL          | BDL            | BDL          | BDL            | BDL          | BDL          | BDL          | 1     |
| Arsenic   | BDL          | 5.0 UJ       | 1.9 UJ         | 2.3 UJ       | BDL            | BDL          | BDL          | 2.9 UJ       | 0.2   |
| Barium    | 683          | 395          | 750            | 460          | 522            | 130 J        | 130 J        | 8.3 UJ       | 2,000 |
| Beryllium | 0.69 UJ      | 0.42 UJ      | 0.42 UJ        | 0.41 UJ      | 0.41 UJ        | 0.27 UJ      | BDL          | BDL          | 0.08  |
| Calcium   | 240,000      | 221,000      | 192,000        | 168,000      | 151,000        | 79,300       | 77,900       | 27,500       | --    |
| Chromium  | 5.3 J        | BDL          | BDL            | 8.8 J        | 3.3 J          | BDL          | BDL          | 4.8 J        | 100   |
| Cobalt    | <b>6.0 J</b> | BDL          | <b>3.6 J</b>   | <b>4.1 J</b> | <b>9.6 J</b>   | BDL          | BDL          | BDL          | 1     |
| Copper    | 21.4 UJ      | 12.3 UJ      | 12.2 UJ        | 21.6 UJ      | 44.6 UJ        | 12.2 UJ      | 9.9 UJ       | 12.1 UJ      | 1,000 |
| Iron      | 69,600       | 9,850        | 13,400         | 28,300       | 42,900         | 596          | 600          | 28.5 UJ      | --    |
| Lead      | BDL          | 3.7 UJ       | BDL            | BDL          | BDL            | BDL          | BDL          | BDL          | 20    |
| Magnesium | 203,000      | 118,000      | 71,400         | 72,800       | 51,800         | 29,200       | 28,400       | 3,200 J      | --    |
| Manganese | <b>787 J</b> | <b>988 J</b> | <b>1,830 J</b> | <b>349 J</b> | <b>2,110 J</b> | <b>348 J</b> | <b>356 J</b> | 29.0 J       | 300   |
| Nickel    | 16.0 UJ      | BDL          | BDL            | BDL          | 35.1 UJ        | BDL          | BDL          | <b>136</b>   | 70    |
| Potassium | 90,100       | 74,300       | 38,300         | 68,700       | 39,900         | BDL          | 2,940 UJ     | 5,080 UJ     | --    |
| Selenium  | BDL          | 7.1          | <b>13.6</b>    | BDL          | 2.2 J          | BDL          | BDL          | BDL          | 10    |
| Sodium    | 143,000 J    | 103,000 J    | 63,900 J       | 88,200 J     | 64,300 J       | 9,690 J      | 9,310 J      | 15,000 J     | --    |
| Thallium  | BDL          | BDL          | BDL            | BDL          | BDL            | BDL          | BDL          | <b>5.5 J</b> | 0.3   |
| Vanadium  | 31.3 J       | 22.9 UJ      | 19.1 UJ        | 23.8 UJ      | 21.6 UJ        | 15.3 UJ      | 15.8 UJ      | 16.7 UJ      | 20    |
| Zinc      | 60.6 UJ      | 81.8 UJ      | 3.8 UJ         | 228 UJ       | <b>886</b>     | BDL          | 5.7 UJ       | 100 UJ       | 700   |
| Cyanide   | BDL          | 5.3 J        | BDL            | 1.5 UJ       | 2.9 UJ         | BDL          | BDL          | 4.7 J        | 100   |

## Notes:

- a BDL = Below laboratory method detection limits  
b -- = RAL not assigned to analyte  
c J = Estimated concentration value  
d **Shaded bold values** indicate that concentration exceeds RAL  
e UJ = Estimated quantitation limit

**TABLE 5-12**  
**VOC CONCENTRATIONS IN SURFACE WATER SAMPLES**  
 (Results in ppb)

| VOC                | I00S             | I00S-D             | K600N | E1600S | A1000S | H1800S |
|--------------------|------------------|--------------------|-------|--------|--------|--------|
| Methylene chloride | BDL <sup>a</sup> | 10 UJ <sup>b</sup> | 10 UJ | 10 UJ  | 10 UJ  | 10UJ   |
| Acetone            | 10 UJ            | 22 UJ              | 10 UJ | 13 UJ  | 10 UJ  | 10 UJ  |
| 1,2-DCA            | 1 J <sup>c</sup> | BDL                | BDL   | BDL    | BDL    | BDL    |
| 2-Butanone         | BDL              | BDL                | BDL   | 10 UJ  | BDL    | BDL    |
| Benzene            | BDL              | 1 J                | BDL   | 5 J    | BDL    | 4 J    |
| 2-Hexanone         | 10 UJ            | BDL                | 10 UJ | 10 UJ  | BDL    | BDL    |
| Chlorobenzene      | BDL              | BDL                | BDL   | 2 J    | BDL    | 2 J    |
| Styrene            | 1 J              | 1 J                | BDL   | BDL    | BDL    | BDL    |
| Xylenes (total)    | BDL              | BDL                | BDL   | 3 J    | BDL    | BDL    |
| Total VOCs         | 2                | 2                  | BDL   | 10     | BDL    | 6      |
| TICs               |                  |                    |       |        |        |        |
| Unknowns           | BDL              | BDL                | BDL   | BDL    | BDL    | 9      |
| Total TICs         | BDL              | BDL                | BDL   | BDL    | BDL    | 9      |

Notes:

<sup>a</sup> BDL = Below laboratory method detection limit

<sup>b</sup> UJ = Estimated quantitation limit

<sup>c</sup> J = Estimated concentration value

**TABLE 5-13**  
**SVOC CONCENTRATIONS IN SURFACE WATER SAMPLES**  
**(Results in ppb)**

| SVOC                       | I00S               | I00S-D | K600N | E1600S | A1000S | H1800S           |
|----------------------------|--------------------|--------|-------|--------|--------|------------------|
| 1,4-DCB                    | BDL <sup>a</sup>   | BDL    | BDL   | BDL    | BDL    | 1 J <sup>b</sup> |
| Phenanthrene               | BDL                | BDL    | BDL   | 2 J    | BDL    | BDL              |
| Carbazole                  | BDL                | BDL    | BDL   | BDL    | BDL    | 2 J              |
| Fluoranthene               | BDL                | BDL    | BDL   | 3 J    | BDL    | BDL              |
| Pyrene                     | BDL                | BDL    | BDL   | 2 J    | BDL    | BDL              |
| Benzo(a)anthracene         | BDL                | BDL    | BDL   | 1 J    | BDL    | BDL              |
| Chrysene                   | BDL                | BDL    | BDL   | 2 J    | BDL    | BDL              |
| bis(2-Ethylhexyl)phthalate | 10 UJ <sup>c</sup> | 10 UJ  | 10 UJ | 10 UJ  | 10 UJ  | 10 UJ            |
| Di-n-butyl phthalate       | BDL                | BDL    | BDL   | BDL    | BDL    | 10 UJ            |
| Dimethyl phthalate         | BDL                | 10 UJ  | BDL   | 10 UJ  | BDL    | 10 UJ            |
| Benzo(b)fluoranthene       | BDL                | BDL    | BDL   | 2 J    | BDL    | BDL              |
| Benzo(a)pyrene             | BDL                | BDL    | BDL   | 1 J    | BDL    | BDL              |
| Total SVOCs                | BDL                | BDL    | BDL   | 13     | BDL    | 3                |
| <b>TICs</b>                |                    |        |       |        |        |                  |
| Hydrocarbons               | BDL                | BDL    | 18 J  | 130 J  | 4 J    | 6 J              |
| Oxygenated hydrocarbons    | 11 J               | 41 J   | BDL   | 600 J  | 3 J    | 64 J             |
| Oxygenated aromatics       | BDL                | 2 J    | BDL   | 11 J   | BDL    | 31 J             |
| Heterocyclic aromatics     | 10 J               | 17 J   | 5 J   | BDL    | 3 J    | 41 J             |
| Phosphoric acid esters     | BDL                | 4 J    | BDL   | 12 J   | BDL    | BDL              |
| Sulfonamides               | BDL                | 3 J    | 2 J   | 9 J    | BDL    | 14 J             |
| Amines and amides          | BDL                | BDL    | BDL   | BDL    | 2 J    | 19 J             |
| Total TICs                 | 21                 | 67     | 25    | 762    | 12     | 175              |

Notes:

<sup>a</sup> BDL = Below laboratory method detection limits

<sup>b</sup> J = Estimated concentration value

<sup>c</sup> UJ = Estimated quantitation limit



**TABLE 5-14**  
**METAL CONCENTRATIONS IN SURFACE WATER SAMPLES**  
**(Results in ppb)**

| Metal     | E1600S                  | K600N               | I00            | I00-D          | A1000S          | H1800S         | AWQC            |
|-----------|-------------------------|---------------------|----------------|----------------|-----------------|----------------|-----------------|
| Aluminum  | 7,520                   | 55.7 J <sup>a</sup> | 132 J          | 144 J          | 169 J           | 439            | -- <sup>b</sup> |
| Arsenic   | 16.7                    | 2.0 J               | 2.2 J          | 2.2 J          | 13.2            | 2.2 J          | 190             |
| Barium    | 2,300 J                 | 108 J               | 112 J          | 119 J          | 238 J           | 123 J          | --              |
| Beryllium | 2.4 J                   | BDL <sup>c</sup>    | 1.2 J          | BDL            | 1.2 J           | BDL            | --              |
| Cadmium   | <b>52.6<sup>d</sup></b> | BDL                 | BDL            | BDL            | BDL             | BDL            | 1.1             |
| Calcium   | 290,000 J               | 30,800 J            | 52,800 J       | 53,800 J       | 133,000 J       | 55,300 J       | --              |
| Chromium  | 35.6                    | BDL                 | BDL            | BDL            | BDL             | BDL            | --              |
| Cobalt    | 22.0 J                  | BDL                 | BDL            | BDL            | 4.9 J           | BDL            | --              |
| Copper    | <b>997</b>              | BDL                 | BDL            | BDL            | BDL             | BDL            | 12              |
| Iron      | <b>260,000 J</b>        | <b>2,990 J</b>      | <b>6,370 J</b> | <b>7,300 J</b> | <b>11,600 J</b> | <b>5,020 J</b> | 1,000           |
| Lead      | <b>36.2 J</b>           | 1.2 J               | 3.1 J          | 3.0 J          | <b>5.4 J</b>    | <b>10.2 J</b>  | 3.2             |
| Magnesium | 52,100 J                | 40,600 J            | 24,400 J       | 25,700 J       | 42,500 J        | 24,100 J       | --              |
| Manganese | 2,710 J                 | 61.5 J              | 266 J          | 254 J          | 1,340 J         | 326 J          | --              |
| Mercury   | <b>0.16 J</b>           | BDL                 | BDL            | BDL            | BDL             | BDL            | 0.012           |
| Nickel    | <b>256</b>              | BDL                 | BDL            | BDL            | BDL             | BDL            | 160             |
| Potassium | 18,100 J                | 37,300 J            | 9,000 J        | 10,500 J       | 87,500 J        | 8,390 J        | --              |
| Selenium  | BDL                     | BDL                 | 2.1 J          | BDL            | BDL             | BDL            | 36              |
| Sodium    | 30,400 J                | 72,200 J            | 63,500 J       | 62,800 J       | 190,000 J       | 67,200 J       | --              |
| Vanadium  | 69.3                    | BDL                 | BDL            | BDL            | BDL             | BDL            | --              |
| Zinc      | <b>9,710 J</b>          | BDL                 | BDL            | BDL            | BDL             | BDL            | 110             |
| Cyanide   | BDL                     | BDL                 | <b>13.0 J</b>  | BDL            | <b>37.0 J</b>   | <b>26.4 J</b>  | 5.2             |

Notes:

- <sup>a</sup> J = Estimated concentration limit
- <sup>b</sup> -- = AWQC not assigned to analyte
- <sup>c</sup> BDL = Below laboratory method detection limits
- <sup>d</sup> **Shaded bold values** indicate that concentration exceeds AWQC

**TABLE 5-15**  
**VOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94**  
**(Results in ppb)**

| VOC                | F1400S             | K600N            | I00   | L1200S | L1200S-D | J1400S | TCLP x 20       |
|--------------------|--------------------|------------------|-------|--------|----------|--------|-----------------|
| Chloromethane      | 5 J <sup>a</sup>   | BDL <sup>b</sup> | BDL   | BDL    | BDL      | BDL    | -- <sup>c</sup> |
| Methylene chloride | 22 UJ <sup>d</sup> | 42 UJ            | 15 UJ | 14 UJ  | 17 UJ    | 26 UJ  | --              |
| Acetone            | 190 UJ             | 230 UJ           | 31 UJ | 51 UJ  | 100 UJ   | 190 UJ | --              |
| 2-Butanone         | 42 UJ              | 48 UJ            | BDL   | 14 UJ  | 18 UJ    | 40 UJ  | 4,000,000       |
| Chlorobenzene      | 5 J                | BDL              | BDL   | BDL    | BDL      | BDL    | 2,000,000       |
| Toluene            | BDL                | BDL              | BDL   | 101 J  | 180 J    | BDL    | --              |
| Xylenes (total)    | 5 J                | BDL              | BDL   | BDL    | BDL      | BDL    | --              |
| Total VOCs         | 15                 | 0                | 0     | 101    | 180      | 0      | --              |

Notes:

- a J = Estimated concentration value
- b BDL = Below laboratory method detection limits
- c -- = TCLP limit not assigned to analyte
- d UJ = Estimated quantitation limit

**TABLE 5-16**  
**VOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 09/14/94**  
**(Results in ppb)**

| VOC                        | SED-1  | SED-1-DUP | SED-2 | TCLP x 20       |
|----------------------------|--------|-----------|-------|-----------------|
| Methylene chloride         | 59 UJ  | 43 UJ     | 29 UJ | -- <sup>b</sup> |
| Acetone                    | 150 UJ | 71 UJ     | 69 UJ | --              |
| Benzene                    | 12 J   | BDL       | BDL   | 10,000          |
| Toluene                    | BDL    | BDL       | 5 J   | --              |
| Total VOCs                 | 12     | BDL       | 5     |                 |
| TICs                       |        |           |       |                 |
| Alkylaromatic hydrocarbons | 32 J   | BDL       | BDL   |                 |
| Oxygenated aromatics       | 97 J   | BDL       | BDL   |                 |
| Total TICs                 | 129    | BDL       | BDL   |                 |

Notes:

- <sup>a</sup> UJ = Estimated quantitation limit
- <sup>b</sup> -- = TCLP limit not assigned to analyte
- <sup>c</sup> J = Estimated concentration value
- <sup>d</sup> BDL = Below detection limit

**TABLE 5-17**  
**SVOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94**  
**(Results in ppb)**

| SVOC                           | F1400S            | K600N            | I00      | L1200S   | L1200S-D            | J1400S   | TCLP x 20       |
|--------------------------------|-------------------|------------------|----------|----------|---------------------|----------|-----------------|
| 1,4-DCB                        | 87 J <sup>a</sup> | BDL <sup>b</sup> | BDL      | BDL      | BDL                 | BDL      | 150,000         |
| 4-Methylphenol                 | BDL               | BDL              | BDL      | 290 J    | 380 J               | BDL      | 4,000,000       |
| Naphthalene                    | 83 J              | BDL              | BDL      | BDL      | BDL                 | BDL      | -- <sup>c</sup> |
| 2-Methylnaphthalene            | 100 J             | BDL              | BDL      | BDL      | BDL                 | BDL      | --              |
| Acenaphthylene                 | 150 J             | BDL              | BDL      | 69 J     | 81 J                | BDL      | --              |
| Phenanthrene                   | 800               | BDL              | 650      | 1,200 J  | 1,600 J             | 460 J    | --              |
| Dibenzofuran                   | BDL               | BDL              | BDL      | 50 J     | 68 J                | BDL      | --              |
| Anthracene                     | 300 J             | BDL              | 110 J    | 270 J    | 380 J               | BDL      | --              |
| Carbazole                      | BDL               | BDL              | 95 J     | 120 J    | 140 J               | BDL      | --              |
| Fluoranthene                   | 1,600             | 150 J            | 1,400    | 3,000 J  | 3,200 J             | 1,400    | --              |
| Pyrene                         | 1,800             | BDL              | 1,200    | 2,100 J  | 2,200 J             | 1,300    | --              |
| Butyl benzyl phthalate         | BDL               | BDL              | BDL      | BDL      | 570 UJ <sup>d</sup> | BDL      | --              |
| Benzo(a)anthracene             | 1,900             | BDL              | 800      | 1,600 J  | 1,700 J             | 620 J    | --              |
| Chrysene                       | 1,600             | 140 J            | 980      | 1,600 J  | 1,800 J             | 1,100    | --              |
| Di-n-octyl phthalate           | BDL               | BDL              | BDL      | 460 UJ   | 570 UJ              | BDL      | --              |
| 2-Ethylhexyl phthalate         | 720 UJ            | 1,400 UJ         | 560 UJ   | 1,200 UJ | 1,500 UJ            | 850 UJ   | --              |
| Benzo(b)fluoranthene           | 1,800             | 140 J            | 1,500    | 2,600 J  | 2,400 J             | 1,600    | --              |
| Benzo(a)pyrene                 | 730               | BDL              | 470 J    | 690 J    | 700 J               | 560 J    | --              |
| Indeno(1,2,3-cd)pyrene         | 430 J             | BDL              | 330 J    | 470 J    | 460 J               | 370 J    | --              |
| Total SVOCs                    | 11,380            | 430              | 7,535    | 14,059   | 15,109              | 7,410    |                 |
| TICs                           |                   |                  |          |          |                     |          |                 |
| Hydrocarbons                   | 27,000 J          | 14,000 J         | 13,000 J | 29,000 J | 39,000 J            | 24,000 J |                 |
| Oxygenated hydrocarbons        | 12,000 J          | 2,300 J          | 810 J    | 10,000 J | 3,400 J             | 4,600 J  |                 |
| Cyclic oxygenated hydrocarbons | 38,000 J          | 16,000 J         | 3,400 J  | 16,000 J | 18,000 J            | 25,000 J |                 |
| Oxygenated aromatics           | BDL               | 1,200 J          | BDL      | 2,400 J  | 1,900 J             | BDL      |                 |
| PAHs                           | BDL               | BDL              | 600 J    | BDL      | 2,100 J             | BDL      |                 |
| Heterocyclic aromatics         | BDL               | BDL              | BDL      | BDL      | 2,800 J             | BDL      |                 |
| Total TICs                     | 77,000            | 33,500           | 17,810   | 57,400   | 67,200              | 53,600   |                 |

Notes:

- a J = Estimated concentration value
- b BDL = Below laboratory method detection limits
- c -- = TCLP limit not assigned to analyte
- d UJ = Estimated quantitation limit

**TABLE 5-18**  
**SVOC CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 09/14/94**  
**(Results in ppb)**

| SVOC                       | SED-1              | SED-1-DUP | SED-2               | TCLP x 20       |
|----------------------------|--------------------|-----------|---------------------|-----------------|
| bis(2-ethylhexyl)phthalate | BDL <sup>a</sup>   | BDL       | 930 UJ <sup>b</sup> | -- <sup>c</sup> |
| Total SVOCs                | BDL                | BDL       | BDL                 |                 |
| TICs                       |                    |           |                     |                 |
| Unknowns                   | 910 J <sup>d</sup> | 1,300 J   | 290 J               |                 |
| Total TICs                 | 910 J              | 1,300 J   | 290 J               |                 |

Notes:

- a BDL = Below detection limit
- b UJ = Estimated quantitation limit
- c -- = TCLP limit not assigned to analyte
- d J = Estimated concentration value

**TABLE 5-19**  
**TOTAL METAL CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94**  
**(Results in parts per million [ppm])**

| Metal     | F1400S             | K600N                  | I00              | L1200S  | L1200S-D | J1400S     | TCLP x 20       |
|-----------|--------------------|------------------------|------------------|---------|----------|------------|-----------------|
| Aluminum  | 14,300             | 13,400                 | 7,400            | 4,830   | 4,470    | 14,700     | -- <sup>a</sup> |
| Arsenic   | 11.5               | 11.8                   | 3.4              | 3.6     | 2.7 J    | 6.2        | 100             |
| Barium    | 764                | 575                    | 143              | 78.8    | 75.3     | 204        | 2,000           |
| Beryllium | 1.5 J <sup>b</sup> | 0.65 J                 | 0.42 J           | 0.32 J  | 0.30 J   | 0.77 J     | --              |
| Cadmium   | 13.7               | 16.7                   | 3.5              | 2.6     | 3.3      | 4.2        | 20              |
| Calcium   | 80,600             | 61,900                 | 22,600           | 14,200  | 13,100   | 23,100     | --              |
| Chromium  | 65.2               | <b>329<sup>c</sup></b> | 76.2             | 42.3    | 51.2     | 59.3       | 100             |
| Cobalt    | 16.8 J             | 13.7 J                 | 7.5 J            | 4.9 J   | 4.7 J    | 14.1 J     | --              |
| Copper    | 189                | 525                    | 104              | 56.6    | 60.5     | 86.4       | --              |
| Iron      | 194,000            | 27,500                 | 15,200           | 14,500  | 12,300   | 37,300     | --              |
| Lead      | <b>176</b>         | <b>463</b>             | 60.6             | 51      | 37.6     | <b>113</b> | 100             |
| Magnesium | 15,500             | 9,410                  | 6,540            | 4,990   | 4,140    | 10,700     | --              |
| Manganese | 2,260              | 724                    | 449              | 407     | 335      | 1300       | --              |
| Mercury   | 0.84               | 0.18 J                 | BDL <sup>d</sup> | BDL     | BDL      | BDL        | 4               |
| Nickel    | 54.9               | 90.3                   | 34.3             | BDL     | BDL      | BDL        | --              |
| Potassium | 2,260 J            | 1,700 J                | 897 J            | 564 J   | 545 J    | 1,500 J    | --              |
| Selenium  | 1.6 J              | BDL                    | BDL              | BDL     | BDL      | BDL        | 20              |
| Silver    | BDL                | 20.9                   | 4.8              | 2.8 J   | 2.3 J    | BDL        | 100             |
| Sodium    | 2,970 J            | BDL                    | 836 J            | 1,150 J | 705 J    | BDL        | --              |
| Vanadium  | 59.9               | 30.1                   | 27.8             | 19.9    | 18       | 56.3       | --              |
| Zinc      | 1,130              | 1,220                  | 261              | 161     | 143      | 336        | --              |

Notes:

- <sup>a</sup> -- = TCLP limit not assigned to analyte
- <sup>b</sup> J = Estimated concentration value
- <sup>c</sup> **Shaded bold values** indicate that concentration exceeds TCLP x 20
- <sup>d</sup> BDL = Below laboratory method detection limits

**TABLE 5-20**  
**TOTAL METAL CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 09/14/94**  
**(Results in ppm)**

| Metal     | SED-1                     | SED-1-DUP           | SED-2         | TCLP x 20       |
|-----------|---------------------------|---------------------|---------------|-----------------|
| Aluminum  | 18,500                    | 22,800              | 18,900        | -- <sup>a</sup> |
| Antimony  | BDL <sup>b</sup>          | 51.9 J <sup>c</sup> | 21.0 J        | --              |
| Arsenic   | 12.6                      | 14.4                | 8.9           | 100             |
| Barium    | 895                       | 1,040               | 728           | 2,000           |
| Beryllium | 1.4 UJ <sup>d</sup>       | 1.2 UJ              | 1.1 UJ        | --              |
| Cadmium   | <b>43.7 J<sup>e</sup></b> | <b>43.2 J</b>       | <b>77.6 J</b> | 20              |
| Calcium   | 106,000                   | 107,000             | 118,000       | --              |
| Chromium  | <b>479</b>                | <b>532</b>          | <b>832</b>    | 100             |
| Cobalt    | 19.2 J                    | 19.0 J              | 56.8          | --              |
| Copper    | 942                       | 1,070               | 1,430         | --              |
| Iron      | 48,700                    | 40,000              | 32,300        | --              |
| Lead      | <b>704 J</b>              | <b>861 J</b>        | <b>596 J</b>  | 100             |
| Magnesium | 12,700                    | 14,500              | 9,340         | --              |
| Manganese | 1,160                     | 971                 | 696           | --              |
| Mercury   | 0.36 J                    | 0.32 J              | 0.78 J        | 4               |
| Nickel    | 200                       | 180                 | 255           | --              |
| Potassium | 5,450 J                   | 4,510               | 2,970         | --              |
| Selenium  | 5.7 UJ                    | 3.6 UJ              | 2.6 UJ        | 20              |
| Silver    | 37.7                      | 43.6                | 45.2          | 100             |
| Sodium    | 1,940 J                   | 1,710 J             | 1,100 J       | --              |
| Vanadium  | 49.1 J                    | 58.3                | 40.8          | --              |
| Zinc      | 1,850                     | 2,140               | 2,030         | --              |
| Cyanide   | 0.72 J                    | BDL                 | 0.36 J        | --              |

Notes:

<sup>a</sup> -- = TCLP limit not assigned to analyte

<sup>b</sup> BDL = Below detection limit

<sup>c</sup> J = Estimated concentration value

<sup>d</sup> UJ = Estimated quantitation limit

<sup>e</sup> **Shaded bold values** indicate that concentration exceeds TCLP x 20

**TABLE 5-21**  
**PESTICIDE CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 5/5/94**  
**(Results in ppb)**

| Pesticide       | F1400S | I00                | J1400S           | K600N | L1200S | L1200S-D |
|-----------------|--------|--------------------|------------------|-------|--------|----------|
| 4,4'-DDE        | 23     | 4.8 J <sup>a</sup> | BDL <sup>b</sup> | BDL   | 2.8 J  | 5.7 J    |
| 4,4'-DDT        | 45 J   | BDL                | BDL              | BDL   | BDL    | BDL      |
| 4,4'-DDD        | 13     | 3.1 J              | BDL              | 9.6 J | BDL    | BDL      |
| Aldrin          | BDL    | BDL                | BDL              | 4.8 J | BDL    | BDL      |
| Gamma chlordane | BDL    | BDL                | 2.5 J            | BDL   | 1.8 J  | 3.6 J    |

Notes:

<sup>a</sup> J = Estimated concentration value

<sup>b</sup> BDL = Below laboratory method detection limits



**TABLE 5-22**

**PCB CONCENTRATIONS IN SEDIMENT SAMPLES COLLECTED 09/14/94  
(Results in ppb)**

| PCB          | SED-1              | SED-1-DUP | SED-2            |
|--------------|--------------------|-----------|------------------|
| Aroclor-1248 | 220 J <sup>a</sup> | 270 J     | BDL <sup>b</sup> |
| Aroclor-1254 | 240 J              | BDL       | BDL              |

Notes:

<sup>a</sup> J = Estimated concentration value

<sup>b</sup> BDL = Below detection limit

---

TABLE 5-23

**VOC CONCENTRATIONS IN TRENCH SOIL SAMPLES**  
**(Results in ppb)**

| VOC                        | T2-1               | T2-1-DUP         | T3-1             | TCLP x 20       |
|----------------------------|--------------------|------------------|------------------|-----------------|
| Methylene chloride         | 12 UJ <sup>a</sup> | 13 UJ            | BDL <sup>b</sup> | -- <sup>c</sup> |
| Acetone                    | 40 UJ              | 54 UJ            | 35 UJ            | --              |
| Toluene                    | BDL                | 2 J <sup>d</sup> | BDL              | --              |
| Chlorobenzene              | 19                 | 20               | BDL              | 2,000           |
| Ethylbenzene               | 7 J                | 9 J              | BDL              | --              |
| Xylenes (Total)            | 26                 | 17               | BDL              | --              |
| Total VOCs                 | 52                 | 48               | BDL              |                 |
| TICs                       |                    |                  |                  |                 |
| Hydrocarbons               | 40 J               | 870 J            | BDL              |                 |
| Oxygenated hydrocarbons    | 45 J               | BDL              | BDL              |                 |
| Alkylaromatic hydrocarbons | 268 J              | 410 J            | 86 J             |                 |
| Halogenated aromatics      | 99 J               | 50 J             | 5 J              |                 |
| Oxygenated aromatics       | BDL                | BDL              | BDL              |                 |
| Unknowns                   | 95 J               | 670 J            | 134 J            |                 |
| Total TICs                 | 547 J              | 2000 J           | 225 J            |                 |

## Notes:

- <sup>a</sup> UJ = Estimated quantitation limit  
<sup>b</sup> BDL = Below detection limit  
<sup>c</sup> -- = TCLP limit not assigned to analyte  
<sup>d</sup> J = Estimated concentration value

TABLE 5-24

**SVOC CONCENTRATIONS IN TRENCH SOIL SAMPLES**  
(Results in ppb)

| SVOC                              | T2-1                     | T2-1-DUP     | T3-1             | TCLP x 20       |
|-----------------------------------|--------------------------|--------------|------------------|-----------------|
| 1,4-Dichlorobenzene               | <b>160 J<sup>b</sup></b> | <b>220 J</b> | BDL <sup>c</sup> | 150             |
| Naphthalene                       | 69 J                     | BDL          | BDL              | -- <sup>d</sup> |
| 2-Methylnaphthalene               | 64 J                     | 140 J        | BDL              | --              |
| Acenaphthene                      | BDL                      | 76 J         | BDL              | --              |
| Diethylphthalate                  | 410 UJ <sup>e</sup>      | BDL          | 420 UJ           | --              |
| Fluorene                          | BDL                      | 72 J         | BDL              | --              |
| N-nitrosodiphenylamine            | 120 J                    | 380 J        | BDL              | --              |
| Phenanthrene                      | BDL                      | 520 J        | 110 J            | --              |
| Anthracene                        | BDL                      | 100 J        | BDL              | --              |
| Di-n-butylphthalate               | 410 UJ                   | 440 UJ       | 420 UJ           | --              |
| Fluoranthene                      | BDL                      | 380 J        | 160 J            | --              |
| Pyrene                            | BDL                      | 830 J        | 140 J            | --              |
| Butylbenzylphthalate              | 410 UJ                   | 440 UJ       | 420 UJ           | --              |
| Chrysene                          | BDL                      | 320 J        | 74 J             | --              |
| bis(2-ethylhexyl)phthalate        | 1700 UJ                  | 920 UJ       | 720 UJ           | --              |
| Di-n-octylphthalate               | 410 UJ                   | BDL          | BDL              | --              |
| Benzo(b)fluoranthene              | BDL                      | BDL          | 100 J            | --              |
| Benzo(a)pyrene                    | BDL                      | BDL          | 63 J             | --              |
| Total SVOCs                       | 413                      | 3038         | 647              |                 |
| TICs                              |                          |              |                  |                 |
| Hydrocarbons                      | 21,440 J                 | 81,630 J     | 9,240 J          |                 |
| Oxygenated hydrocarbons           | 30,250 J                 | BDL          | 3,620 J          |                 |
| Oxygenated aromatics              | 67,000 J                 | BDL          | BDL              |                 |
| Polynuclear aromatic hydrocarbons | 1,700 J                  | BDL          | 330 J            |                 |
| Amines/Amides                     | BDL                      | BDL          | 840 J            |                 |
| Unknowns                          | 20,410 J                 | 29,880 J     | 2,220 J          |                 |
| Total TICs                        | 140,800 J                | 111,510 J    | 16,250 J         |                 |

## Notes:

- <sup>a</sup> Shaded bold values indicate that concentration exceeds TCLP x 20  
<sup>b</sup> J = Estimated concentration value  
<sup>c</sup> BDL = Below detection limit  
<sup>d</sup> -- = TCLP limit not assigned to analyte  
<sup>e</sup> UJ = Estimated quantitation limit

TABLE 5-25

**METAL CONCENTRATIONS IN TRENCH SOIL SAMPLES**  
(Results in ppm)

| Metal     | T2-1                 | T2-1-DUP | T3-1                      | TCLP x 20       |
|-----------|----------------------|----------|---------------------------|-----------------|
| Aluminum  | 6,540                | 5,340    | 17,000                    | -- <sup>a</sup> |
| Antimony  | 13.5 UJ <sup>b</sup> | 12.3 UJ  | 17.0 UJ                   | --              |
| Arsenic   | 4.7                  | 2.4 J    | 2.7                       | 100             |
| Barium    | 112                  | 99.2     | 520                       | 2,000           |
| Beryllium | 0.50 UJ              | 0.43 UJ  | 0.89 UJ                   | --              |
| Cadmium   | 2.3 UJ               | 2.4 UJ   | <b>25.4 J<sup>c</sup></b> | 20              |
| Calcium   | 14,900               | 31,300   | 100,000                   | --              |
| Chromium  | 39.1                 | 55.9     | <b>816</b>                | 100             |
| Cobalt    | 7.0 J                | 5.7 J    | 11.1 J                    | --              |
| Copper    | 422                  | 146      | 764                       | --              |
| Iron      | 18,200               | 32,000   | 37,900                    | --              |
| Lead      | 81.4 J               | 100 J    | <b>506 J</b>              | 100             |
| Magnesium | 5,130                | 12,600   | 8,150                     | --              |
| Manganese | 415 J                | 565 J    | 498 J                     | --              |
| Mercury   | 0.34 J               | 0.36 J   | 0.22 J                    | 4               |
| Nickel    | 33.9 J               | 62.3 J   | 215 J                     | --              |
| Potassium | 1,060 J              | 4,030 UJ | 804 UJ                    | --              |
| Selenium  | 0.82 J               | 0.53 UJ  | 1.8                       | 20              |
| Silver    | 9.8 J                | 30.3 J   | 26.5 J                    | 100             |
| Sodium    | 343 J                | 400 J    | 646 J                     | --              |
| Vanadium  | 21.6                 | 20.9     | 32.2                      | --              |
| Zinc      | 393                  | 321      | 1410                      | --              |
| Cyanide   | 0.31 UJ              | 0.17 UJ  | 0.32 J                    | --              |

## Notes:

<sup>a</sup> -- = TCLP limit no assigned for analyte<sup>b</sup> UJ = Estimated quantitation limit<sup>c</sup> J = Estimated concentration value<sup>d</sup> Shaded bold values indicate that concentration exceeds TCLP x 20

**TABLE 5-26**

**PCB CONCENTRATIONS IN TRENCH SOIL SAMPLES  
(Results in ppb)**

| PCB          | T2-1               | T2-1-DUP | T3-1  |
|--------------|--------------------|----------|-------|
| Aroclor-1016 | BDL <sup>b</sup>   | BDL      | 310   |
| Aroclor-1254 | 110 J <sup>a</sup> | BDL      | 210   |
| Aroclor-1260 | BDL                | BDL      | 180 J |

Notes:

<sup>a</sup> J = Estimated concentration value

<sup>b</sup> BDL = Below detection limit

---

## 6.0 CONCLUSIONS AND RECOMMENDATIONS

Results of analytical data for groundwater, surface water, and sediments samples collected at the Pig's Eye site indicate that a significant impact to the environment has occurred from the Pig's Eye site. The presence of organic and inorganic contaminants in on-site groundwater indicate that contaminants from the fill material are traveling through the upper water-bearing unit. The lower water-bearing unit below the organic silt and peat unit has also been impacted by contaminants from the fill material. The lack of a confining layer between the fill material and bedrock indicates that the underlying Prairie du Chien-Jordan Aquifer is highly vulnerable to contamination.

The extent of organic and inorganic contaminants in sediments from Battle Creek and Pig's Eye Lake indicate that significant impact to these water bodies has occurred from the Pig's Eye site. Elevated concentrations of pesticides such as 4,4-DDT and 4,4-DDD and metals such as lead and chromium pose a serious ecological and human health risk. Elevated concentrations of contaminants are particularly high near the battery casing disposal area at the south end of the site near Pig's Eye Lake.

On- and off-site surface water has also been impacted by past waste management operations at the site. The most contaminated area is near the battery casing disposal area, where elevated concentrations of metals are present in a pond connected to Pig's Eye Lake. Numerous leachate seeps also drain into Battle Creek, the unnamed ditch east of the site, and Pig's Eye Lake.

In order to further characterize site conditions, PRC recommends the following activities for additional study at the Pig's Eye site:

- Additional monitoring wells should be installed in the deeper unconsolidated valley fill deposits underlying the site. If groundwater from these wells also shows contamination, installation of bedrock monitoring wells at the site should be considered.
- Groundwater samples from the monitoring wells should also be analyzed for oxygen, nitrates, and sulfates to determine whether or not natural bioremediation is occurring at the site.
- Monitoring well nests should be installed in the shallow and deeper water-bearing units to determine if the organic silt and peat unit acts as a semiconfining or confining unit at the site.

- Seismic or other nonintrusive geophysical survey methods, such as a gravity survey, should be performed to locate the axis of the buried valley.
- TCLP analysis of the ash from the ash disposal area and soil and sediment near the battery casings disposal area should be performed to determine if the materials are Resource Conservation and Recovery Act (RCRA) hazardous wastes. If TCLP analysis indicates that this material is above TCLP limits for RCRA hazardous waste, the soil, battery casings, and ash should either be removed or remediated.
- Invertebrate sampling and additional sediment sampling in Battle Creek and Pig's Eye Lake should be conducted in order to assess potential impact of the site on the food chain in the area.

## 7.0 REFERENCES

- Bureau of Census. 1990. Summary of Population and Housing Characteristics for Minnesota.
- Kanivetsky, Roman and Jane M. Cleland. 1992. *Geologic Atlas of Ramsey County, Minnesota*. Surficial Hydrogeology, Plate 6. County Atlas Series C-7. ed. by Gary N. Meyer and Lynn Swanson.
- Minnesota Department of Health. 1991. Recommended Allowable Limits for Drinking Water Contaminants, Release No. 3.
- Minnesota Pollution Control Agency (MPCA). 1989. Screening Site Investigation of the Pig's Eye Site. October 11.
- MPCA. 1992. Expanded Site Investigation of the Pig's Eye Site. December 11.
- Mossler, John H. 1987. *Paleozoic Lithostratigraphic Nomenclature for Minnesota*. Minnesota Geological Survey, Report of Investigations 36. 36 Pages.
- Mossler, John H. 1992. *Geologic Atlas of Ramsey County, Minnesota*. Bedrock Topography Map, Plate 4. County Atlas Series C-7. Edited by Gary N. Meyer and Lynn Swanson.
- Mossler, John H. and Bruce A. Bloomgren. 1992. *Geologic Atlas of Ramsey County, Minnesota*. Bedrock Geology, Plate 2. County Atlas Series C-7. Edited by Gary N. Meyer and Lynn Swanson.
- Mossler, John H. and Jane M. Cleland. 1992. *Geologic Atlas of Ramsey County, Minnesota*. Depth to Bedrock Maps and Confining Units of the St. Peter Sandstone, Plate 5. County Atlas Series C-7. Edited by Gary N. Meyer and Lynn Swanson.
- Patterson, Carrie J. 1992. *Geologic Atlas of Ramsey County, Minnesota*. Surficial Geology, Plate 3. County Atlas Series C-7. Edited by Gary N. Meyer and Lynn Swanson.
- U.S. Department of Agriculture (USDA). 1980. *Soil Survey of Washington and Ramsey Counties, Minnesota*. Soil Conservation Service.
- U.S. Environmental Protection Agency (EPA). 1981. Notification of Hazardous Waste Form, Submitted by Unknown Waste Hauler. Exact Date Unknown.
- EPA. 1983. Preliminary Assessment of the Pig's Eye dump site. Performed by Ecology and Environment. Exact Date Unknown.
- EPA. 1988. Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA. Office of Emergency and Remedial Response.
- EPA. 1992. Quality Criteria for Water.